



**DEPARTMENT OF BUILDING
UNIVERSITI TEKNOLOGI MARA
(PERAK)**

**MANAGEMENT AND SUPERVISING OF MECHANICAL AND
ELECTRICAL WORK AT PHASE 2 THE HAVRE BUKIT JALIL**

**Prepared by:
AZAD BUKHARI BIN AZIZ
2016458536**

**DEPARTMENT OF BUILDING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA
(PERAK)
DECEMBER 2018**

By

**AZAD BUKHARI BIN AZIZ
2016458536**

entitled

**MANAGEMENT AND SUPERVISING WORK OF MECHANICAL AND
ELECTRICAL WORK AT PHASE 2 THE HAVRE BUKIT JALIL**

accepted in partial fulfillment of requirement has for obtaining Diploma In Building.

Report Supervisor : Ms. Nor Azizah Talkis.

Practical Training Coordinator : Mr. Muhammad Naim bin Mahyuddin

Programme Coordinator : Dr. Dzulkarnaen bin Ismail

**DEPARTMENT OF BUILDING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA
(PERAK)**

DECEMBER 2018

STUDENT'S DECLARATION

I hereby declare that this report is my own work, except for extract and summaries for which the original references stated herein, prepared during a practical training session that I underwent at Kenwingston Sdn. Bhd for duration of 14 weeks starting from 3 September 2018 and ended on 9 December 2018. It is submitted as one of the prerequisite requirements of DBG307 and accepted as a partial fulfillment of the requirements for obtaining the Diploma in Building.

Name: Azad Bukhari bin Aziz

UiTM ID No: 2016458536

Date: 18 December 2018

ACKNOWLEDGEMENT

First of all, I am grateful to my supervising lecturer Ms. Azizah Talkis for giving me an opportunity and guiding me to complete the internship program for three months starting from September to December 2018.

I am really grateful to Kenwingston Sdn. Bhd. For giving me an opportunity and successfully arranging the internship program to me. I also thank to Ms. Koh from Kenwingston human resources department for recruit me as a trainee in this grateful company.

I would like to thanks to my Project Director Mr. Lew Kok Sin for treating like a staff during the internship and teach me to be an extraordinary employer. The way he treats their staff every day is the same way he treats me every day.

I also thanks to my Project Manager Mr. Fakhrudin for teach me how to settle the problem in using a big machinery on site during peak hour.

In my internship here, I was mentored by two persons which is my Assistant Mechanical and Electrical Manager Mr. Muhamad Najmi as my department manager also teach me in handling the big task on site. Next, I want to thank to my mechanical and electrical supervisor Mr. Hamidi Saiful Haq for teaching me in handling six sub-contractor under my department and show me the routine of our department every day. I feel really lucky to be able to work under their direction.

Another thanks to Mr. Koo from architect and operation department for teaching me the standard operation procedure in their area in charge. This will be the great knowledge I have got during my internship because I learn scope of work of two departments. This will help me in improving my knowledge in other work.

I also take this opportunity to express a deep sense of gratitude to all the employees of Kenwingston Sdn. Bhd. For presenting me such amazing experience. They are all really wonderful people, and I will never forget these days of mine at Kenwingston.

ABSTRACT

Supervising and management is the important planning work on site, therefore this report will discuss about the supervising and management of mechanical and electrical work which is plumbing work, electrical work, ventilation work, firefighting work, and elevation work at Phase Two the Havre Bukit Jalil. As a main contractor, the mechanical and electrical work on site is too many and need a good planning to conduct the work. There are different work and material with different contractor doing the different work. The objective of this report is to carry out the sub-contractor outstanding work which are not completed yet. Second is to ensure the sub-contractors follow the standard operating procedure based on the flow of a residences project. Third, to solve their problem during the progress or installing work. Forth, is to inspect their completed work and report for reinstall if necessary. In conclusion, this report will describe the way to supervise the mechanical and electrical work progress on-site.

CONTENTS	PAGE NO
Acknowledgements	i
Abstract	ii
Contents	iii
List of Tables	iv
List of Figures	v
CHAPTER 1.0 INTRODUCTION	1
1.1 Background and Scope of Study	1
1.2 Objectives	2
1.3 Methods of Study	3
CHAPTER 2.0 COMPANY BACKGROUND	4
2.1 Introduction of Company	4
2.2 Company Profile	5
2.3 Organization Chart	6
2.4 List of Project	8
2.4.1 Completed Projects	8
2.4.2 Project in Progress	8
CHAPTER 3.0 CASE STUDY	9
3.1 Introduction to Case Study	9
3.2 Supervising of mechanical and electrical work	15
3.3 Management of sub-contractor's issue	26
CHAPTER 4.0 CONCLUSION	30
4.1 Conclusion	30
REFERENCES	31
APPENDICES	32

LIST OF TABLES

		PAGE NO
Table 2.1:	List of Completed Project	8
Table 2.2:	List of On Going Project	8
Table 3.1:	Scope of Works	11
Table 3.3.1:	material inspection list	14
Table 3.3.2:	Piping work and appliances	15
Table 3.2.3:	Electrical work and related	19
Table 3.2.3:	Method study for another work	23
Table 3.3.1:	Method for manage the problems	26

LIST OF FIGURE

		PAGE NO
Figure 2.1:	Kenwingston Sdn. Bhd.	5
Figure 2.2:	The Chart Department of Mechanical and Electrical	7
Figure 3.1:	The Signboard of Site Project	9
Figure 3.2:	Sky Garden	10
Figure 3.3:	Podium Ramp	10
Figure 3.4:	house unit	11
Figure 3.5:	Lift motor room	11
Figure 3.6:	Cold water point	15
Figure 3.7:	Cold water point	15
Figure 3.8:	water closet	15
Figure 3.9:	floor trap	15
Figure 3.10:	opening ceiling	16
Figure 3.11:	Exhaust fan	16
Figure 3.12:	floor pipe opening	16
Figure 3.13:	installing pipe	17
Figure 3.14:	corridor floor trap and rain water down pipe	17
Figure 3.15:	locating dome	17
Figure 3.16:	transfer water tank	18
Figure 3.17:	install water tank	18
Figure 3.18:	pressure test	18
Figure 3.19:	flow test	19
Figure 3.20:	television socket	19
Figure 3.21:	plug point installation	19
Figure 3.22:	cable connector	20
Figure 3.23:	pressure test	20
Figure 3.24:	alarm bell	20
Figure 3.25:	TNB pressure inspection	21
Figure 3.26:	Megger test	22
Figure 3.27:	continuity test	22
Figure 3.28:	paint defect	23
Figure 3.29:	correct water point	23

Figure 3.30:	Lift Motor Room	23
Figure 3.31:	Button and Car top	23
Figure 3.32:	exhaust fan for stairs	24
Figure 3.33:	Valve for air pressure	24
Figure 3.34:	transfer water tank	24
Figure 3.35:	condition before	24
Figure 3.36:	condition after	25
Figure 3.37:	after housekeeping	25
Figure 3.38:	slab before concreting	25
Figure 3.39:	column to install conduit	25
Figure 3.40:	cold water point	26
Figure 3.41:	cold water point	26
Figure 3.42:	yard skirting tiles	26
Figure 3.43:	floor trap	27
Figure 3.44:	water closet	27
Figure 3.45:	ceiling opening	27
Figure 3.46:	wall break	27
Figure 3.47:	mistake cutting position	27
Figure 3.48:	yard pipe	28
Figure 3.49:	yard pipe	28
Figure 3.51:	leaking wall	28
Figure 3.52:	leaking wall	28
Figure 3.53:	condition before	29
Figure 3.54:	condition after	29
Figure 3.55:	condition after	29

LIST OF APPENDIX

	PAGE NO
Appendix 1: Master plan level 40	32
Appendix 2: Floor plan Phase 2 Block A and Block B Units	32
Appendix 3: Floor plan Phase 2 Block A and Block B Podium	32

CHAPTER 1.0

INTRODUCTION

1.0 Background and Scope of Study

This study focuses on management and supervising of mechanical electrical work in high rise building type of residences. The process of managing work will be focus for this research. For the information, this work will be seen along the construction progress. Starting before concreting work until the finishing work is done. The scope of study for this report is to understand then method of supervising of mechanical and electrical work according to the Uniform Building by Law.

Management and supervising work of mechanical and electrical work of The Havre Bukit Jalil. The project worth of RM 357, 500, 000.00 is starting from 2nd May 2017 until 4 March 2019. In addition, this study aims to describe the mechanical work which need to inspect on site. The problems that occurred during the installation. This study involve the planning and management skill to control the sub-contractor and their issues to run the project properly with minimize the problems

1.2 Aim

To study the management and supervising of mechanical and electrical work at Phase 2 The Havre Bukit Jalil

1.3 Objective

This report is developed based on a few objectives. The objectives are as follow:

1. To investigate the sub-contractor outstanding. The main contractor has given the schedule for their reference and target to complete the work.
2. To inspect their problem during the progress when the work is collided with different party.
3. To inspect their completed work during the progress time for reinstall if necessary.

1.4 Method of Study

The research of case study about supervising work of the building has been carried out by using all of these methods.

1.4.1 Primary

1. Observation

The method of identifying problems is observing the sub-contractor's outstanding around the site area. Walking around the site area such as sub-con's store, their workplace and their material. The inspection will be more accurate if we know the material belongs to who and the inspection done twice.

2. Interviews

The interview has been carried out with a supervisor (m&e) of the company and sub-contractors. There are lot of information will get in the meeting helping to solve the problem

1.4.2 Secondary

3. Internet

Internet is a faster and easier way to collect data and knowledge to support the deficiency of data

4. Books

Books also can be referred to obtain knowledge and understanding of the operating system for the supervisor

CHAPTER 2.0

COMPANY BACKGROUND

2.1 Introduction of Company

Kenwingston Sdn. Bhd. is a private sector of construction in Malaysia. Established in September 2015 operates as contractor in construction field of private sector.

2.1.1 Organization structure

Kenwingston Sdn. Bhd. led by a Managing Director Dato' Lovis Lam Kong Tang. The headquarters of the organization is in Jalan Wangsa Delima 6, Pusat Bandar Wangsa Maju (KLSC), Seksyen 5, Wangsa Maju, 53300 Kuala Lumpur. And their projects are located in many state around Kuala Lumpur and Selangor.

Kenwingston was led by seven director below the Managing Director. Every director leads every project with their supporting staff to ensure the projects complete on time. They has a profession in finishing work quality make them got one of the best quality workmanship contractor.

2.1.2 Kenwingston Sdn. Bhd. Strategic Plan

Kenwingston has decided to move from construction to development. It is because the construction is their expert and they want to give more with development to build more quality product to achieve higher level of customer satisfaction.

Since the year 2018, kenwingston is the property developer and the construction is the main area of business. The first develop project is services apartment at Sg. Besi. Since they become a developer, they can bring the luxuries characteristic in their idea to fulfill the needs of customer in Kuala Lumpur property.

Previously, they take a project with a client Aset Kayamas as a selective tender. Their first project is at Parkhill Bukit Jalil. Then Kenwingston take an advantage to continue the contract with the same client at The Havre Bukit Jalil.

2.2 Company Profile



Figure 2.1 Kenwingston Sdn. Bhd.

Source: google images/kenwingston

Address	: No. 82 Jalan Wangsa Delima 6, Pusat Bandar Wangsa Maju (KLSC), Seksyen 5, Wangsa Maju, 53300 Kuala Lumpur.
CIDB registration	: 0120120912 – WP145307
Telephone no.	:
Fax	:
Email	: Kenwingston.my@gmail.com

2.3.1 Organization Chart




Figure 2.3 The Organization Chart of The Hayre Kenwingston Contract department

2.3.2 Organization chart for Mechanical and Electrical Department




Figure 2.4 The Chart Department of Mechanical and Electrical
Source: Contract Department Kenwingston

2.4 List of Project

2.4.1 Completed Project

Table 2.1: List of Completed Project

No	Project title	Building type	Address	Contract price
1	The Wharf Residence	Serviced Apartment	Puchong, Selangor	RM69 million
2	De Centrum	Mix Development	Sepang, Selangor	RM80 million
3	Almyra Residence	Mix Development	Bangi, Selangor	RM24 million
4	Season garden	Serviced Apartment	Wangsa Maju, Kuala Lumpur	RM60 million
5	Conexion	Apartment	Sepang, Selangor	RM 87 million

2.4.2 On Going Project

Table 2.2: List of On Going Project

No	Project title	Building type	Address	Contract price
1	The Havre	Serviced Apartment	Bukit Jalil	RM 357 million
2	Square Garden	Serviced Apartment	Cyberjaya, Selangor	RM 295 million
3	De Centrum	Serviced Apartment	Sungai Besi, Kuala Lumpur	RM 135 million
4	Season garden	Serviced Apartment	Sri Hartamas, Kuala Lumpur	RM 150 million

CHAPTER 3.0

Introduction to Case Study

3.1 Introduction of Project

The construction project of private on 'Cadangan Pembinaan 2102 Unit Yang Mengandung Fasa 1: 2 Blok Pangsapuri Mampu Milik dan Fasa 2: 2 Blok Pangsapuri di Daerah Bukit Jalil. A case study of management and supervising of mechanical and electrical work.

This project lead by Kenwingston Sdn Bhd as main contractor for the Sinerjuta Sdn Bhd as their client with the contract number. The project date of possession is on 2 May 2017 duration. The contract price of this project is RM 357, 500, 000.00. Mechanical and electrical is Jurutera Perunding WTA Sdn Bhd and the nominated sub-contractor (M&E) is Kejuruteraan Asastera Berhad, Kok Wee Sdn Bhd, Boon Wah Engineering, KMChia Sdn Bhd, Sigma Elevator Malaysia and Commutech Sdn Bhd.





Figure 3.1 The Signboard of Site Project

Source: Site Project

3.1.1 Scope of Works

Table 3.1 Scope of Works

No.	Scope of Works
1.	<p data-bbox="300 405 472 434">Fitting works</p> <p data-bbox="300 506 472 535">1. Sky Garden</p> <p data-bbox="300 555 1206 640">The level 40 floor that have public toilet, planter box, water tanks, and hall that has many facilities here</p>  <p data-bbox="619 1117 916 1146">Figure 3.2 Sky Garden</p> <p data-bbox="563 1167 971 1196">Source: Sky garden site project</p> <p data-bbox="300 1272 520 1301">2. Driveway/ramp</p> <p data-bbox="300 1321 1197 1406">The place where the pipe for electric cable, manhole and sanitary waste is located. The ramp is from Phase 2 block A to Block B</p>  <p data-bbox="608 1863 933 1892">Figure 3.3 Podium Ramp</p>

Source: Podium site project

3. House unit

The unit has to check the fitting and electrical work. One block has 35 floor and every floor has 15 unit.



Figure 3.4 house unit

Source: house unit site project

4. Lift Motor Room

The machine that hold lift car. One block has six nos of lift. Located at level 43 from ground.



Figure 3.5 Lift motor room

Source: lift motor room site project

1.2 Location of Project

‘Cadangan Pembinaan 2102 Unit Yang Mengandung Fasa 1: 2 Blok Pangsapuri Mampu Milik dan Fasa 2: 2 Blok Pangsapuri di Daerah Bukit Jalil is a two type of building that provide a shelter for people in Bukit Jalil and surrounding. With the low cost type of residences provide by government which is ‘rumawip’ may help those people with less amount of salary to have a house with safe and comfort place while the luxury condominium one provide many facilities to fulfill the needs of the rich.

The location of the site project is 4.1km or 6 minutes from ‘Stadium Bukit Jalil’ near to the residential area and ‘Lebuhraya Bukit Jalil’. Thus the acces road has two which is from the residential area and “Lebuhraya Bukit Jalil’. The two access road may ease the supplier to send the material through small road and highway.



Figure 3.6 The Location of Site project

Source: Google Map Satellite

3.1.3 Case Study

This project using the 'Jurutera Perunding WTA sdn bhd' for the mechanical plan in the building and the services of nominated sub-contractor for mechanical and electrical work. With six sub-contractor, all the services are done by them except the material provide by main contractor.

The sub-contractor of elevator, electrical, firefighting, and mechanical ventilation, use one company each but the piping work use two different company. This is the best strategy taken by main-contractor to prevent from lack of work progress and lack of material supply. Because of the fitting work in this type of building is many.

The element such as rain water down pipe, sanitary appliances, and fitting provide by one company and the rest by another one company. The quality is inspected by architect teams from the main contractor three times before the clerk of work from the client inspected. The quality is very important in keep the price of the unit worth.

3.1.4 Complete Material Inspection

The following checks and activities shall be carried out during the supervising works.



Table 3.3.1 material inspection list




No.	Work
1	<p>Piping work</p> <ol style="list-style-type: none">1) Cold water point2) Sanitary ware and floor trap3) Sanitary fitting4) Balcony rain pipe5) Yard pipe6) Rain water pipe and dome7) Water tank installation8) Clerk of work inspection<ol style="list-style-type: none">I. Pressure testII. Flow test
2	<p>Electrical work</p> <ol style="list-style-type: none">1) Switches2) Cable connector3) Distribution board4) Firefighting5) Clerk of work inspection<ol style="list-style-type: none">I. Meggar testII. Fiber optic test
3	<p>Another work</p> <ol style="list-style-type: none">1) Quality installation (piping and electrical)2) Lift inspection3) Mechanical ventilation4) Broken material




3.2 The supervising of mechanical and electrical work




3.2.1 The piping work


Table 3.3.2 Piping work and appliances

NO	WORK	DIAGRAM
1	<p>Cold water point</p> <ul style="list-style-type: none"> • The cold water is not allowed to install over the wall tile level like the Figure • Also when the cap is sink in the wall tile level • It must be in same level like third Figure 	 <p>Figure 3.7 Cold water point</p>
2	<p>Sanitary ware and floor trap</p> <ul style="list-style-type: none"> • Related for units • The water closet and basin must have a layer of protection • To keep the quality of material and thrusworthy of customer • Floor trap must be closed to prevent cement and trash turn inside 	 <p>Figure 3.8 water closet</p> <p>Figure 3.9 floor trap</p>



<p>3</p>	<p>Ventilation ware</p> <ul style="list-style-type: none"> • Only for toilet with no window • Check the opening and dimension first • Inform sub-contractor to install the exhaust fan 	 <p>Figure 3.10 opening ceiling</p>  <p>Figure 3.11 Exhaust fan</p>
<p>4</p>	<p>Yard pipe</p> <ul style="list-style-type: none"> • Check the wall render and paint finish first one day • Check the wall skirting for not use the pipe opening • Install the pipe <p>Balcony rain pipe</p> <ul style="list-style-type: none"> • Check the wall render finish first with one day • Check the balcony tile, cut to size of pipe done • Install the pipe 	 <p>Figure 3.12 floor pipe opening</p>




		 <p data-bbox="858 577 1185 611">Figure 3.13 installing pipe</p>
5	<p data-bbox="311 638 630 672">Rain water pipe and dome</p> <ul data-bbox="359 689 762 1093" style="list-style-type: none"> <li data-bbox="359 689 762 779">• Check the wall render finish first <li data-bbox="359 797 762 936">• Install the corridor floor trap during the common area tiles progress <li data-bbox="359 954 762 987">• Install the pipe by floor <li data-bbox="359 1005 762 1093">• At top floor, make sure the dome area is free from trash 	 <p data-bbox="826 996 1233 1086">Figure 3.14 corrior floor trap and rain water down pipe</p>  <p data-bbox="874 1462 1201 1496">Figure 3.15 locating dome</p>


<p>6</p>	<p>Water tank installation</p> <ul style="list-style-type: none"> • Move all the tank to side of plinth • Ensure the plinth surface is level • The plinth area is zero from other material • Install the tank wall 	
		<p>Figure 3.16 transfer water tank</p> 
<p>7</p>	<p>Clerk of work inspection</p> <p>Pressure test</p> <ul style="list-style-type: none"> • Close the cold water point in units • Install the gas meter at meter room • Pump gas 100 psi to every unit with meter • After a day check the pressure, fall 20 psi is allowed 	
		<p>Figure 3.17 install water tank</p> <p>Figure 3.18 pressure test</p>

	<p>Flow test</p> <ul style="list-style-type: none"> • Give water to discharge pipe below the basin in kitchen and toilet • Make sure the water flow seen in the floor trap 	 <p>Figure 3.19 flow test</p>
--	--	---

3.2.2 The electrical work

NO	WORK	DIAGRAM
1	<p>Switches</p> <ul style="list-style-type: none"> • Only in units • Make sure the units finish the painting work • Including yard area • Install the switches 	 <p>Figure 3.20 television socket</p>  <p>Figure 3.21 plug point installation</p>

<p>2</p>	<p>Cable connector</p> <ul style="list-style-type: none"> • Install before first coat wall • Must have to prevent broken cable • Location at toilet, dining room, kitchen, bedroom, yard. 	 <p>Figure 3.22 cable coonnector</p>
<p>3</p>	<p>Distribution board</p> <ul style="list-style-type: none"> • Install before the skim coat • Make sure the area is free from big material • Check the wall quality • Install the distribution board 	 <p>Figure 3.23 distribution board</p>
<p>4</p>	<p>Firefighting</p> <ul style="list-style-type: none"> • Alarm bell corridor, 3 set every floor, 2 wings and one lobby • After the skim coat and corridor paint • Install 2 floor one times 	 <p>Figure 3.24 alarm bell</p>

<p>5</p>	<p>TNB room inspection</p> <ul style="list-style-type: none"> • The area and inside is clean and clear from water and leakage • Part involve is main-contractor supervisor, TNB Officer and their staff, related sub-contractor supervisor, Clerk of work • To check the air pressure inside the room for burning purpose • Closed all the opening at door leaf slit and exhaust fan with masking tape • The portable door is installed and the fan is open to give pressure 	 <p>Figure 3.25 TNB pressure inspection</p>
<p>6</p>	<p>Clerk of work inspection</p> <p>Meggar Test</p> <ul style="list-style-type: none"> • To check all the cable is function and no shot • The meggar box is inspect first before apply on site 	

- First check the 1000W cable, it has 3 nos. It is from riser to unit
- Second check the 600W cable that connect to every plug and switches in unit
- If the needle move a bit, the reading is accepted, if the needle move fast, there has short wire
- The short caused by wire rolling or sink in the wall

Fiber Optic Test/Continuity Test

- To make sure the fiber cable is in good condition without bend in the pipeline.
- Worker torch the laser light in the unit
- Inspector stand at ELV Riser that connect to all units
- The good condition is the cable at riser will be light up



Figure 3.26 Meggar test
















Figure 3.27 continuity test

3.2.3 Another work

Table 3.2.3 Method study for another work




NO	WORK	DIAGRAM
1	<p>Quality installation (piping and electrical)</p> <ul style="list-style-type: none"> • Check after the installation • The peeling of paint will repair with skim coat • The condition of pipe must be 100% perfect 	 <p>Figure 3.28 paint defect</p>  <p>Figure 3.29 correct water point</p>
2	<p>Lift inspection</p> <ul style="list-style-type: none"> • Inspect by JKKP • The lift motor room must be clean and dry from watermark and water pond • Check the room, car speed, car top, lift pit, the button accuracy, door leaf speed 	 <p>Figure 3.30 Lift Motor Room</p>  <p>Figure 3.31 Button and Car top</p>




<p>3</p>	<p>Ventilation appliances</p> <ul style="list-style-type: none"> • The exhaust fan installed at level 5 podium • To give pressure to closed type stairs and lift lobby • Confirmed the concrete ceiling have no leakage and watermark. • Inform sub-contractor to install fan • Check the valve at lift lobby either it is installed or not • Inform to sub-contractor to install it. 	 <p>Figure 3.32 exhaust fan for stairs</p>  <p>Figure 3.33 Valve for air pressure</p>
<p>5</p>	<p>Transfer material</p> <ul style="list-style-type: none"> • Ask supervisor where to place • Place worker to supervise material downstairs and upstairs • Inform both signalman to transfer material 	 <p>Figure 3.34 transfer water tank</p>
<p>6</p>	<p>Housekeeping for inspection</p> <ul style="list-style-type: none"> • For TNB and lift inspection • Provide clean and dry area for incoming officer • To give well expectation before the inspection 	 <p>Figure 3.35 condition before</p>





	<ul style="list-style-type: none"> • Ask the staff which responsible at that place • Supervise the worker from begin to finish 	 <p>Figure 3.36 condition after</p>  <p>Figure 3.37 after housekeeping</p>
7	<p>Piping material in structure</p> <ul style="list-style-type: none"> • Structure staff will leave the element without formwork • Including slab, planter box and column • Check where the pipe location need to connect • Ask the sub-contractor to connect the pipe • Once done, inform the structure staff to proceed pour concrete 	 <p>Figure 3.38 slab before concreting</p>  <p>Figure 3.39 column to install conduit</p>






3.3.1 Management of sub-contractor's issue

Table 3.3.1 Method for manage the problems

NO	PROBLEMS & SOLUTION	DIAGRAM	PARTY INVOLVE
1	<p>Piping work</p> <ol style="list-style-type: none"> 1) Ask permission from architect department to repair the point if the tile broke with proper information 2) Inform to sub-contractor to repair the point in given date 3) After finish, inform to architect department to repair the finish. <ol style="list-style-type: none"> 1) When the skirting disturb the pipe area, ask the tiler to cut and customize the size 2) Then ask the plumber to install the pipe 	 <p>Figure 3.40 cold water point</p>  <p>Figure 3.41 cold water point</p>  <p>Figure 3.42 yard skirting tiles</p>	<ul style="list-style-type: none"> • Mechanical and electrical department • Architect department • 1 plumber/work • 1 tiler

<p>2</p>	<p>Sanitary appliances</p> <ol style="list-style-type: none"> 1) The floor trap must be closed anytime 2) Ask the tiler to give closer to floor trap <ol style="list-style-type: none"> 1) The sanitary ware must have the protection 2) Ask the related sub-contractor to give protection to the material with proper place information <ol style="list-style-type: none"> 1) The opening for exhaust fan must be accurate with the dimension 275mm x 275mm 2) The steel for hang the fan must be on it 3) When the dimension is false and no have the steel 4) Ask the architect staff and sub-contractor from their party to install and repair it. 5) Once done, tell the s to install it. 	 <p>Figure 3.43 floor trap</p>  <p>Figure 3.44 water closet</p>  <p>Figure 3.45 ceiling opening</p>	<ul style="list-style-type: none"> • Mechanical and electrical department • Architect department • 1 plumber for protection • 1 tiler for floor trap • 1 worker for ceiling • 1 installer exhaust fan
-----------------	--	--	---

<p>3</p> <p>Electrical work</p> <ol style="list-style-type: none"> 1) The area around the switches break, cause of plaster or installer 2) Inform to architect staff to sent the worker to repair the broken wall without touch the swithes <ol style="list-style-type: none"> 1) The back box and conduit break cause of wall hacked. 2) Architect staff will inform the broken material 3) Check and inform to the sub-contractor related <ol style="list-style-type: none"> 1) The sub-con supervisor will mark the mistake at wall 2) Find the mark and inform to architect staff to break the tiles and make a new proper holes 	 <p>Figure 3.46 wall break</p>  <p>Figure 3.47 mistake cutting position</p>	<ul style="list-style-type: none"> • Mechanical and electrical department • Architect department • 1 sub-cons worker • 1 plasterer • 1 tiler
<p>4</p> <p>Operation procedure</p> <ol style="list-style-type: none"> 1) The render work will start first before anyone take place 2) Once render finish, either pipe or paint can start work 3) Inform to plumber to break the pipe and give way to renderer run their work 4) Once finish a day, the pipe may install 	 <p>Figure 3.48 yard pipe</p>  <p>Figure 3.49 yard pipe</p>	<ul style="list-style-type: none"> • Mechanical and electrical department • Architect department • 1 sub-cons worker • 1 renderer

<p>5</p> <p>Water leaking in lift shaft</p> <ol style="list-style-type: none"> 1) The water come from planter box outside the wall 2) It has 4 place that leaking happened 3) Ask for PU Inject team from director 4) Bring them to that place 5) Once finish, clean the overhead 6) Then apply one layer of mortar 	 <p>Figure 3.51 leaking wall</p>  <p>Figure 3.52 leaking wall</p>	<ul style="list-style-type: none"> • Mechanical and electrical department • 2 PU Inject worker • 1 plasterer
<p>6</p> <p>House keeping</p> <ol style="list-style-type: none"> 1) Once for inspection day only 2) Ask permission with operation staff to provide worker 3) Supervise the worker until finish 	 <p>Figure 3.53 condition before</p>  <p>Figure 3.54 condition after</p>  <p>Figure 3.55 condition after</p>	<ul style="list-style-type: none"> • Mechanical and electrical department • Operation department • 6 worker for housekeeping

CHAPTER 4

CONCLUSION

Overall after involvement in the construction field at 'Cadangan Pembinaan 2102 Unit Yang Mengandung Fasa 1: 2 Blok Pangsapuri Mampu Milik dan Fasa 2: 2 Blok Pangsapuri di Daerah Bukit Jalil, mechanical and electrical work is the main element in all building project.

The mechanical product such as pipe, elevator, and electrical should be inspect and it is the most important things that should be taken care. As example, the observation and inspection by client of installation is received. To ensure the quality of the finishes of mechanical work will not harm the condition surrounding.

In completing this report, the way to handling and solving the mechanical work is explained in detail by using the well management worker arrangement and communicate with related party to solve the problem. This task give the best experience and knowledge for student practical. This way create the curiosity to learn new knowledge and develop skills in making good management in construction site.

The result after the supervisory, will give the best installation without any big problem that can bring damage for other material. Then, the quality of finishes will give high expectation to the client and the customer which considered to purchase the unit and comment the material inside units.

After the handover, defects will be found and need to be repaired. The supervising work before may decrease the amount of defect of mechanical material. The proper installation will not damage other material also contribute the less wastage to the defect cost to the company.

To conclude, all the mechanical and electrical work should be confirm the quality of work achieve the high standard level of quality.

REFERENCES

Books

Building Construction Handbook, Roy Chudley and Roder Greeno, eight edition
2010, rain water installation page 754

Building Construction Handbook, Roy Chudley and Roder Greeno, eight edition
2010, sanitary fitting page 778

Building Construction Handbook, Roy Chudley and Roder Greeno, eight edition
2010, installation electrical supply Page 788

Building Construction Handbook, Roy Chudley and Roder Greeno, eight edition
2010, telephone installation page 811

Building Construction Handbook, Roy Chudley and Roder Greeno, eight edition
2010, pipe joints page 777

Website


The meaning of supervising work, <https://www.merriam-webster.com/dictionary/work>

The meaning of supervising work,
<https://www.missouristate.edu/human/jobdescriptions/8733-construction-foreman.htm>


Company references, <https://www.kenwingston.com/>

Site project https://thehavre-bukitjalil.com/?gclid=Cj0KCQiAr93gBRDSARIsADvHiOrW81pDVbUqyZBq3In2Vd72WeDCChA0GJE7yGD-QLYqpDrg4regDnQaAgi7EALw_wcB


APPENDICES



Appendix 1: Master plan level 40
Source: Technical Department Havre project



Appendix 2: Floor plan Phase 2 Block A and Block B Units
Source: Technical Department Havre project



Appendix 3: Floor plan Phase 2 Block A and Block B Podium
Source: Technical Department Havre project