PERFORMANCE OF REINFORCED CONCRETE WALL FOUNDATION CONNECTION UNDER LATERAL STATIC LOAD

By

.

AIDA KARTINI BINTI SAIDIN

This report is submitted as a requirement for the degree of **Bachelor of Engineering (Hons.) Civil**

UNIVERSITI TEKNOLOGI MARA JULY 2012

DECLARATION BY THE CANDIDATE

I Aida Kartini binti Saidin(2009997327) confirm that the work in this report is my own work and the appropriate credit has been given where reference has been made to the work of others researchers.

7.

Student Name:Aida Kartini binti SaidinStudent ID:2009997327Date:4th June 2012

ABSTRACT

Steel fabric reinforced concrete wall foundation is considered as an innovative construction method in Malaysia to reduce weight on foundation. This type of wall foundation may require sequencial analysis in making an effective product that gives advantanges in all aspects and gives better performance. This research involved laboratory experimental work on three reinforced concrete wall foundation samples. The wall is reinforced with steel fabric of size B7 and concrete Grade 30 mix with steel fabric. The wall foundation samples were tested under lateral static load with the load applied upper of the wall he ight wall. The support condition was considered as fixed at the lower end foundation. The ultimate load sustained by the samples is 30kN with maximum displacement of 35mm before failure. From the observation, there are failure cracks along the connection and at the side of the connection that influence the strength of the connection itself. Wall foundation 1 started to crack when load reach the value of 5kN with maximum deflection of 15.44mm while for sample 2, wall foundation started to crack when applied load reach the value of 5.97kN with maximum deflection of 10.37mm. Lastly, for sample 3, wall foundation started to crack when applied load reach the value of 8.58kN with maximum deflection of 20.13mm. From research the maximum bending stress for sample 1, 2 and 3 is 3.75 kN/mm², 7.36 kN/mm² and 9.72 kN/mm² respectively. Modulus of elasticity for sample 1, 2 and 3 are 8.78862 x10-3 N/mm², 9.9571 x10-3 N/mm² and 0.1180 x10-3 N/mm² respectively. Therefore, maximum modulus of elasticity usually occurs at connection of wall foundation. Besides that, lateral static load has affect on the compressive strength, fracture energy and ductility thus inhabit the crack propagation of the reinforced concrete wall foundation.

TABLE OF CONTENT

ACKNOLEDGEMENT	i			
ABSTRACT				
TABLE OF CONTENT	iii-vi			
LIST OF FIGURES	vii-x			
LIST OF TABLES	xi-xii			
LIST OF ABBREVIATIONS	xiii			
1 INTRODUCTION	1 0			
1.1 Background	1			
1.2 Problem Statement	2			
1.3 Objective of Study	2			
1.4 Scope of Study	3-4			
1.5 Limitation of Study	4			
1.6 Significant of Study	5			
2 LITERATURE REVIEW	6			
2.1 Introduction	6-7			
2.2 Wall Panel	7-8			
2.3 Foundation	9			
2.4 Connection	9-11			
2.4.1 Lapping of Reinforcement	11-12			
2.4.2 Lap or Development of Length	12			
2.5 Steel Fabric	12-14			

	2.6 Structure Behavior				14
		2.6.1	Compressi	ve strength	14
		2.6.2	Crack		14-15
		2.6.3	Deflection		15
		2.6.4	Ductility		16-17
		2.6.5	Tensile str	ength	17-18
	2.7 Loading			18	
		2.7.1	Lateral loa	ıd	18-20
		2.7.2	Wind load		21
	2.8	The P	rocess of co	ncrete mix design	21-22
3	MET	ГНОD	OLOGY		22
	3.1	Flow	22		
	3.2 Introduction3.3 Dimension3.4 Preliminary Laboratory Work3.4.1 Concrete			22	
				23-24	
				26	
				24-25	
			i. Ordina	ary Portland Cement(OPC)	25
			11. Water		25-26
			iii. Coars	e Aggregate	26-27
			iv. Fine A	Aggregate	27
			3.4.1.1	Slump Test	28
			3.4.1.2	Compression Test of Concrete Cubes	28-29
3.4.2 Steel Fabric					29-31