



**DEPARTMENT OF BUILDING SURVEYING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA
CAWANGAN PERAK
KAMPUS SERI ISKANDAR**

(NOTIFICATION OF COMPLETION RECTIFICATION)

**AHMAD HASSANUDDIN BIN MD ISHAK
(2015752193)
DIPLOMA IN BUILDING SURVEYING**

**PRACTICAL TRAINING REPORT
SEPTEMBER 2018 – JANUARY 2019**

**DEPARTMENT OF BUILDING SURVEYING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA
CAWANGAN PERAK
KAMPUS SERI ISKANDAR**

(NOTIFICATION OF COMPLETION RECTIFICATION)

SEPTEMBER 2018 – JANUARY 2019

This practical training report is fulfilment of the practical training course.

PREPARED BY : AHMAD HASSANUDDIN BIN MD ISHAK

SUPERVISING LECTURER : SR AMIR FASHA MOHD ISA

DECLARATION:

I hereby admit that this report is the result of my own efforts, except for the certain parts that are attached from sources that specified in reference chapter.

Prepared By:



.....
(AHMAD HASSANUDDIN BIN MD ISHAK)

Date: 03.01.19

Approved By:



.....
(SR AMIR FASHA MOHD ISA)

Date: 3/1/19

ACKNOWLEDGEMENT

In performing, my assignment I had to take the help and guideline of the person who involve in our task and the completion of this assignment that gives me more pleasure and knowledge about my practical training at Building Control Department, Majlis Perbandaran Seremban. I would like to show my gratitude to my practical coordinator Sr. Mohd Nurfaizal Baharuddin and Sr. Nazhaltulzalkis on the briefing of our practical training and gives us a good guideline for our report. I also want to thanks to my supervisor Sr Amir Fasha bin Mohd Isa for the guidance in completing this report and numerous of consultation during my practical training. I would also like to expand my deepest gratitude to my supervisor of the company, Ms Kay Tan and also the assistant manager of the company, Eddie Zakaria for guidance and any kind help.

Besides that, gratitude to all those people who have directly and indirectly guide me in writing this report. Thanks especially to my classmates which give ideas and help whenever I need.

Abstract

The task been given is to perform a defect inspection mainly for project Suriaman 2A at Bandar Sri Sendayan, in this case study is Unit 188. The double-storey terrace has 277 units in total. Besides, Suriaman 2A is neighboring with Suriaman 2B and Suriaman 1. The units in Suriaman 2A were built-up of 2,807 square feet and two-storey super link comes with 4 bedrooms and bathrooms each. This project was constructed in 2015 and completed in 2018.

The project team involved are KW ASSOCIATE ARCHITECTS SDN BHD Architect, MEXCELCON is the main contractor for the project and also act as the engineering team. The sub-contractor for electrical is OTT Electrical. Mr. Desmond Siaw is the Project Unit Leader (PUL) the one who responsible to coordinate and lead the team on site.