



**DEPARTMENT OF BUILDING SURVEYING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA
CAWANGAN PERAK
KAMPUS SERI ISKANDAR**

**PRACTICAL TRAINING REPORT
(COMPLETE)**

**MUHAMAD AIMAN FAHMI BIN KAMARUZAMAN
(2014854284)
DIPLOMA IN BUILDING SURVEYING**

**PRACTICAL TRAINING REPORT
DECEMBER 2016 – MARCH 2017**

DECLARATION:

I hereby admit that this report is the result of my own efforts, except for the certain parts that are attached from sources that specified in reference chapter.

Prepared By:

.....
(MUHAMAD AIMAN FAHMI BIN KAMARUZAMAN)

Date: 15/3/2017

Approved By:

.....
(Supervising Lecturer)

Date:

ACKNOWLEDGEMENT

Alhamdulillah, praise to Allah, the Most Merciful. I would like to extend my heartfelt gratitude for the guidance, advice and help throughout the practical training period. First and foremost, I would like to thank the Kota Impiana Properties Sdn Bhd because they have allowed me to join their company for the practical training. During the practical training, it has enable me to learn and develop my understanding, knowledge and feels for the real-time project and the theory involve in house development and construction.

I would also like to thank En Mohamad Naem B. Mohamad Nor for his guidance and for all of the knowledge that he has taught me during my practical training. I would also like to thank all the UiTM lecturers that has taught me in becoming a better student and person. I would also like to extend my appreciation to my parent who has help me financially in finishing this practical training report. Thank you so much.

TABLE OF CONTENT.

TITLE: THE INSTALLATION OF PAD FOUNDATION.

No.	TABLE OF CONTENT	PAGES
1.	CHAPTER 1: DETAILS OF INFORMATION	
	1.1 Company background	2
	1.2. Company track record	3
	1.3. Company profile	4
	1.4. Organization chart	5
	1.5 Scope of Work	6
	1.6 Location plan	7
2.	CHAPTER 2: THEORETICAL STUDY	
	2.1. Definition of foundation	9
	2.2. Type of foundation	10
	2.3. Method of Installation	20
3.	CHAPTER 3: CASE STUDY	
	3.1. Introduction	33
	3.2. Type of foundation at the case study	34
	3.3. Installation work for foundation at the case study	35
	3.4 Specification for pad foundation	38
	3.5 Progress of construction	39
4.	CHAPTER 4: PROBLEM AND RECOMMENDATION	41
5.	CHAPTER 5: CONCLUSION	43
6.	REFERENCE	45
7.	APPENDIX	47

LIST OF FIGURES:

Figure 1.1 shows the project in Tanah Merah.	3
Figure 1.2 shows the project in Kota Bharu.	3
Figure 1.3 shows the location of the company	7
Figure 1.4 shows the front view of the company	7
Figure 1.5 shows the construction of pad foundation	11
Figure 1.6 shows the construction of strip foundation	12
Figure 1.7 shows the construction of raft foundation	13
Figure 1.8 show the type of pile foundation	15
Figure 1.9 shows site clearing process	20
Figure 2.0 show the excavated soil for the foundation.	21
Figure 2.1 show the lean concrete is pour into the excavated soil.	21
Figure 2.2 show the installation of formwork.	21
Figure 2.3 show the spacer block is added for the rebar placement.	22
Figure 2.4 show the rebar is put into the formwork.	22
Figure 2.5 show the rebar is extended for the column	23