



**DEPARTMENT OF BUILDING SURVEYING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA
CAWANGAN PERAK
KAMPUS SERI ISKANDAR**

**(MAINTENANCE WORK FOR AIR-CONDITIONING SYSTEM AND
COOLING TOWER AT PANTAI HOSPITAL MANJUNG)
(COMPLETE)**

**MUHAMAD NAQUIB BIN HALMI
(2014857344)
DIPLOMA IN BUILDING SURVEYING**

**PRACTICAL TRAINING REPORT
DECEMBER 2016 – MARCH 2017**

DECLARATION:

I hereby admit that this report is the result of my own efforts, except for the certain parts that are attached from sources that specified in reference chapter.

Prepared By:

.....
(MUHAMAD NAQUIB BIN HALMI)

Date: 03/04/2017

Approved By:

.....
(SR NAZHATULZALKIS JAMALUDIN)

Date:

TABLE OF CONTENT

No.	Content	Page
1.	Acknowledgement	1
2.	Abstract	2
3.	Chapter 1: Company's Background	3
	1.0 Introduction of Company	5
	1.1 Building Background	8
	1.2 Key Map, Location Map and Site Map	10
	1.2.1 Adjacent Building	12
	1.3 Project Brief	13
	1.4 List of Tenants	15
	1.4.1 Building Tenancy	17
	1.4.2 Site Area of Pantai Hospital Manjung	22
	1.4.3 Car Parking Requirements	23
	1.5 Facilities and Building Services	
	1.5.1 Building Facilities	24
	1.5.2 Building Services	28
	1.6 Building Concept and Design	33
	1.6.1 Design Concept of Pantai Hospital Manjung	34
	1.7 Scope of Work Engineering & Facilities Department	39
	1.7.1 Policies of Pantai Hospital Manjung	41
	1.7.2 Organization chart of Pantai Hospital Manjung Engineering & Facilities Department	42
	1.7.3 Organizational of ESH Committee	43
	1.7.4 Scope of Work & Responsibility of Engineering & Facilities Department	44
	1.8 Summary	51
3.	Chapter 2: Literature Review (Air Conditioning System & Cooling Tower) Air-Conditioning System	
	2.1 Chiller System	53

ACKNOWLEDGEMENT

It is a genuine pleasure to express our deep sense of thanks and gratitude to our lecturer, supervisors and guide Sr. Nazhathulzalkis Jamaludin that expertise, understanding, generous guidance and support made it possible for us to work on. Their dedication and keen interest above all their overwhelming attitude to help his/her students had been solely and mainly responsible for completing our work. Timely advices, scholarly advice and scientific approach have helped us to a very great extent to accomplish this task.

Also thank profusely all the staff of Pantai Hospital Manjung especially to Mr. Shyamil Rambiar, the assistant manager of the Facilities and Engineering Department Management, Senior Officer, Mr. Syafiq Naim and the technician, Mr. Firdaus Ruslee in the building for their help and cooperation for my internship report.

We also want to thank other group which willing to share their information about this final report. Also a great thanks to our family who tries their best to give their support. Finally, we realize that there are so many short comings in this study in spite of all my efforts.

ABSTRACT

The practical training takes 4 months to complete the study taking the diploma as a Building Surveyor. The maintenance programme that applied at this Hospital was systematically for this building. The services of this building are well-maintained. Thoroughly, the subject that had been chosen for practical reports are maintenance of cooling tower and air-conditioning. The problems in this building only is air-conditioning due the temperature is not cold. This department receive many complaints from the Operation Theatre (OT) that the people inside the department is hot. so this department had decided to run 2 chiller for one day starts from 6.00 am – 5.30 pm.