



CAWANGAN PERAK KAMPUS SERI ISKANDAR

CONSTRUCTION OF RC FRAME

MARCH - JULY 2018

This practical training report is fulfilment of the practical training course.

PREPARED BY : MOHAMMAD HUZAIRI B M HUSNI

SUPERVISING LECTURER : SITI ZUBAIDAH BT HASHIM

BSR360 PRACTICAL TRAINING FARIDAZ DEVELOPMENT SDN BHD





DECLARATION:		
I hereby admit that this report is the result of my own efforts, exce	ant for the certain narts	
I hereby admit that this report is the result of my own efforts, except for the certain parts that are attached from sources that specified in reference chapter.		
Prepared By:		
(MOHAMMAD HUZAIRI B M HUSNI)	Date: 7 June 2018	
Approved By:		
(SITI ZUBAIDAH BT HASHIM)	Date: 7 June 2018	

BSR360 PRACTICAL TRAINING FARIDAZ DEVELOPMENT SDN BHD





Acknowledgement

I would like to express my gratitude to my supervisor, Puan Siti Zubaidah for providing her valuable guidance, comments and suggestion through the report. I would like to thanks to the Faridaz Development Company for having me internship in the company. I would specially thanks to Encik Rafizi Ismail, Company's site supervisor for showing me the true method in industry.

Finally I would like to thanks all the employee of the company, for helping me and cooperated well during my training season.





TABLE OF CONTENT

No	Title	Pages
1	DECLARATION BY STUDENT AND SV ACKNOWLEDGEMENT TABLE OF CONTENT LIST OF TABLE LIST OF FIGURE ABSTRACT	i iii iv v vi viii
2	CHAPTER 1: INTRODUCTION OF COMPANY	
	1.1 INTRODUCTION 1.2 COMPANY BACKGROUND 1.3 KEY PLAN, LOCATION PLAN, SITE PLAN 1.4 VISION AND MISSION 1.5 ORGANIZATION CHART 1.6 SCOPE OF WORK	1 2 3 5 6 7
3	CHAPTER 2: THEORETICAL STUDY OF FRAME TYPE CONSTRUCTION	
	2.1 INTRODUCTION 2.2 REINFORCEMENT CONCRETE STRUCTURE DEFINITION 2.3 ELEMENT OF FRAME STRUCTURE 2.4 RC STRUCTURE METHOD STATEMENT	8 9 10 13
4	CHAPTER 3 : CASE STUDY OF FRAME TYPE CONSTRUCTION	
	3.1 INTRODUCTION 3.2 PROPOSAL DESIGN OF CASE STUDY 3.3 TYPE OF CONSTRUCTION 3.4 CONSTRUCTION METHOD STATEMENT 3.5 ADVANTAGES AND DISADVANTAGES OF FRAME TYPE CONSTRUCTION	19 20 21 22 30
5	CHAPTER 4 : PROBLEM AND RECOMMENDATION	
3	4.1 INTRODUCTION 4.2 PROBLEM AND RECOMMENDATION	32 33
6	CHAPTER 5 : CONCLUSION	
	5.1 CONCLUSION	35
7	CHAPTER 6: REFERENCES	
8	6.0 REFERENCES	36
O	APPENDICES	

BSR360 PRACTICAL TRAINING FARIDAZ DEVELOPMENT SDN BHD



foridaz

Abstract

An opportunity has been given to fulfil the internship program at Faridaz Development Sdn Bhd. Faridaz Development is the company that is known as the main contractor especially in property developer and renovation work. The company develop the property according to the client's demand in various specification.

As the trainee of the company. I was assigned in team project which supervise the construction progress of the company project. The supervisor need to ensure the project's method statement and specification of the material is according to the agreement. Also on the supervising of the progress and reporting to the company for claim work.

For the first task, I was assigned to supervise the remedial work at the client property that had been hack due to crack caused by surrounding vibration and minor settlement. The location of the property is surrounded by heavy machinery such as piling driving work. The vibration on surrounding effect the house and cause crack. The task is to ensure the labour remedy the crack with the correct procedure and method with the correct material.

As for other, the problem that had been recognized during internship program had been analyzed and had been come out with the recommendation to overcome the problem before getting severe.