

**THE STUDY OF PHYSICAL AND BIO-CHEMICAL POLLUTANT TRANSPORT IN
URBAN DRAINAGE NETWORK**



RESEARCH MANAGEMENT INSTITUTE (RMI)

UNIVERSITI TEKNOLOGI MARA

40450 SHAH ALAM, SELANGOR

MALAYSIA

BY:

JUNAIDAH ARIFFIN

SUHAIMI ABDUL TALIB

ZUHaida MOHD ZAKI

YAMIN YASIN

MOHD IZANI MOHAMED RAWI

NURASHIKIN AHMAD KAMAL

MAY 2010

ACKNOWLEDGEMENT

There are many individuals who have contributed significantly to this project and who deserve a public statement of our gratitude. They are the final year students of the Faculty of Civil Engineering UiTM for their assistance in the sampling operations and Rokiah Deraman for helping out in the printing of the report. Our gratitude also goes to the Ministry of Science & Technology for the funding of this project. Last but not least the Research Management Institute for the management of funds.

EXECUTIVE SUMMARY

This report describes the study on physical and bio-chemical pollutants in three (3) separate sections. The sections are independent and comprised of table of contents for the respective section, research methodology, results and analysis and followed by the conclusion and references. The first section reports the study on physical pollutants that are also termed as soil and sediment in both dry and wet weather flows. Three study areas were chosen and experimented for the computation of sediment characteristics and losses. They are at a construction site in Section 7, Shah Alam, Puncak Alam construction site that houses the UiTM Second Campus and at a palm oil plantation at Puncak Alam. All study areas are located in Selangor, which is known to be the most urbanized state in Malaysia.

While the second and third sections report the study on the bio-chemical pollutants that are organic and in-organic in both dry and wet weather flows. The studies reported in these two sections focused on catchments that are urban catchment in Section 2 and undergoing development catchment in section 7, Shah Alam.

TABLE OF CONTENT

SECTION ONE		Page
CHAPTER ONE INTRODUCTION		
1.1	Background	1
1.2	Problem Statement	2
1.3	Objective	3
1.4	Scope of work	3
1.5	Significance of study	4
CHAPTER TWO LITERATURE REVIEW		
2.1	Introduction	5
2.2	Weathered Materials with Respect to the Factors Degree of Erosivity	5
2.3	Different Approaches of Soil Loss Measurement	6
	2.3.1 Universal Soil Loss Equation (USLE)	6
	2.3.2 Pins Method	6
	2.3.3 Soil Loss Measurement using MLP Model	9
2.4	Erosion Potentials – The Governing Factors	9
2.5	Adverse Effects of Sedimentation	10
2.6	Effect of Vegetation Cover to Rate of Transport of Weathered Materials	11
2.7	Different Approaches of Sediment Measurement	14
2.8	Sediment Traps	15
CHAPTER THREE METHODOLOGY		
3.1	Introduction	17
3.2	Study Area at a Construction Site Section 7, Shah Alam	17
	3.2.1 Fieldwork - Installation of the Erosion Pins	18
	3.2.2 Trapping of Sediment/Pollutant at the Outlet Point	20
	3.2.3 Rainfall and Wind Speed Data Collection	21
	3.2.4 Laboratory Measurements	21

3.3	Study Area at a Construction Site in Uitm Campus in Puncak Alam Selangor	22
3.3.1	Field Measurements	23
3.3.2	Laboratory Measurements	24
3.3.3	Rainfall Data Collection	24
3.4	Study Area at an Oil Palm Plantation in Puncak Alam Selangor	24

CHAPTER FOUR RESULT AND DISCUSSION

4.1	Introduction	26
4.2	Typical Sediment Characteristics at the Construction Site in Section 7, Shah Alam	26
4.2.1	Soil Surface Elevation	27
4.2.2	Soil Surface Elevation for Individual Erosion Pin	27
4.2.3	Effect of Rainfall and Wind Speed to Soil Surface Elevation	34
4.2.4	Soil Loss Estimation Using the Universal Soil Loss Equation	35
4.2.5	Profile of Sediment Yield	35
4.2.6	Sediment Yield and Erosivity Index	38
4.3	Physical Characteristics of Sediment at the Construction Site in Uitm Campus, Puncak Alam	39
4.3.1	Profile of Upstream and Downstream Sediment Yield	40
4.4	Physical Characteristics of Sediment at an Oil Palm Plantation in Puncak Alam	41
4.4.1	Profile of Sediment Yield	42
4.4.2	Suspended Sediment Concentration With Respect To Rainfall	43

CHAPTER FIVE CONCLUSIONS & RECOMMENDATIONS

5.1	Conclusions and Recommendation for Study Area 1 – Construction Site at Section 7 Shah Alam	45
5.1.1	Recommendation	46
5.2	Conclusions for Study Area 2 – Construction Site at Uitm New Campus at Puncak Alam	46
5.3	Conclusions and Recommendation for	46