



اَوْنُوْرْسِيْطِيْ تِيْكَوْلُوْجِيْ مَارَا
UNIVERSITI
TEKNOLOGI
MARA

DEPARTMENT OF BUILDING
FACULTY ARCHITECTURAL, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA
(PERAK)

SEPTEMBER 2015

It is recommended that the report of this practical training provided

By

MOHAMAD ARIF BIN MOHD NASIR

2013821685

Titled

**INSTALLATION OF DOUBLE ALUMINIUM LOUVERS WITH GLASS
NACO LOUVERS**

Accepted in partial fulfillment of requirement has for obtaining Diploma in Building.

Report Supervisor

Dr. Wan Abdullah Bin Wan Alwi.

Practical Training Coordinator

Pn. Noor Rizallinda Binti Ishak

Programme Chairman

Dr. Mohd Rofdzi Bin Abdullah.

**FACULTY ARCHITECTURAL PLANNING AND SURVEYING
UNIVERSITY TECHNOLOGY OF MARA
(PERAK)**

SEPTEMBER 2015

STUDENT'S DECLARATION

I hereby declare that this report is my own work, except for extract and summaries for which the original references stated herein, prepared during a practical training session that I went at Preserver Bina Sdn Bhd for duration 5 months starting from 25 May and 9 October 2015. It is submitted as one of the prerequisite requirements of DBN307 and accepted as a partial fulfilment of the requirement for the Diploma in Building.

Name : Mohamad Arif Bin Mohd Nasir

ID No. UiTM : 2013821684

Date : 12 October 2015

ACKNOWLEDGEMENT

Alhamdulillah, first of all I would like thanks to Allah S.W.T because with the greatness I have been done completed Practical training for 5 months by side of Preserver Bina Sdn. Bhd. I would like to give some respect and dedication to all individuals in Preserver Bina Sdn. Bhd, for help I completing this practical training report especially for my practical training supervisor, Pn Zashila Bte Ishak, Kak Lini because had been taught everything about being a supervisor and how to being calm during critical situation . Although, I would like to give credit to Preserver Bina Sdn. Bhd. because had let me being there as practical trainee starting from 25 may 2015 to 9 oktober 2015. Last but not least, I would like to give this dedication toward for my parents, friends and his report supervisor Dr Wan Abdullah Bin Wan Alwi because every single support from them, helps me to build my strength and give some advice to complete this practical training report.

ABSTRACT

Following the procedure for installation of window is very important, hereby this report will discuss about installation of double aluminum louvers with glass naco louvers and also delivery schedule of window frame and window accessories from factory to site. This report was carried out to gain the knowledge how to install the window following the right step and also to gain knowledge how the journey of delivery schedule of window from factory to site storage. The objective of this report is to identify how to install the window that begin from establish datum floor until finish installed all window including window accessories and also to identify what should do when window frame arrive at site, what method to unload window frame. Method to gain information for this report is interview from site supervisor how conduct, by reconnaissance at site look how the workers carried out installation work. This report will also look at all the installation procedure should be followed so that requirement from client is achieve.

CONTENT

PAGES

Acknowledgement	i
Abstract	ii
Content	iii-iv
List of Tables	v
List of figure	vi
List of Photo	vii
List of appendix	viii

CHAPTER 1.0 INTRODUCTION

1.1	Introduction	1
1.2	Objective	2
1.3	Scope of report	2
1.4	Methodology	2-3

CHAPTER 2.0 COMPANY BACKGROUND

2.1	Introduction	4-5
2.2	Company Profile	5
	2.2.2 Company Awards	7-8
2.4	Company Organizational Chart	9
2.5	Site organization chart	10
2.6	List of Project	
	2.6.1 Completed project	11
	2.6.2 Project in progress	12

CHAPTER 3.0 CASE STUDY

3.1	Introduction of project	13-16
3.2	Case study	16
3.3	Component of the window	17-21
3.4	Method statement	

3.4.1	Delivery schedule of window frame and accessories window	
3.4.1.1	Delivery material	22
3.4.1.2	Receipt Material	22
3.4.1.3	Unloading	22
3.4.1.4	Hoisting	23-24
3.4.1.5	Storage	24
3.5.2	Installation of double aluminum blade louvers with naco glass louvers	
3.5.2.1	Preparation	25
3.5.2.2	Marking for installation	25
3.5.2.3	Inspection of finished work	26
3.5.2.4	Inspection report	27
3.5.2.5	Setting of frame window	27-29
3.5.2.6	Fixing of aluminum blade, naco glass, L channel, weather strip	29-33
CHAPTER 4.0	CONCLUSION	34
	REFERENCES	35
	APPENDIX	

LIST OF TABLE

Table 2.1 List of completed project	11
Table 2.2 List of on-going project	12

LIST OF FIGURE

Figure 2.1	Company logo	3
Figure 2.2	List of awards	6
Figure 2.3	Site organization chart for Malaysia academy of Han study	8
Figure 3.1	Example aluminium profile for frame	15
Figure 3.2	Example shopfront of frame	16
Figure 3.3	Example of aluminium blade profile	16
Figure 3.4	Example of shopfront of aluminium blade	17
Figure 3.5	Example glass naco while it close	17
Figure 3.6	Example of palmair adjustable louvers	18
Figure 3.7	Example shopfront of L channel	19
Figure 3.8	Example of weather strip	19
Figure 3.9	Flow chart for window installation procedure	31

LIST OF PHOTOS

Photo 3.1	Building design	13
Photo 3.2	mock-up room (sample of facade window)	14
Photo 3.3	Front view of the project at 73% completed	15
Photo 3.4	Drum 1 from level 3	15
Photo 3.5	Site view from water tank elevator	15
Photo 3.6	Unload window frame from lorry by car crane	23
Photo 3.7	Car crane	23
Photo 3.8	setting frame on position	28
Photo 3.9	Fixing palmar adjustable	29
Photo 3.10	Fixing aluminum blade at bottom panel before peel off protective tape	29
Photo 3.11	Fixing aluminum blade at middle panel before peel off protective tape	30
Photo 3.12	Fixing naco glass at top panel	30
Photo 3.13	Fix L channel	31
Photo 3.14	Fix weather strip	31
Photo 3.15	Window after peel off protective tape	32
Photo 3.16	After all window installed	32

LIST OF APPENDIX

Appendix A: Illustration design by architectural

Appendix B: Partial plan for drum 2, 3,4 at level 2

Appendix C: Façade drawing arrangement at drum2

Appendix D: Window schedule

CHAPTER 1.0

PREFACE

1.1 Introduction

Window is a one of building element that important on the building. The major functions of window for opening to allow ventilation occur in the space of the building and also for allow sunlight into the space for illumination. Nowadays, criteria for choosing window not only focus on mention above but selected based on strengthness of the frame, durability at any condition and aesthetic.

William (1995) mention that “window is an important part of exterior design of building. The architecture select types and size that suit the architectural style and proportions of the walls of the building. Window admit light and also provide ventilation”.

Ricketts (200) said “The desire of human changing day by day due to aesthetic on window being important characteristic on selection of window and also building which being interest of people for example commercial building contribute to selection of aesthetic”. There are many types of window apply on building such as side hung window, casement window, fixed glass, louvers window and more

1.2 Objective

This report has a several objective that will discuss which are:

- I. To identify and study how delivery schedule window frame and accessories from the factory to the site
- II. To study and identify and studying the method of procedure for installation of aluminium louvers with glass louvers window.
- III. To identify the component of window

1.3 Scope of study

The scope study for this report was analysed the step of installation of double aluminium louvers with glass louvers for Malaysia academy of han studies project on lot 10147, mukim of Bukit Katil Melaka Tengah district. Hang Tuah Jaya This scope of study also to gain knowledge the how the journey of window from the factory to site and to know what we should do when the window frame and accessories, what method to unloading frame window from lorry to storage. And also to study the component that involve on window.

1.4 Methodology

There is a several method that uses in this report to gain information which is:

1. Reconnaissance
Involve during installation work to get experience at site and also look at near sight how they carried out installation work from middle step until final step. Learn how to manage delivery schedule of window frame and window accessories.
2. Interview
Get the information from people who are versed about installation of window, Mr Ah Lun as a foreman who have experience installation of window about

10 year. Asking how the step to install window. And also Mr Hazim as a site supervisor how to manage the window frame and window accessories when it arrive at site

3. Study on drawing

Study on drawing how to find frame located before installation work begin.
Make sure location and coordinate of frame based on drawing

CHAPTER 2.0


COMPANY BACKGROUND

3.1 Introduction of company

Preserver Bina Sdn. Bhd. is one of the general and specializing in fabrication of steel. This company also constructs including the construction of factories and guest house, Power generation, Petrochemical and Oleo Chemical Plants, Heavy Equipment Installation, Bridge and Infrastructural Steel Structures, Commercial Buildings and High-Rise Buildings, High-Ends show Units, Bungalows and Residential Building.

Preserver Bina Sdn. Bhd. had a multi-talented team of workers as experts who works efficiently as a single force to provide technical expertise and consultancy. This company can design and tailor-make solutions according what clients needed. Besides that, their own Steel Fabrication factory at Lot 4977 & 4978 Jalan Dahlia off Jalan Meru, 41050 Klang, Selangor Darul Ehsan. Therefore, Preserver Bina Sdn Bhd can move forward in line with other companies in Malaysia and abroad.

In 17 April 2009, Preserver Bina Sdn. Bhd. had cooperated with its own partner business as known as Alubina Sdn. Bhd to listed services included fabricated and installed an Aluminum component for general construction and infrastructural projects as well as residential divisions. Alubina Sdn. Bhd. services are backed by very experienced technicians and professional knowledge to ensure high quality products to fulfill client's needs. Alubina Sdn Bhd also has their own factory fabrication at No.22A, Jalan Tiara 5, Bandar Baru Klang, 41150, Klang, Selangor Darul Ehsan.



PRESERVERBINA
sendirian berhad (610805-M)

Figure 2.1: Company logo

Source: [preserverbina](http://preserverbina.com)

2.2 Company profile

Company name : Preserver Bina Sdn Bhd
Incorporated on : 1st April 2003
CIDB registration no : 0120040628-SL 096423 Grade G7(Unlimited)
Quality management system: ISO 9001:2008

Cert. No. 154418-2014-AQ-MYS-UKAS

Address (Office) : Lot 8292 No 3 tingkat 1, Jalan Istimewa, Kg
Batu Belah, 41050 Klang, Selangor, Malaysia

(Factory) : Lot 4977 & 4978 Jalan Dahlia off Jalan Meru,
41050 Klang

Selangor, Malaysia

Paid up capital : RM 3751000.00

Authorized capital : RM 5000000.00

Director board : Khoo Beng Aun , Wong Kok Meng , Ng Boon
Chieng ,

Soon Kien Eng.

Bankers : OCBC Bank Berhad , United Oversea Berhad (UOB) ,
Ambank Berhad

RHB Bank

Telephone no :

Fax no :

Email address : director@pbinasb.org

2.2.1 Company Awards

The Awards and recognition Preserver Bina Sdn. Bhd won over the years prove their capabilities. Among the significant ones are:


- 2 Awards from the Malaysia Architects Association (MAA) – Excellence in Architecture – Winning Showroom Building PAM 2007 for the Ameera Residences Sales Gallery.
- Honorary Mention Showroom Building PAM 2007 Awards for excellence in Architecture for the ONE Menerung Showroom & BRDS Sales Gallery Project.
- Achieved 3,000,000 and 2,000,000 Man Hours Without A Lost Time Incident in its Coal Fired Power Plant from TAISEI CORPORATION (in 30th September 2007 and 21st February 2008 respectively).
- Special Recognition as a Specialist Sub-contractor for the SUNCON GROUP OF COMPANIES' Overseas Projects (Sunway Construction).
- Achieved 2,500,000 Man Hours Without Lost Time Accident Safety Performance For the Superstructure Works – 3A University Technology PETRONAS, Tronoh, Perak. Recognition by NAMFATT-ZAQ JV (31st March 2004).
- ISO 900 1:2008, CONSTRUCTION OF STEEL STRUCTURE.
- Preserver Bina Sdn Bhd also won numerous Recognition for Architectural excellence, outstanding reliability and superior performance from numerous other leading developers.



Figure 2.2: List of award

Source: preserverbina

2.3 Organization chart



2.3.1 Site organization chart




Figure 2.3: Site organization chart for Malaysia academy of Han study

2.4 List of project

2.4.1 Completed Project

Table 2.1: List of completed project

Project	Scope of work	Contract value	Completion date
Samudra Kargo,Bukit Raja The development of a warehouse at Bukit Raja,Klang for M/S Samudra Kargo Sdn Bhd	Main contractor: -substructure -C&S include steel structure -Architecture -M&E	RM 20.4 M	June 2014
KLK-Oleomas New Plant 5B & Tankfarm 2C, Westport Substructure & related civil works For new plant 5B & Tankfarm 2C For M/S KL-Kepong Oleomas Sdn Bhd	Main contractor: -substructure -C&S include steel structure -Architecture -M&E	RM 960 K	July 2014
Nilam Tekad Sdn Bhd-Process Plant & Warehouse package 7, Pulau Indah, Klang Proposed develop of guard house/weighbridge-canopy/canteen/road&drainage/sewerage	Main contractor: -substructure -C&S include steel structure -Architecture -M&E	RM 7.36 M	Apr 2013
Hicom Automotive manufacturer (M) Sdn Bhd Proposed development of Volkswagen facilities for Hicom Automotive	Main contractor: -substructure -C&S include steel structure -Architecture -M&E	RM 46.80 M	Jab 2013

Port Dickson Learning Centre (PDLC) Proposed development learning center at lot 1888, mukim Pasir Panjang daerah Port Dickson Negeri Sembilan	Main contractor: -substructure -C&S include steel structure -Architecture -M&E	RM 15.6 M	July 2012
--	--	-----------	-----------

2.4.2 Project in progress

Table 2.2: On-going project

Project	Scope of work	Contract value	Completion date
Malaysia Academy of Han Studies, Melaka Proposed development of Malaysia academy of han studies on lot 10147, mukim of Bukit Katil Daerah Melaka Tengah, Hang Tuah Jaya.	Main contractor: -substructure -c&s include steel structure -architecture -m&e	RM 66 m	October 2015
Matrade Convention Centre, KL Structural steel work for 1 block pusat pameran matrade 3 tingkat (double volume) dengan tingkat basement tempat letak kereta for TTDI KL Metropolis Sdn Bhd	Construction of steel structure: -Fabrication -Erection	RM 22.5 m	March 2015
Maha Tower, Langkawi Proposed development of mixed commercial building on lot 1424, Kuah langkawi	Main contractor: -substructure -c&s include steel structure -architecture -m&e	RM 100 m	November 2017

CHAPTER 3.0

CASE STUDY

3.1 Introduction of project

Name for this project is Malaysian Academy of Han Studies-Melaka. Proposed development of Malaysia academy of han studies on lot 10147, mukim of Bukit Katil Melaka Tengah district. Hang Tuah Jaya. Preserver bina as main contractor with total project cost RM 60,000,000.00. Contract period is 15 months. Date of commencement is 10th December 2013. Extended completion date is 30th October 2015. Insurance for workmen compensation is RM 6,555,173.32.

The academy comprises 12 blocks called drum covering a built up area of 21,553m², as follow:1 block(drum) of landscape, 1 block (drum) of administrative and classroom auditorium and workshop, 1 block (drum)of office and classroom, 1 block (drum) of office and hostel & 8 blocks (drum) of hostel. This is how it looks after finish construction (refer to photo 3.1)



Photo 3.1: Building design

The client for this project is Malaysia academy of han studies. Lead consultant is studio 505 office hq at Melbourne, Australia. For civil and structural, mechanical and electrical by Arup jururunding Sdn Bhd. Project management consultant by Sweet group office HQ at Singapore. Architect by Akitek KHP. Quantity surveyor by CKP Nizarudin jurukur bahan Sdn Bhd. Interior design by A.I associates Sdn Bhd. Landcape architect by Areca design. This is illustration design by architect (refer to appendix A)

At this site, people call window as facade because of window at exterior finishes of building and also located at the front of building especially an imposing or decorative one. For facade work subcontractor will undertake fabricate work and installation work.



Photo 3.2: mock-up room (sample of façade window)



Photo 3.3: Front view of the project at 73% complete



Photo 3.4: Drum 1 from level 3



Photo 3.5: Site view from water tank elevator

3.2 Case study

Case study in this report will explain how the frame window and the accessories from factory deliver to site and how method to unload the frame from lorry. All this method should be follow to make sure all window safely arrive to storage for installation work. Foreman and supervisor is a responsible people who are need supervise unloading work. This case study also to find the component on the window that involves.

This case study also will discuss how going of installation of double aluminium louvers with naco glass louvers. All the step to install the window should be follow to make sure low mistake happen during installation work. Façade located at every drum and level. (Appendix B). Each window frame is installed next to each other. This drawing showing façade arrangement at drum 2 (refer to appendix C). There are a various type size of window. (Refer to appendix D). The window frame have been fabricated at factory, so it will deliver to site just for installation work.

3.2 Component of the window

1. Window frame

Punmia (1984) mention that “Window frame is main component of the window that support own weight of window”. There so many types frame such as timber, aluminium, steel and so on. For this window it use aluminium frame. This is example aluminium profile can be use

Unit: MM




Figure 3.1: Example aluminium profile for frame

Source: <http://www.aliexpress.com>



Figure 3.2: Example shopfront of frame

Source: <http://www.archivalmethods.com>

2. Aluminium blade

Aluminium blade use to allow ventilation and illumination on the room and vice versa. Every pieces of blade is fix at the end of left and right of frame.




Figure 3.3: Example of aluminium blade profile

Source: <http://www.tamiluz.es>




Figure 3.4: Example of shopfront of aluminium blade

Source: <http://www.aluminumextrusion-profiles.com>

3. Naco glass

The function glass naco same like to aluminium blade but it different between aluminium blade is allow illumination even it close. Types of naco glass that use on this window is clear and tempered glass.




Figure 3.5: Example glass naco while it close

Source: <http://www.glasbau-hahn.com>

4. Palmair adjustable louvers

The purpose of palmair adjustable louvers is to adjust aluminium blade or naco glas whether open or close.




Figure 3.6: example of palmair adjustable louvers

Source: <http://www.lowes.com>

5. L channel

L channel is fixed to allow weather strip to be installed. It be installed at bottom of every panel



Figure 3.7: shopfront of L channel

6. Weather strip

Weather strip is use to seal the gap on L channel. Weather strip also prevent the rain and water enter the room.



Figure 3.8: weather strip

3.3 Method statement

3.3.1 Delivery schedule of frame window and accessories window:

3.3.1.1. Delivery material

- I. The delivery schedule will be planned according to the main processing chart in conjunction to the volume, date and time of delivery, number of trucks and the usage of lifting (hoisting) equipment. Refer to attachment schedule.
- II. All the frame will be protected with pvc protection tape.
- III. The aluminum frame will be delivering to the factory for fabrication and send to the site directly ready for site installation.
- IV. The vehicles used for the delivery shall enter and leave the site according to the site's regulations.

3.3.1.2. Receipt material

- I. When unloading, a check to the material for symbol or presence of damage-in-transit and quantity according to the delivery order.
- II. Report to the personnel concerned in the manufacturing plant of the damage or lack of quantity, if any, immediately.

3.3.1.3. Unloading

All material will be unloaded by fork-lift, site tower crane or mobile crane from the transporting lorry upon arrival at site. When using tower crane or mobile crane, materials will be hoist using a "polyester lifting slings" with a safety lifting capacity of 2,000 kg (as appropriate).

3.3.1.4. Hoisting

1. All the window frame will be distributed to the designated level base on the type and mode of hoisting.

- Tower Crane/ - During unloading, these material which is stack in “A-Rack” will
- Mobile Crane is hoist the transporting lorry using “polyester lifting slings” with a safety lifting capacity of 2,000 kg.



Photo 3.6: Unload window frame from lorry by car crane



Photo 3.7: Car crane

- Passenger - These material will be hoist up to the respective floor Hoist using the passenger hoist.
 - Hand Carry - The material will be hand carried by our workers piece by piece from the passenger hoist to be distributed to the respective floor.
2. All delivered aluminium cladding panels will be stored at the appointed temporary stock yard.
 3. Aluminium cladding panels to each respective floor will be made on weekly basis, and it will be submitted to the main contractor for approval. Lifting work will follow the approved schedule.
 4. The window frame will be store at the appointed area of each designated floor

3.3.1.5. Storage

1. Place of storage is to be given special consideration and as follows: -
 - The place shall be free from rain and ventilation must be good.
 - The place shall be close to the installation area
 - The place shall be away from any major movement to avoid damage by other trades.
2. All aluminium cladding panels are to be stacked against wall (as appropriate). All fitting are to be kept in site store.

3.3.2 Installation of double aluminium louvers with naco glass louvers

3.3.2.1 Preparation

1. Establishing of base reference floor (datum floor). Main Contractor is to survey the general structure of the building (vertically, torsion, in and out, level and structural deviation) on floor to floor and provide the work contractor the datum floor.
2. After determining the datum floor, main contractor is to mark on every floor the survey setting outline and level reference line.

3.3.2.2 Marking for installation

Determine the off-set lines from the survey setting out-line and level reference line for installation.

- Guideline for marking
 1. Off-set line to be transferred out as near to the installation position as possible using a short scale ruler to avoid errors.
 2. Similarly, marking of level reference should be done for the convenience of easy measurement.
- Location of marking
 1. Level marking to be set to column or wall which is 1 meter high from floor finish level.
 2. Location of Grid Center Marking at every floor should be convenient for checking the position of fasteners.
 3. Location of In-Out Marking will be parallel to the installation face to the aluminum framed window.
- Pulling piano wire
 1. Purpose of piano wire is to check the in-out horizontal alignment of aluminum frame window. Therefore, position of piano wire shall be properly transferred from the in-out marking on the floor level. Usually a piano wire of 0.8mm diameter is being used.
- Check marking

1. Counter checking each marking that is provided by Main Contractor to the marking has been set accordingly.
2. Measure the marking for installation from basic reference marking. Counter check both the markings.

3.3.2.3 Inspection of finished work

The entire installed unit will be inspected by Main Contractor's representative base on the following main item:

1. Level Position – Inspect level by level start from ground to level 3 and drum by drum
2. Marking – After inspect supervisor mark the façade with color tape and mark in the drawings.




Figure 3.9: Marked with color frame have been installed at Drum 4 level 2

3.3.2.4 Inspection report

The sets of inspection report to be provided:

- 1 set for main contractor
- 1 set for internal reference

3.3.2.5 Setting of frame Window

It is set in accordance to the 3 directional positions.

- i. Leveling position
The level of the bracket shall be set by the theodolite and scale with reference to the 1 meter finishing level. The allowable tolerance is $\pm 5\text{mm}$.
- ii. Horizontal in-out position
The horizontal in-out alignment shall be checked with a scale ruler against the off-set line.
- iii. Horizontal left-right position
Using the corner unit as a reference starting position, check the balance
frame to the predetermined setting panels' position.



Photo 3.8: Setting frame on position

3.3.2.6 Installation of palmair adjustable, naco glass, aluminium blade, L channel, weather strip

- i. Fix palmair adjustable the both side frame at every panel



Photo 3.9: Fixing palmair adjustable

- ii. Fix naco aluminium at bottom and middle panel. Then fix naco glass at top panel



Photo 3.10: Fix aluminum blade at bottom panel before peel off protective tape



Photo 3.11: Fixing aluminum blade at middle panel before peel off protective tape



Photo 3.12: Fixing naco glass at top panel

- iii. Fix L channel and weather strip at top and bottom every panel



Photo 3.13: Fix L channel



Photo 3.14: Fix weather strip

- iv. Peel of the protective tape after finish install.



Photo 3.15: Window after peel off protective tape



Photo 3.16: After all window installed




Figure 3.1: Flow chart for installation of window procedure

CHAPTER 4.0

CONCLUSION

In conclusion, got a knowledge about how to install the window following suitable method it is important to ensure the durability of frame in various climate and also to make sure aesthetic value still exist on the building even using this window installation method. Furthermore, I get a knowledge the journey of window frame fabricated at factory to the storage at site. Moreover, I gain technic and step to install the window starting datum floor level. Finally, I got a knowledge component that have on a window.

And also I have feel real working environment at site with a several of condition that so challenging in physically and mentally. Working at site is just not only need a tough physical but also a tough mental because there are a lot of problem and pressure from any direction. Sometimes one problem have been solved, followed by a new problem. For example, workers has strike not to working because did not receive a salary. Tough mental ensure all these problem can be solved with the best solution. I also has learned right step to install the window from beginning until it finish. Basically, step to install window is same but at this site there are a bit different during preliminary installation work. I also gain a knowledge how the journey of frame window from factory to storage. Furthermore, I have learned how to communicate to worker who are cannot speak in english and malay language. Give an order to the head of group that can speak in English also malay to tell them.

REFERENCES


Books:


Punmia, D. B. (1984). Building construction. Laxmi Publication Ltd. New Delhi.


Ricketts, M. (2000). Technology and engineering. Mc Graw Hill, New York.


William, P. S. (1995). Finish carpenter: A complete interior and exterior guide.
Sterling Publishing Co, New York.


Appendix A: Illustration design by architectural























Appendix B: Partial plan for drum 2, 3,4 at level 2

PROJECT & CLIENT:
 MALAYSIAN ACADEMY OF HAN STUDIES
 LOT 10147
 MUKIM OF BUKIT KATIL
 CENTRAL DISTRICT, MALAKA

CONSULTANTS:

STUDIO 505
 LEVEL 11
 THE LONSDALE ST
 MEBER SQUARE VIC
 4013 BOUT 2222

ARUP JURURUNDIRING
 LVL 6, WISMA FLAMMA NO. 20
 BANDAR JAYA LALAYA
 52200 KUALA LUMPUR


ARKITERK:

Pa arkitek
 201, TRAYUSAN HILL, 20000 MALAKA, MALAKA
 06-76310000
 www.paarkitek.com

ALUMINIUM SPECIALIST
 ALUBINA SDN. BHD. (MILIK)
 LOT 129, NO. 11, TRINGKIL 1,
 JALAN SINGAPURA, BUKIT KATIL,
 75200 MALAKA, MALAKA
 BERKAMPUS DARI SENAN

REVISION	DESCRIPTION	DATE
-	GOOD FOR APPROVAL	30.12.14
-	REVISION	DECIPHER-TRIX
SUBJECT OF DRAWG:		
PARTIAL PLAN LV2		
DRAW 3		

SCALE	1:50
DESIGNED	-
DRAWN	CHC
CHECKED	LOK
DWG. START DATE	-
REV. NO.	2
DRWG. NO.	HS-12-PL03
SCALE	00




PRODUCT & CLIENT :
MALAYSIAN ACADEMY OF HAN STUDIES
 LOT 10147
 MUKIM OF BUKIT KATIL,
 CENTRAL DISTRICT, MALAKA


CONSULTANTS :
STUDIO 505
 101, HILL LONSDALE ST
 MELBOURNE, VIC
 +61 3 9870 2322

ARUP JURURUNDIRING
 L11 & WISMA FAMMA, NO.20
 BANDAR MANKALARA
 52201 KUALA LUMPUR

ARKITET :
teak KHIP
 201, Jalan Kledang, No. 7500 BERA, MALAKA
 75400 BERA, MALAKA
 +60 6 666 4419



ALUMINIUM SPECIALIST	
ALUBINA SDN. BHD. (GROUPS)	
LOT 1292, NO. 1 TRUKATI, ALIRAN KAYU, WAKO KOTI BERAU, SELOKOR DAHAT, ERAK	
DESIGNED FOR APPROVAL	26.12.14
REVISION	DATE
PARTIAL PLAN LV2 DRUM 2	
SCALE	1:80
DESIGNED	
DRAWN	CHC
CHECKED	LOK
DATE	
FORM NO : HS-L2-PI.02	
ISSUE : 00	



<p>CONSULTANTS :</p> <p>STUDIO 505</p> <p>100-111, LEONISDALE ST</p> <p>MEIKERBOURNE VIC</p> <p>03 9510 9870 2322</p>		<p>PROJECT NO :</p> <p>505</p>
<p>CONSULTANTS :</p> <p>ALUBINA SDN BHD</p> <p>LOT 10147, BUKIT KATIL</p> <p>ALUBINA STRAWWALK (RETAIL)</p> <p>SELANGOR DARUL EHSAN</p>		<p>DATE :</p> <p>30.12.14</p>
<p>REVISION :</p> <p>REVISION NO :</p> <p>DESCRIPTION :</p> <p>DATE :</p>		<p>DESIGNED :</p> <p>DRAWN :</p> <p>CHECKED :</p> <p>DATE :</p>
<p>SCALE :</p> <p>1:50</p>		<p>DESIGNED :</p> <p>DRAWN :</p> <p>CHECKED :</p> <p>DATE :</p>
<p>PARTIAL PLAN LV 2</p> <p>DRUM 4</p>		<p>DESIGNED :</p> <p>DRAWN :</p> <p>CHECKED :</p> <p>DATE :</p>
<p>PROJECT NO :</p> <p>HS-L2-P1.04</p>		<p>SCALE :</p> <p>00</p>

ARUP JURURUNDIRING

LOT 10147, WISMA FLAMMA, NO. 20, BANDAR MANJALARA 52200 KUALA LUMPUR

ARUP

ta tekl KHIP

201, TRINITY HILLS, 75200 MELAKA, MALAYSIA

06-7655 5511

06-7655 5511

06-7655 5511

ALUMINUM SPECIALIST

ALUBINA SDN BHD (RETAIL)

LOT 10147, BUKIT KATIL

ALUBINA STRAWWALK (RETAIL)

SELANGOR DARUL EHSAN

DESIGNED :

DRAWN :

CHECKED :

DATE :

DESIGNED :

DRAWN :

CHECKED :

DATE :

DESIGNED :

DRAWN :

CHECKED :

DATE :

Appendix C: Façade drawing arrangement at drum2

PROJECT & CLIENT :





MALAYSIAN ACADEMY OF HAN STUDIES
LOT 10147
MUKIM OF BUKIT KATIL
CENTRAL DISTRICT, MALAKA

CONSULTANTS :

STUDIO 505
LEVEL 1
288 LITTLE BONGAPLE ST
MELBOURNE VIC 3000
AUSTRALIA
+61 3 9870 2222

ARUP JURURUNDIRING
LVL 5, WISMA FLAMMA, NO. 20
JALAN FLAMMA
50250 KUALA LUMPUR


ARTISTEK :



ALUMINIUM SPECIALIST	ALDIANA SDN. BHD. 600009	
LOT 288, MOUNTINOKATI, 40000 KUALA LUMPUR, MALAYSIA	TEL: 603-26001133	
REVISION	DATE	
01	ISSUED FOR APPROVAL	14.02.15
02	ISSUED FOR APPROVAL	20.07.14
REASON FOR CHANGE		
DESCRIPTION		
DATE		
DRAWN BY		
CHECKED BY		
DATE		
SCALE		
1:10		
DESIGNED BY		
CHKD BY		
DRAWN BY		
LXK		
CHECKED BY		
DATE		
DRAWING NO. : HS-2-APL02		
ISSUE : 01		

FAÇADE ARRANGEMENT 2
DRUM 2

Appendix D: Window schedule



TYPE	QUANTITY	DESCRIPTION	FINISH
02-750-A	1 nos.	ALUM. LOUVER BLADE & 8mm THK. LOUVER GLASS	POWDER COATED
02-900-A	85 nos.	ALUM. LOUVER BLADE & 8mm THK. LOUVER GLASS	POWDER COATED
02-1000-A	172 nos.	ALUM. LOUVER BLADE & 8mm THK. LOUVER GLASS	POWDER COATED
02-1100-A	34 nos.	ALUM. LOUVER BLADE & 8mm THK. LOUVER GLASS	POWDER COATED

PROJECT & CLIENT
 MALAYSIAN ACADEMY OF HAN STUDIES
 LOT 10147
 MUKIM OF BUKIT KATIL
 CENTRAL DISTRICT, MALAKA

CONSULTANTS
 STUDIO 605
 LEVEL 1
 255 LITTLE LONGSPALE ST. #1401B
 AUSTIN SQUARE, VIC
 +61 3 9870 2322

ARUP JURURUNDIRING
 LVL 6, WISMA FLAMMA, NO. 20
 JALAN PERAK
 52000 KUALA LUMPUR

ARKITEK :
aktitek KHP
 201, Pers. Malaysia Impromedia, Jalan
 Pers. Impromedia, Seksyen 13,
 Petaling Jaya, Selangor

ALUMINIUM SPECIALIST
ALIBINA SON BHD.
 101, SRI MONTICOTTI,
 MALAYSIAN INDUSTRIAL PARK,
 SEREMBAN, NEGERI SEMBILAN

NO.	REVISION	REVISION	DATE
01	REVISED FOR APPROVAL		17.11.14
02	REVISION		03.12.14

SUBJECT OF DRAWING
 WINDOW SCHEDULE

SCALE 1:20
 DESIGNED CHC
 DRAWN LOK
 DWG. START DATE 15 NOV 2014
 DWS 152
 HS-ASCO2
 00