

# DEPARTMENT OF BUILDING FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING UNIVERSITY TEKNOLOGI MARA (PERAK)

#### SEPTEMBER 2014

It is recommended that the report of this practical training provided

By

# Noor Hafizah Bt Abd Rahman 2012832138

#### entitled

## **Raft Foundation**

Accepted in partial fulfillment of requirement has for obtaining Diploma in Building.

Report Supervisor

Pn. Hasni Suryani Binti Mat Hasan

Practical Training Coordinator

Pn. Wan Nordiana Binti Wan Ali

**Faculty Coordinator** 

Dr. Mohd Rofdzi Bin Abdullah

#### ACKNOWLEDGEMENT

Alhamdulillah, all praises to Allah for the strengths and His blessing in completing this thesis. Special appreciation goes to my project coordinator, Mr. Mohd Danial Bin Ibrahim, for his supervision and constant support. His invaluable help of constructive comments and suggestions throughout the experimental and thesis works have contributed to the success of this research. Not forgotten, my appreciation to Mr. Hayazi Bin Ibrahim for his support and knowledge regarding this topic. I would to express my appreciation to the Project Manager at Masjid Ar-Rahman , Kedawang, Mr. Norizan for their support and help towards my postgraduate affairs. Sincere thanks to my lecturer supervisor Mrs. Hasni Suryani Bt Mat Hasan for their guidance, advice and moral support during this report in successfully. Thanks for their concern in ensure to being success at training time. Not forget, great appreciation go to the rest Practical Training Coordinator Mrs. Wan Nordiana Wan Ali and Faculty's Coordinator Dr. Mohd Rofdzi Bin Abdullah. Last but not least, my deepest gratitude goes to my beloved parents, and to my siblings for their endless love, prayers and encouragement. To those who directly contributed in this report, your kindness means a lot to me.

Thank you very much

#### **ABSTRACT**

This report explains about a construction of raft foundation. A case study are based on the site which is located at Lot 32, Masjid Ar-Rahman, Kg Gelam, Mukim Kedawang, Daerah Langkawi, Kedah Darul Aman. The objective is to study the installation method of raft foundation and identify the plant and machineries involve in this in this project. To fulfill the objective, there are two method of study which is observation and interview. As a conclusion, the installation of raft foundation started from setting out, excavate soil, compacted hardcore, pest control, installation of formwork, DPM and BRC and also concrete works. Besides that, the plant and machineries use are mobile crane, excavators, concrete lorry, dump truck, concrete mixer, vibrator and compactor.

## CONTENTS

Acknowledge	ements		i
Abstract			ii
Table of Con	tents		iii
List of Tables	S		V
List of Figure	)		vi
List of Abbre	viations		viii
CHAPTER	1.0	PREFACE	
	1.1	Introduction	1
	1.2	Objective	2
	1.3	Scope of Study	2
	1.4	Method of Study	2 - 3
CHAPTER	2.0	COMPANY BACKGROUND	
	2.1	Introduction	4
	2.2	Company Profile	5
		2.2.1 Transportation	6
		2.2.2 Company certificate	7 - 8
	2.3	Organization Chart	9
	2.4	List of Project	10
		2.4.1 Completed projects	11 - 13
		2.4.2 Project in progress	14 - 15

CHAPTER	3.0	CASE STUDY	
	3.1	Introduction	16
	3.2	Projects Background	17
	3.3	Case Study	18
		3.3.1 Method of construction	19 - 23
		3.3.2 Plant and machineries	24 - 28
CHAPTER	4.0	CONCLUSION AND RECOMMENDATION	
	4.1	Conclusion	29
	4.2	Recommendation	30
	43	References	31

## LIST OF TABLES

		Pages
Table 2.1	List of vechicle for company use.	6

## LIST OF FIGURES

		Pages
Photo 2.1	Certificate Issue by SIRM	7
Photo 2.2	Certificate Issue by SIRIM	8
Photo 2.3	Rear elevation of Kompleks KDN Langkawi	11
Photo 2.4	Bengkel Elektronik SMV Langkawi	11
Photo 2.5	Balai Polis Ayer Hangat	12
Photo 2.6	Makmal Sains Tulen Tiga, SMKTP Langkawi	12
Photo 2.7	Bangunan Pejabat Tanah Langkawi	13
Photo 2.8	Bangunan Pejabat JKR Langkawi	13
Photo 2.9	Bazar Wakaf Rakyat, Kedawang	14
Photo 2.10	Concrete work for approach bridge	14
Photo 2.11	Additional store behind the building, Istana Bukit Malut	15
Photo 2.12	Construction signboard	17
Photo 3.1	Setting out .	19
Photo 3.3	Installation of plumbing	20
Photo 3.2	Excavation work	21
Photo 3.4	Hardcore has been compacted	22
Photo 3.5	Termite treatment	23
Photo 3.6	Installation of lean concrete	24
Photo 3.7	Setup the formwork	25
Photo 3.8	The type of DPM has been approval from JKR	26
Photo 3.9	Binding the reinforcement to the first BRC layer	27
Photo 3.10	Using bucket to poured the concrete	28
Photo 3.11	The raft foundation	29
Photo 3.12	Lift up a concrete bucket use mobile crane	30
Photo 3 13	Excavator use to excavate and remove the soil	31

Photo 3.14	Ready mix concrete from factory	32
Photo 3.15	Carried sand, aggregate and hardcore to the site	33
Photo 3.16	Concrete mixture usually use to make in small quantity of concrete	34
Photo 3.17	Vibrate the concrete produce a strength and higher density of concrete	35
Photo 3.18	Compact hardcore	36

## LIST OF ABBREVIATIONS

UiTM Universiti Teknologi Mara

JKR Jabatan Kerja Raya

#### **CHAPTER 1**

#### **PREFACE**

#### 1.1 Introduction

Foundation is the structure which supports the rest of the building. It usually below ground level, that serve to transfer the load from the building or structures to a natural or artificial bedding make it safe and can with stand the load such as dead load, wind load, live load and seismic loads (Chandra Gupta,2007). It can be classified into two type, shallow foundation and deep foundation. The factors that influence the types of foundation is geological, engineering, hydrological condition, the purpose an design of the building structure, the magnitude of the load and the production capacities of the construction organization.

The project at Lot 32, Masjid Ar-Rahman, Kg. Gelam, Mukim Kedawang, Langkawi was purpose to built 1 storey of wakaf bazaar for four units. According to the architectural drawing, raft foundation has been chosen for this project. Raft foundation is essentially the entire building is placed on the large continuous footing and carried downwards load from the structure over a large area. The soils have low bearing capacity and cannot support load from the structure straight forward to the ground. Based on the types of soil, individual footing would cover more than about half of the construction site. This type mostly economic because less cost and the numbers of reinforcement can be reduce.

## 1.2 Objective

- i) To study the installation method of raft foundation
- ii) To identify the plant and machineries that involves in this project

### 1.3 Scope of Study

The scope of study focuses on raft foundation. In this topic, Masjid Ar-Rahman, Kg Gelam Mukim Kedawang which is purpose to built 1 storey of Bazar Wakaf for four units have been choose as location to study about the construction, machinery and tools to construct this building. The client is Yayasan Wakaf Malaysia.

## 1.4 Method of Study

There are two method of study were used in obtain information for this report:

## a) Primary Study

Primary source is source achieved from witness in writing form, record and witness to something which occurred. The materials that can be refer by where the condition still original and unmodified. It can be divided into observation and interview.

#### i) Observation

An observation can be made based on the activity carried out at site built. Instrumentation such as camera also can help to get distinct image on activity that carried out.

#### ii) Interview

Make an interview directly and asks relevant questions to the person who in charge on the project. This method can be used to obtain more detailed information about the procedure/method and material used on the construction.

## b) Secondary

Secondary source is information or publications grouped by other individual as reference. It includes public document, archive, administrative document and formal report. In construction industry, former document must be kept so that can be used as a reference material when something happens in the future on building built. For example, submission fail which is contain certificate submit owned by project, relevant information project, layout guarantee certificates building, as-build drawing and project pictures.

#### i) Book/Journal

 Journal is a daily written record of experiences and observations by person. It is a periodical dedicated to a particular subject such as ledger which transactions have been recorded as they occurred.

#### ii) Article

 Making reference from source that is reliable such as article from official website published by company.

#### **CHAPTER 2**

## **COMPANY BACKGROUND**

#### 2.1 Introduction



Sources: Website JKR Langkawi

Jabatan Kerja Raya (JKR) is one of government body that had helped to upgrade people's life in Malaysia. The mission is to provide infrastructure and public amenities especially walk, water supply, building, airport and port to fulfill needs of the nation's development with always give emphasis to complete in fast period, economic and good design.

The objective of operational this company is to provide infrastructure and public facilities according to the quality, efficiency, economic, complete in short period and good in planning and performance. Second, to ensure maintenance for all facilities and always in a good condition, comfort and fulfill customer needs. Besides that, it also provides technical advisory service to state government, local government and customer departments with the best expertise. In building department under state basically more focus on built the mosque, hotel, hospital, and facilities. Building department under education focus on built school, library, and so on.

## 2.2 Company Background

Company Name : Jabatan Kerja Raya (JKR) Langkawi

Date in Corporation : 19 October 1955

Company Address : Pejabat Jurutera Daerah Langkawi,

JKR Langkawi, Jalan Air Hangat,

O7000 Kuah, Langkawi, Kedah Darul Aman.

No. Tel :

No. Fax

E-mail : langkawi@jkr.gov.my

Business Status : Government

# 2.2.1 Transportation

Table 2.1 List of vechicle for company use.

NO	EQUIPMENT/PLANT	NUMBER
1	UTILITY VEHICLE:  Toyota Land Cruiser  Isuzu Trooper  Land Rover  Misubishi Pajero  Isuzu Pick-up  Nissan X-Trail  Mercedes Benz  Toyota Harrier  Explorer Long Boat	1 1 1 3 1 2 1 1 2
2	TIPPER LORRY:  Hino Tipper Lorry	2
3	FLAT BOTTOM LORRY :  > Hino Flat Bottom > Isuzu Flat Bottom Lorry	2 1
4	SHOVEL :  > Hitachi	1
5	BACK-HOE LOADER :  > UMV Case Back Hoe Loader	1
6	ROLLER:  > Vibromax > Trailer Kayu	1
7	TRACTOR: > Flat Tractor	2

## 2.2.2 Company Certificate



Photo 2.1 Certificate Issue by SIRM

Source: Jabatan Kerja Raya Langkawi



## CERTIFICATE

IQNet and SIRIM QAS International hereby certify that

#### JABATAN KERJA RAYA NEGERI KEDAH

JKR DAERAH LANGKAWI ARAS 5, KOMPLEKS LADA PERSIARAN PUTRA 07000 KUAH, LANGKAWI KEDAH DARUL AMAN MALAYSIA

has implemented and maintains a

#### QUALITY MANAGEMENT SYSTEM

which fulfils the requirements of the following standard

ISO 9001: 2008

for the following activities

TECHNICAL ADVISORY SERVICES AND MANAGEMENT FOR GOVERNMENT INFRASTRUCTURE PROJECTS.

Issued on

: 20 February 2013

Validity date

: 11 January 2016

Certification Number : MY-AR 4224



Michael Drechsel

Khalidah Mustafa Managing Director SIRIM QAS International Sdn Bhd



[QNet Partners\*]

AENOR Spain AFNOR Certification France Alls. Vincole laternational Beginn ANCE Moster AFCER Forugal CCC Cyprus CLSQ Intiv CQC Crima CQG Coch Republic Cro Cert Creation DQS Holding GmbH Germany DS Demoural. FCAN Bright FONDORONAM Avenerated ICONTEC Geological INNOCEM Training Consist Germany DS Demoural. Imagesta Certification Federal RAM Argenian IQA Japan KPQ Korna MST Hungary Newko AS Norway NSA Hedand PCBC Foliand Quality Austria Austra RR Resease SIL Invest [30] Sovenia ISBIND AQS International Adalogica GoS Selectedual SRAC Romania TEST St Pastesburg Russia TSR Turkery YUQS Serbia ISBIND ADS CHIEF CONTROL OF CHIEF CONTROL DOS CONTROL OF CHIEF CONTRO

Photo 2.2 Certificate Issue by SIRIM

Source: Jabatan Kerja Raya Langkawi

### 2.3 Organization Chart




Diagram 2.1 Organization chart at JKR Langkawi

## 2.4 List of Project

#### 2.4.1 Completed Projects

- Kementerian Dalam Negeri, Jalan Padang Matsirat, Mukim Kuah, 07000 Langkawi, Kedah Draul Aman.
- ii) Bengkel Elektronik SMV Langkawi, 07000 Langkawi, Kedah Darul Aman.
- iii) Balai Polis Ayer Hangat, 07000 Langkawi, Kedah Darul Aman.
- iv) Bangunan Makmal Sains Tulen Tiga Sekolah Menengah Kebangsaan Tunku Putra, 07000 Langkawi, Kedah Darul Aman.
- v) Tapak Kompleks Pejabat Daerah dan Tanah Langkawi, Lot 348, Bandar Kuah Seksyen 4, Daerah Langkawi.
- vi) Jabatan Kerja Raya, Pejabat Jurutera Daerah JKR Langkawi, Jlan Ayer Hangat, 07000 Kuah Langkawi, Kedah Darul Aman.

## 2.4.2 Project in Progress

- Bazar Wakaf Masjid Ar-Rahman, Mukim Kedawang, 07000 Langkawi, Kedah Darul Aman.
- Naik Taraf Jeti Gua Kelawar, 07000 Kuah Langkawi, Kedah Draul Aman.
- iii) Cadangan Kerja-kerja Tambahan Di Istana Bukit Malut, Mukim Ulu Melaka, Daerah Langkawi, Kedah Darul aman.

## 2.4.1 Completed Projects

i) Proposed extension and renovation work for Kompleks KDN Langkawi at Jalan Padang Matsirat, Mukim Kuah, 07000 Langkawi, Kedah. Project was started on 15/07/2010 and finish on 15/10/2011. The total amount of construction is RM 42,987,619.00.



Photo 2.3 Rear elevation of Kompleks KDN Langkawi

i) Proposed to build one unit of Bengkel Elektronik SMW Langkawi at Jalan Padang Gaung, 07000 Langkawi, Kedah.These projects was started on 12/11/2012 and completed on 11/07/2013. The total amount of construction is RM 807,967.50.



Photo 2.4 Bengkel Elektronik SMV Langkawi

ii) Purposed to build Balai Polis Ayer Hangat at Jalan Ayer Hangat, 07000 Langkawi, Kedah. This project was started on 24/12/2009 and completed on 11/07/2013. The total amount of construction is RM 8,198,045.52.



Photo 2.5 Balai Polis Ayer Hangat

iii) Proposed to build 3 storey of Makmal Sains Tulen Tiga, Sekolah Menengah Kebangsaan Tunku Putra at Padang Matsirat, 07100 Langkawi, Kedah. The project was started on 10/10/2007 and completed on 07/12/2008. The total amount of construction is RM 3,232,555.00.



Photo 2.6 Makmal Sains Tulen Tiga, SMKTP Langkawi

iv) Proposed extension and renovation work for Bangunan Pejabat Tanah which is located at Lot 348, Bandar Kuah Seksyen 4, Daerah Langkawi. These project was started on 26/08/2013 and finish on 25/04/2014. The total amount of construction is RM 3,979,000.00.



Photo 2.7 Bangunan Pejabat Tanah Langkawi

v) Proposed to built Bangunan Pejabat JKR Langkawi which is located at Jalan Ayer Hangat, Kuah, 07000 Langkawi, Kedah Darul Aman. The construction are started on 13/02/2008 and completed on 10/02/2009. The total amount of construction is RM 4,148,425.00.



Photo 2.8 Bangunan Pejabat JKR Langkawi

## 2.4.2 Project in Progress

i) Proposed to built Bangunan Bazar Wakaf Rakyat for 4 unit at Lot 32, Masjid Ar-Rahman, Kg Gelam, Mukim Kedawang, Daerah Langkawi, Kedah Darul Aman. Started on 08/05/2014 and completed on 28/08/2014. The total amount of construction is RM 354,600.00. This building have been reach about 95% of completion.



Photo 2.9 Bazar Wakaf Rakyat, Kedawang

ii) Proposed to upgrade Jeti Gua Kelawar at Kilim, Langkawi, Kedah Darul Aman. The project was started on 03/08/2013 and will complete on 14/04/2014. The total amount of construction is RM 1,348,010.00. It just leave about 24% to complete this project.



Photo 2.10 Concrete work for approach bridge

iii) Proposed additional work at Istana Bukit Malut, Mukim Ulu Melaka, Daerah Langkawi, Kedah Darul Aman. The total amount for this project is not available because it involving certain person.



Photo 2.11 Additional store behind the building, Istana Bukit Malut

#### **CHAPTER 3**

#### RAFT FOUNDATION

#### 3.1 Introduction

These studies describe about the method to construct raft foundation and machineries involve in construction of raft foundation. The location is at Lot 32, Masjid Ar-Rahman, Kg Gelam Mukim Kedawang, Daerah Langkawi which is purpose to built Bangunan Bazar Wakaf Rakyat for 4 units. Foundation is the structures which supports the rest of the building and transfer the loads from the building or structures to the soil. There are two types of raft foundation, that is flat raft and the wide toe raft which is commonly used in the construction of commercial building in the UK. In Malaysia, typically use pad foundation and piling because the of the soil condition. Moreover, The factors should be consider in choose foundation such as geological, engineering, hydrological condition at the construction site, the purpose and design at the building or structure, the magnitude of the load impose on the foundation and the production capacities of the construction organization.

Besides that, it can be determining using probe McIntosh and soil investigation at the point which is has been plotted at the site. Probe McIntosh method commonly made by contractor while soil investigation will done by professional. This method can ensure type and size of footing. For each footing, it consist concrete slab which extends over the entire loaded area. Therefore, spread footing would cover more than 50% of the building foot print area.

### 3.1.1 Project Background



Photo 2.12 Construction signboard

For this case study, a project proposed to build Bazar Wakaf Rakyat for 4 unit at Lot 32, Masjid Ar-Rahman, Kg. Gelam Mukim Kedawang, Daerah Langkawi, Kedah Darul Aman has been choose as a location. Based on construction at the site, it will explain about the construction of raft foundation and machineries involve in this project. A client for this project is Yayasan Wakaf Malaysia.

To choose a qualified contractor, JKR will analyze quotations from the contractor. Usahacoms Bina Enterprise was elected for this project because the price is low and 5% less than department estimate, period equivalent to fixed-term department and experienced carrying out work under JKR supervision. The total cost for Bazar Wakaf Rakyat for 4 unit is RM 354,600.00. Contract period for this project is 16 weeks started from 5 Mei 2014 and completed on 28 August 2014.




Diagram 1: Installation of raft foundation for Bazar Wakaf Rakyat

## 3.3.1.1 Setting out

Setting out is the process indicate building border position using surveying instrument. Nowadays, surveyor might use theodolite to measure horizontal and vertical angles, measure location on line, prolonging survey lines, determine differences in elevation, setting out and others. Contractor should be responsible to ensure that all instruments and equipment in good condition. After survey works done, contractor will transfers from the architecture drawing to site plan according to spec. This stake will be built around the building line with distance at least 1.2m from the line to make sure it not disturbing construction works. Then, thread will be pulled and strapped to nail. The function is to mark area which is involved in excavation work. Make sure the position of building and other structural like basis, fence, road and water drainage are planning properly. For the project one storey of Bazar Wakaf Rakyat for 4 unit, the size is 18.28 x m 9.2 m. Then, setting out should be done before excavate works take over.



Photo 3.1 Setting out

#### 3.3.1.2 Excavation

Excavation works shall consist of all required excavation within the limits of the works. It must include the removal, proper utilization or disposal of all excavated materials, constructs, shaping and finishing of all earthworks. Levels should be taken before and after excavation. It is because to calculate the volume for each method and also the type of plant and machineries used. In this project, excavation only involve in basic construction and sewage pipe drainage only. According to the drawing, 230mm of depth are to bear load from trusses and column then distribute the load to the horizon and course below. The depth of foundation must be decided on site refer to drawing plan which is had been prepared by civil and structure consultant.



Photo 3.2 Excavation work

Before commencing on any excavation, contractor shall make site inspection to identify the presence of underground cables, water or other service pipes at the excavation area. If during excavation, the workers uncover any cables, water or other service pipes, work shall be stopped immediately. For this project, sewage pipe drainage installation shall be made before soil compressed.



Photo 3.3 Installation of plumbing

# 3.3.1.3 Compacted Hardcore

The function of hardcore to fill the concrete volume, increase strength and concrete resilience and arrest contraction. The size is among 5mm to 50mm but for this project it prefers to use 25mm of hardcore. Then, 150mm thickness of hardcore shall be provided and laid on the sand and well rammed, compacted and blinded.



Photo 3.4 Hardcore has been compacted

## 3.3.1.4 Pest control

Pest control shall be applied between the lean concrete and hardcore at minimum rate of 1 litre per linear meter. Minimum surface application rate should be 5 litres per m² on all ground floor built-up including apron, and 1 meter from the building area. It cannot perform properly and reduce the workability of chemical when it exposed to the heavy rain. After spraying of chemical, the area must be protected or covered with an impervious black PVC sheet with minimum thickness of 0.08mm. Besides that, contractor also should remove the covering and applied lean concrete immediately. The anti-termites treatment specialist's guarantee for 2 years from the date completion works due to any defects, fault or ineffective.



Photo 3.5 Termite treatment

Lean concrete consist of cement, fine aggregate and course aggregate in the nominal ratio by volume of 1:3:6 and 1:4:8. Provide and measured all the materials separately appropriate to the nominal mix. Then, laid and flat the lean concrete about 50mm thickness and make sure cover overall the area involved.



Photo 3.6 Installation of lean concrete

## 3.3.1.5 Installation of formwork and Damp Proof Membrane

Formwork included as temporary or permanent forms required for forming the concrete. The formwork should be sufficiently rigid and tight to prevent loss of grout or mortar and be appropriate for the methods of placing and compacting. Formwork required for their support to maintain the forms in correction position, shape, profile and dimensions. It must be arranged properly and remove from cast concrete without any effect to the concrete.



Photo 3.7 Setup the formwork

The next step is to laid the DPM layer on the compacted hardcore which is acts as prevention moisture from entering to the building. According in the drawing, the damp proof membrane should be extruded polythene film with nominal thickness of 0.5mm. A minimum of 150mm overlap must be providing between each of the sheet. Use double sided or mastic strip compound to join the sheet together. The durability is over than 30 years with a high compressive strength and extremely flexible.



Photo 3.8 The type of DPM has been approval from JKR

#### 3.3.1.6 Bar reinforcement concrete

In this project, two layers of bar reinforcement concrete size A7 are used. Contractor responsibility to make sure the reinforcement is laid out correctly and supported by spacing block to forms the displacement during the placing and compacting of concrete. Spacing block are use to ensure that reinforcement is correctly position, consistent with their purpose to infill the concrete. It is commonly use between damp proof membrane and the first layer of bar reinforcement concrete. Otherwise, to form a space to the second bar reinforcement concrete they use s-curve shape. So, all intersecting bars shall be tied together with binding wire shall be turned into the main body of the concrete.




Photo 3.9 Binding the reinforcement to the first BRC layer

#### 3.3.1.7 Concrete work

For these construction of Wakaf Bazar Rakyat, concrete grade 35 are used with the total amount of concrete is 50m³. Before start a concrete work, the contractor shall making a trial mixer and preliminary testing of the cube. The workability of each of the three trial batches determined by means of the slump test or compacting factor test. For the cube test, six cube shall be made from each batch. For each set shall be test at age of 7 to 28 days. The average strength can be decided after 28 days. Concrete shall be poured into place from a height exceeding 1.5 meters. It is because higher drops may be allowed provided that mix has been well designed and proportioned. It shall be thoroughly compacted using vibrator. Then, the concrete shall be uniformly leveled and screeded to produce a plain surface.



Photo 3.10 Using bucket to poured the concrete

#### 3.3.1.8 Surface Finish for Structure

Formwork shall be removed without such shock or vibration as would damage the concrete. Contractor must be ensure that concrete are ready before removed the formwork. The removal of the formwork for various part of the structure as suit the requirements for its curing. The minimum period between concreting and removal of formwork is 21 days.



Photo 3.11 The raft foundation

## 3.3.2 Plant and Machineries in Installation of Raft Foundation

# i) Mobile Crane



Photo 3.12 Lift up a concrete bucket use mobile crane

Crane mobile is crane with a tower that is used to lift and lower materials. Cranes are commonly used in the construction industry and in manufacturing heavy equipment. This type only suitable for small building due to ability capacity allowed. In concrete work, it uses to lift up the bucket to reach far place. Crane may either be controlled from an operator in cab, workers on the ground will communicate with the operator using hand-signals.

# ii) Backhoe



Photo 3.13 Excavator use to excavate and remove the soil

Excavator commonly use in excavation work. It is because the ability to perform many jobs, for examples cleans up construction site, removal soil, digging trenches including laying pipes, cables and foundation. A shovel or bucket attachment can be control at one place. The operator can adjust the seat to control both attachments necessary.

# iii) Batching Plant



Photo 3.14 Ready mix concrete from factory

According to the nature of work into cyclical mixer and the continuous mixer work. It is to make sure the concrete not become harden all the materials are mix properly. The ready mix concrete will made according to the grade order by a contractor. For this building, it used grade 35 for the whole construction. There are several type of batching plan such as mix tube structure form points pear types mixer, drum tube type mixer, dual cone mixer, the disc vertical shaft type mixer and circular trough horizontal-axis type mixer and others. In addition, mixer is divided into crack tube type and circular groove mixer.

# iv) Dump Truck



Photo 3.15 Carried sand, aggregate and hardcore to the site

The function of a dump truck is to move or transport brut matter such as earth, sand, rocks, gravels, and sometimes refuses or rumbles. A typical dump truck is equipped with one open box bed, to lift the box it use hydraulic pistons which allowing the material in the bed to be deposited to the ground behind the truck at the site of delivery. Mostly founded on the road is 6 wheels, 10 wheels or 12 wheels.

# v) Concrete Mixer



Photo 3.16 Concrete mixture usually use to make in small quantity of concrete

Concrete mixer always used to mix concrete in small quantity. The benefits is could simplify a work and save time. To get the consistent quality of cement concrete all ingredients like cements, sand, meta, water and additive chemicals are measured and mix per batch. It also can make the concrete durable and not hardens easily.

# vi) Vibrator



Photo 3.17 Vibrate the concrete produce a strength and higher density of concrete

A concrete vibrator is a construction tool used on concrete pouring sites. It used to ensure concrete free from bubbles, make the concrete strong and have a smooth finishes even after the formwork is removed. Proper use of concrete vibrator requires some training. It is because it can effected the instability concrete mix where a concrete mix with a wide range of materials sizes causing weaker concrete paste to fill the area. The head should always be slowly lowered into the pour and pulled out gradually to avoid the formation of an air pocket.

# vii) Compactor



Photo 3.18 Compact hardcore

Compacted machineries is a kind of heavy equipment which is use for construction work. The function is for compacting soil or other material so that the soil or other materials will reach the determined density level. It will make the soil structure tighter ad more hardens. Compacted machineries totally made from steel. A special small compacted machineries more easy because the direction of compact area can be control manually. It makes work easier and need short time to finish while the result is very good.

#### **CHAPTER 4**

#### CONCLUSION AND RECOMMENDATION

#### 4.1 Conclusion


The conclusion is about the construction of raft foundation. The site project are located at Lot 32, Masjid Ar-Rahman, Kg. Gelam, Mukim Kedawang, Langkawi was purpose to built 1 storey of wakaf bazaar for four units. The objective for this project is to study the installation method of raft foundation and identify the plant and machineries involve in this project. From this report, learn the process from beginning started from setting out, excavate soil, compacted hardcore, pest control, installation of formwork, DPM and BRC and also concrete works. Besides that, the plant and machineries use are mobile crane, excavators, concrete lorry, dump truck, concrete mixer, vibrator and compactor. Therefore, learn more detail and exposure to the site activity can gain new experiences.


## 4.2 Recommendation


For the future report, is preferred to make a research about pad foundation. The construction of pad foundation commonly use even in built a house. There several function of pad foundation is to carry load then separeted to the ground level, support existing and unstable structures and resist a soil movement when have a forces.


### REFERENCES


- Gvsonlineuk, (2012). A Guide to DPM Damp Proof Membrane And Its Uses. Retrieved on 21 July 2014, from http://www.ebay.com/gds/A-Guide-To-DPM-Damp-Proof-Membrane-And-Its-Uses-/10000000176470477/g.html.
- Sharat Chandra Gupta, (2007). Raft Foundation Design and Analysis With A Practical Approach. Retrieved on 15 July 2014, from http://books.google.com.my
- Thomas Telford, (2000). Design Applications of Raft Foundation. Retrieved on 26 July 2014, from http://books.google.com.my











# USAHACOMS DINA ENTERPRISE

Kg. Perana, Mukim Olu Moiona, 07000 Longkawi, Kedah Darul Aman.

Ruj. Kami

: UBE/JKR/15/2014

Tarikh

: 26 Ogos 2014

Ketua Penolong Pengarah Arkitek Jabatan Kerja Raya Negeri Kedah, Tingkat 5,Bangunan Sultan Abdul Halim, Jalan Sultan Badlishah, 05582 Alor Setar, Kedah Darul Aman.

Tuan.

CADANGAN MEMBINA BANGUNAN BAZAR WAKAF RAKYAT 1 TINGKAT (4 UNIT) DI LOT 32, MASJID AR-RAHMAN, KAMPUNG GELAM, MUKIM KEDAWANG, DAERAH LANGKAWI, KEDAH DARULAMAN.
(NO.SEBUTHARGA: ARKITEK 01/2014)

-Tuntutan Bayaran Kemajuan No. 2

Merujuk kepada perkara diatas.

- 2. Bersama-sama dengan ini disertakan BQ bagi Tuntutan Bayaran Kemajuan No.2 yang berjumlah <u>RM 195,890.00</u> ( Ringgit Malaysia : Seratus Sembilan Puluh Lima Lapan Ratus Sembilan Puluh Sahaja.
- 3. Kerjasama dan kelulusan dari pihak tuan amat dihargai.

Sekian, terima kasih.

Yang bengr,

s.k: Jurutera Daerah,
Jabatan Kerja Raya Langkawi,
Jalan Ayer Hangat,
07000 Kuah, Langkawi
Kedah Darujaman.

***						0	7 1/1/1	W T W T W O O U
	WAKAF RAKYAT N	BAZAR WAKAF RAKYAT MASJID KEDAWANG LKWI	KWI 100 days	Mon 5/5/14	Thu 28/8/14	73%		· Autom
	KERJA-KERJA AWALAN	z		Mon 5/5/14	Tue 20/5/14	10.77		
	Milik tapak		0 days		Man 5/5/14	%6	⊕_5/5	
>	Insuran		4 days	Mer. 5/5/14	Thu 8/5/14	100%	100%	
5. V pro	program kerja & CPM		4 days	Mon 5/5/14	Thu 8/5/14	100%	Months and the second second 499%	,9
6 V Mo	Mobilisation mesin & alatan	alatan	2 days	Sat 10/5/14	Sun 11/5/14	100%	₹	160%
. We	Memasang dinding adang	lang	5 days	Sat 10/5/14	Wed 14/5/14	100%	7	100%
Kei	Kerja-kerja meroboh		3 days	Sat 10/5/14	Mon 12/5/14	100%		100%
Wie Wie	Mengalih tiang TNB & STMB	STMB	10 days	Sat 10/5/14	Tue 20/5/14	100%	*	TOO
10 V. Me	Mengalih garaj		2 days	Sat 10/5/14	Sun 11/5/14	100%	-	100%
Kel Kel	Kerja rekabentuk struktur binaan	ktur binaan	6 days		Thu 15/5/14	100%	**	100%
FERJ.	KERJA-KERJA BANGUNAN	NAN .	93 days	Tue 13/5/14	Thu 28/8/14	%89	to design the second of the se	
18 7 7 81	STRUKTUR ASAS RAKIT	\KIT ·	15 days	Tue 13/5/14	Thu 29/5/14	100%		
	sedingout & penyediaan tapak	diaan tepak	3 days	Tue 13/5/14	Thu 15/5/14	100%		Xxvinance and and a 400%
<u>&gt;</u>	Penyediaan asas tapak/CF base	apak/CE base	5 days	Sat 17/5/14	Wed 21/5/14	100%		A COUNTY OF THE PROPERTY OF THE PARTY OF THE
> 2	Kerja rawatan anai-anai	-anai	2 days	Thu 22/5/14	Sat 24/5/14	100%		
	Pasang acuan		3 days	Thu 22/5/14	Sun 25/5/14	106%		
	Pasang BRC & besi tetulang& DPM	si tetulang& DPM	2 days	Mon 26/5/14	Tue 27/5/14	100%		_
`> :2:	Kerja konkrit asas rakit	rakit	2 days	Wed 28/5/14	Thu 29/5/14	100%		
,	KERJA KERANGKA BANGUNAN	BANGUNAN	26 days	Sat 31/5/14	Sun 29/6/14	85%		
21 1	Memasang besi tetulang utk tiang	tulang utk tiang	2 days	Sat 31/5/14	Sun 1/6/14	100%		
22	Memasang acuan tiang	tiang	2 days	Won 2/5/14	Tue 3/6/14	100%		
23 🗸	Kerja konkrit tiang		2 days	Wed 4/6/14	Thu 5/6/14	100%		
24 🔨	Memasang acuan rasuk bumbung	rasuk bumbung	6 days	Sat 7/6/14	Thu 12/6/14	150%		
25 🗸	Mernasang besi tetulang	tulang	2 days	Sat 14/6/14	Sun 15/6/14	100%		
.>. 97	Kerja konkrit rasuk bumbung	bumpand :	2 days	Mon 15/6/14	Tue 17/6/14	100%		
27 ~	Membina konkrit gutter	utter	6 days	Wed 18/6/14	Tue 24/6/14	100%		
32	Membina dinding konkrit (perabong)	(onkrit (perabong)	4 days		Sun 29/6/14	%0		
29 V KE	KERJA BINAAN BUMBUNG	IBUNG	46 days	Sat 17/5/14	Tue 8/7/14	100%		WHEN THE WASHINGTON
	0	Critical		Milestone	*		Manual Task	
	·	Critical Split		Summary Progress		and community of the co	Duration-only	
		Critical Progress	and the other statement of the control of the statement o	Summary	The state of the s	A STATE OF THE PARTY OF THE PAR	Manual Summary Rollup	in the state of th
		Task	And the best best and the second the latest de Landson II.	Project Summary	The second	Standarden Advantage	Manual Summary	Control of the second s
Property WR Masjid KedawangReport3		Split		External Tasks	Seal of the shall be seal	to a Service board office and	Start-only	. · · ·
	<b></b>	Task Progress	CALLES CRIMENS OF THE PARTY OF	External Milestone	<i>\( \)</i>		Finish-only	177
	<u> </u>	Baseline		Inactive Task			Deadline	ラ
	œ 	Baseline Split		Inactive Milestone	ć,			
	ω	Baseline Milestone	$\Diamond$	Inactive Summary	٨	>		
				Page 1				

Task Name		Duration	Start	Finish	% Complete 4 May '14	TWTF	11 May 14 S S M T W T F	S   S   M   T   W   1
3.0 Rekabentul	Rekabentult steel roof trusses	14 days	Sat 17/5/14	Sun 1/5/14	100%			
	Kerja pemasangan roof trusses	5 days	Mon 30/6/14	Sat 5/7/14	100%		æ	
>	Kerja pemasangan atap	3 days	Sur. 6/7/14	Tue 8/7/14	100%			
33 KERJA MEMBINA SILING	SINA SILING	9 days	Sun 6/7/14	Tue 15/7/14	31%			
>	Pasang kerangka kayu	5 days	Sun 6/7/14	Thu 10/7/14	100%			
Pasang silir	Pasang siling asbestos	4 days	Sat 12/7/14	Tue 15/7/14	%08			geriana. I
1	KERJA MEMBINA LANTA! & APRON	10 days	Wed 9/7/14	Sun 20/7/14	%46			
37 V Pasang acuan & BRC	uan & BRC	2 days	Wed 9:7/14	Thu 10/7/14	100%		-	-
<u>\</u>	Kerja Pasang longkang	3 days	Sat 12/7/14	Mon 14/7/14	100%			
	ti.	2 days	Tue 15/7/14	Wed 16/7/14	100%			
Kerja Lepas	Kerja Lepaan simen 20mm	3 days	Thu 17/7/14	Sun 20/7/14	%08			
KERJA MEMB	KERJA MEMBINA DINDING	22 days	Wed 16/7/14	Sun 10/8/14	71%		2	
Kerja pasar	Kerja pasang frame tingkap & pintu	4 days	Wed 16/7/14	Sun 20/7/14	100%			
Kerja mema	Kerja memasang bata & party wall	8 days	Mon 21/7/14	Tue 29/7/14	100%		n leer	
Kerja melepa dinding	pa dinding	8 days	Mon 21/7/14	Tue 29/7/14	80%			
	Kerja mengecaf dalam & luar	10 days	Wed 30/7/14	Sun 10/8/14	30%		,	
,	KERJA KEMASAN LANTAI, DINDING & PINTU		Wed 30/7/14	Tue 26/8/14	30%			
Pemasangan jubin	an jubin	10 days	Wed 30/7/14	Sun 10/8/14	30%			
Pernasanga	Pernasangan pintu & Rolier shutter	8 days	Mon 11/8/14	Tue 19/8/14	30%			
49 pemasangan grill	an griil	6 days	Wed 20/8/14	Tue 26/8/14	30%			
SO Pemasanga	nemasangan penutup longkang bgn	6 days	Mon 11/8/14	Sun 17/8/14	30%			** *
S1 KERJA BILIK AIK	AIR	13 days	Mon 11/3/14	Mon 25/8/14	30%			
52 Memasang	Memasang jubin dinding & lantai	6 days	Mon 11/8/14	Sun 17/3/14	30%			
53 Mamasang sinki	g sinki	4 days	Mon 18/8/14	Thu 21/8/14	30%			
54 Memasang	Memasang tandas duduk	3 days	Sat 23/8/14	Mon 25/8/14	30%			
55 KERJA-KERJA LUAR	JA LUAR	8 days	Mon 18/8/14	Tue 26/8/14	30%			-
56 Pasang lon	Pasang longkang & periutup	8 days	Mon 18/8/14	Tue 26/8/14	30%			
Memasang	Memasang laluan jalan kaki	8 days	Mon 18/8/14	Tue 26/8/14	30%			
58 KERJA BEKALAN AIR	ALAN AIR	9 days	Mon 18/8/14	Wed 27/8/14	71%		-	
9	Critical		Milestone	•		Manuai Task		
	Critical Split		Summary Progress			Duration-only		
	Critical Progress		Summary			Manual Summary Rollup	Up (Compression of the Compression of the Compressi	
	Task	AND SECTION OF AN EMPLOYED SECTION OF THE SECTION OF THE SEC	Project Summary	Y	White the section is the second	Manual Summary		
Project: JKR Masjid KedawangReport3	ort3 Split		External Tasks	a widering		Start-only	П	
	Task Progress	March Section of the	External Milestone	≎ О		Finish-only	п	
	Baseline		Inactive Task			Deadline	⇔	
	Baceline Split	37	Inactive Milestone	9				
	Saseline Milestone	0	Inactive Surrmary	ry v				
	rice de constante de companya de companya de serviça dos com dos com é, para e e como está con aporte dos esta	A STATE OF THE PARTY OF THE PAR	Fage 2	2				
								•

20 days Wed 30/7/14 4 days Sat 23/8/14 1 day Wed 27/8/14 V 1 day Thu 28/8/14	4 days Mon 18/8/14 Thu 21/8/14		100% 20% 100% 39% 30% 30% 100% 100% 0%	Thu 21/8/14 Sun 24/8/14 Tue 26/8/14 Wed 27/8/14 Thu 21/8/14 Tue 26/8/14 Wed 27/8/14 Thu 28/8/14 Thu 28/8/14 Thu 28/8/14 Thu 28/8/14 Thu 28/8/14	Mon 18/8/14 Sat 23/8/14 Mon 25/8/14 Wed 27/8/14 Mon 18/8/14 Sat 23/8/14 Wed 30/7/14 Wed 30/7/14 Wed 27/8/14 Thu 28/8/14	4 days 2 days 2 days 1 day 9 days 4 days 1 day 26 days 20 days 1 day 1 day		Pasang paip bekalan dalaman Pasang paip luaran & pili bomba Pasang tangki sambunagn bekalan SADA KERJA SISTEM KUMBAHAN mernibina lurang memasang paip VCP memasang tangki septik KERJA ELEKTRIK Pendawaian pernasangan lampu sambungan TNB
	2 days Sat 23/8/14 Sun 24/8/14 2 days Mon 25/8/14 Tue 26/8/14 1 day Wed 27/8/14 Wed 27/8/14 4 days Mon 18/8/14 Thu 21/8/14 4 days Sat 23/8/14 Thu 28/8/14 1 day Wed 27/8/14 Wed 27/8/14 26 days Wed 30/7/14 Thu 28/8/14 20 days Sat 23/8/14 Thu 28/8/14 1 day Wed 27/8/14 Thu 28/8/14 1 day Wed 27/8/14 Thu 28/8/14 1 day Wed 27/8/14 Tue 26/8/14 1 day Thu 28/8/14 Tue 28/8/14		%0	Thu 28/8/14	Thu 28/8/14	0 days		SERAHAN PROJEK SIAP
	2 days Sat 23/8/14 Sun 24/8/14 2 days Mon 25/8/14 Tue 26/8/14 1 day Wed 27/8/14 Wed 27/8/14 9 days Mon 18/8/14 Wed 27/8/14 4 days Mon 18/8/14 Tue 26/8/14 4 days Sat 23/8/14 Tue 26/8/14 1 day Wed 27/8/14 Wed 27/8/14		77%	Thu 28/8/14	Wed 30/7/14	26 days		EKTRIK
26 days Wed 30/7/14	2 days Sat 23/8/14 Sun 24/8/14 2 days Mon 25/8/14 Tue 26/8/14 1 day Wed 27/8/14 Wed 27/8/14 9 days Mon 18/8/14 Wed 27/8/14 4 days Sat 23/8/14 Thu 21/8/14 4 days Sat 23/8/14 Tue 26/8/14		30%	Wed 27/8/14	Wed 27/8/14	1 day		sang tangki septik
1 day Wed 27/8/14 26 days Wed 30/7/14	2 days Sat 23/8/14 Sun 24/8/14 2 days Mon 25/8/14 Tue 26/8/14 1 day Wed 27/8/14 Wed 27/8/14 9 days Mon 18/8/14 Wed 27/8/14 4 days Mon 18/8/14 Thu 21/8/14		30%	Tue 26/8/14	Sat 23/8/14	4 days		sang paip VCP
VCP 4 days Sat 23/8/14 vi septik 1 day Wed 27/8/14 v 26 days Wed 30/7/14	2 days Sat 23/8/14 Sun 24/8/14 2 days Mon 25/8/14 Tue 26/8/14 1 day Wed 27/8/14 Wed 27/8/14 9 days Mon 18/8/14 Wed 27/8/14		%09	Thu 21/8/14	Mon 18/8/14	4 days		ina lurang
4 days Mon 18/8/14  VCP 4 days Sat 23/8/14  i septik 1 day Wed 27/8/14 V 26 days Wed 30/7/14	aran & pili bomba       2 days       Sat 23/8/14       Sun 24/8/14         2 days       Mon 25/8/14       Tue 26/8/14         kalan SADA       1 day       Wed 27/8/14		39%	Wed 27/8/14	Mon 18/8/14	9 days		SISTEM KUMBAHAN
9 days Mon 18/8/14 4 days Mon 18/8/14 4 days Sat 23/8/14 1 day Wed 27/8/14 26 days Wed 30/7/14	aran & pili bomba 2 days Sat 23/8/14 Sun 24/8/14 2 days Mon 25/8/14 Tue 26/8/14		%0	Wed 27/8/14	Wed 27/8/14	1 day		unagn bekalan SADA
1 day Wed 27/8/14 9 days Mon 18/8/14 4 days Mon 18/8/14 4 days Sat 23/8/14 1 day Wed 27/8/14 26 days Wed 30/7/14	2 days Sat 23/8/14 Sun 24/8/14		. 100%	Tue 26/8/14	Mon 25/8/14	2 days	(9)	g tangki
2 days Mon 25/8/14 1 day Wed 27/8/14 9 days Mon 18/8/14 4 days Sat 23/8/14 1 day Wed 27/8/14 26 days Wed 30/7/14			20%	Sun 24/8/14	Sat 23/8/14	2 days	,	g paip luaran & pili bomba

		And Manager and Andreas and An	A STATE SECTION AND ASSESSMENT ASSESSMENT AND ASSESSMENT ASSESSME						A DESCRIPTION OF THE PROPERTY
Contact states		dr.		LJ	m	S			
Manual Task	Duration-orlly	Menual Summary Rolls	Manual Summary	Start-only	Fir-sh-only	Deadiine			A principal and the second sec
4	ounimannamen	Service and the service of the servi	Charles and the same of the sa	n farte ander and bilde extentible in above	♦		: `*		
Milestone	Summary Progress	Summary	Project Summary	External Tasks	External Milestone	Inactive Task	Inactive Milestone	inactive Summary	Page 3
		and the second s	The state of the s	www.men.ann.man.e.	The same with the season of th			$\diamond$	
Critical	Critical Split	Critical Progress	Task	Spliř	Task Progress	Baseline	Baseline Split	Baseline Milestone	and a supplied of control and the following of the supplied of
				JKR Masjid KedawangReports					
	with the state of	Manual Task  Milestone  Summary Progress  Output  Duration-only	Summary Progress aurimunimum Duration-only Summary Summary Rollup	Critical Split Summary Progress Critical Progress Critical Progress Summary Project Summary Project Summary	Cutical Split Summary Progress aurittumminante Summary Project Summary Froject Summary Cartering Summary Split Summary	Critical Split Critical Progress Critical Progre	Critical Split Summary Progress aurmannanum Critical Progress Summary Progress aurmannanum Summary Progress Critical Progress Summary Summary Progress Summary Progress Critical Progress Summary Progress Summary Progress Critical Progress Summary Progress Critical Progre	Critical Split Summary Progress aurmannmine Summary Progress aurmannmine Summary Progress aurmannmine Summary Progress aurmannmine Summary Project Summary Project Summary Project Summary Project Summary Project Summary Project Summary Split External Tasks External Milestone Split Inactive Task Progress Inactive Task Progress Inactive Milestone Split Inactive Milestone	Critical Split Summary Progress aurmunmmuno Summary Progress aurmunmmuno Summary Progress aurmunmmuno Summary Progress aurmunmmuno Summary Project Summary Progress aurmunmmuno Split External Milestone Split Inactive Milestone Split Inactive Milestone Inactive Milestone Inactive Milestone Inactive Summary Inacti