

PROGRAMME IN BUILDING SURVEYING DEPARTMENT OF BUILT ENVIRONMENT STUDIES AND TECHNOLOGY FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING UNIVERSITI TEKNOLOGI MARA PERAK BRANCH SERI ISKANDAR CAMPUS

HANDLING THE PROCESS OF INSTALLATION, TESTING AND COMMISSIONING OF THE EXTRA LOW VOLTAGE (ELV) – ACCESS CONTROL SYSTEM AT MANUFACTURING INDUSTRIES, BATU KAWAN, PENANG

SITI NADIAH BINTI OTHMAN FOAD (2018694844)

Bachelor of Building Surveying (Hons.)

PRACTICAL TRAINING REPORT

Jan 2022

PROGRAMME IN BUILDING SURVEYING DEPARTMENT OF BUILT ENVIRONMENT STUDIES AND TECHNOLOGY FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING UNIVERSITI TEKNOLOGI MARA PERAK BRANCH SERI ISKANDAR CAMPUS

HANDLING THE PROCESS OF INSTALLATION, TESTING AND COMMISSIONING OF THE EXTRA LOW VOLTAGE (ELV) – ACCESS CONTROL SYSTEM AT MANUFACTURING

Jan 2022

Practical Training Report is Fulfilment of The Practical Training Course

PREPARED BY

STUDENT'S NAME	:	SITI NADIAH BINTI OTHMAN FOAD
SIGNATURE	:	
UITM STUDENT NO	:	2018694844
DATE	:	JANUARY 2022

SUPERVISING LECTURER

SUPERVISOR'S NAME	:	SR. ZAHIR ZULKERNAIN
SIGNATURE	:	

)22
)

ACKNOWLEDGEMENT



First of all, I would like to thank ALLAH S.W.T and HIS messenger, Prophet Muhammad S.A.W. It is because of HIS blessing, I was managed to finish my Practical Industry Training which is to fulfil the requirement for the award of Bachelor in Building Survey (Hons). I had finally managed to finish up this internship with great enthusiasm and determination. All the time spent to do all the lifecycle of the real work in the construction industry as well as the installation of the material which is construction work.

Therefore, I would like to acknowledge with thanks, the individuals who had guided me and proactive support during my practical training. Firstly, I would like to thank my supervisor which is Mr. Alex Teh and another superior staff which are Mr. KM Tan, Mr. Ravi, Felix Tan, Zerlin Chooi, Teo Yee Zent and Mr. Syafiqq who had guided me on how to complete this practical training by giving proper guidelines. Furthermore, I would like to extend my gratitude to my lecturer, Sr Zahir Zulkernian who guide me to do the training industry report and advise me during my internship.

Lastly, I would like to thank my parents and friends who always prayed well for me and giving their time to hear my problems and continuous encouragement and support throughout my endeavour.

Thank you.

CONTENTS

AUTHOR'S DECLARATION i
CONFIRMATION OF PRACTICAL TRAINING PROJECT REPORT Error! Bookmark not defined.
ACKNOWLEDGEMENTii
LIST OF FIGURESv
LIST OF TABLEvi
1.1 COMPANY BACKGROUND1
1.2 SITE AND LOCATION
1.2.1 KEY PLAN
1.2.2 LOCATION PLAN
1.2.3 SITE PLAN
1.3 COMPANY BRIEF
1.4 ORGANIZATION CHART6
1.5 TRACK RECORD7
1.5.1 LIST OF PREVIOUS PROJECT9
2.1 INTRODUCTION OF BUILDING AUTOMATION SYSTEM
2.2 ELV SERVICES
2.2.1 CLOSED-CIRCUIT TELEVISION (CCTV)
2.2.2 ACCESS CONTROL SYSTEM 18
2.2.3 PUBLIC ADDRESS SYSTEM 19
2.3 CONCLUSION
3.1 INTRODUCTION
3.2 ADVANTAGES OF THE ACCESS CONTROL SYSTEM AT MANUFACTURING INDUSRIES
3.3 PROJECT INFORMATION & TEAM
3.4 SITE LOCATION
3.4.1 KEY PLAN
3.4.2 LOCATION PLAN
3.4.3 SITE PLAN
3.5 COMPONENT OF ACCESS CONTROL SYSTEM
3.6 METHOD STATEMENT
3.6.1 PURPOSE OF THE INSTALLATION
3.6.2 SCOPE OF THE INSTALLATION
3.6.3 PURPOSE OF TESTING AND COMMISSIONING
3.6.4 SCOPE OF TESTING AND COMMISSIONING

3.6.5 EQUIPMENTS	32
3.6.6 INSTALLATION PROCEDURE OF ACCESS CONTROL SYSTEM	36
3.6.7 INSTALLATION OF CARD READER	38
3.6.8 INSTALLATION OF SINGLE INTERFACE	39
3.6.9 INSTALLATION OF EXIT PUSH BUTTON	40
3.6.10 INSTALLATION OF DOOR CONTACT AND EM LOCK	41
3.6.11 PRE-TESTING AND COMMISSIONING WORK PROCEDURE	42
3.6.12 CABLE TESTING (FOR EACH PANEL)	43
3.6.13 TESTING AND COMMISSIONING WORK PROCEDURE	44
3.6.14 POST-TESTING AND COMMISSIONING WORK PROCEDURE	46
3.7 HIRARC ASSESSMENT FOR THE ELV- ACCESS CONTROL SYSTEM	47
3.8 FIRE SAFETY STRATEGY – EMERGENCY BREAKGLASS	49
4.1 INTRODUCTION	50
4.2 CHALLENGES OF THE ELV WORKS	50
4.2.1 CHALLENGES DURING THE DESIGN STAGES	50
4.2.2 CHALLENGES DURING THE TERMINATION WORK	52
5.1 CONCLUSION	53
5.2 RECOMMENDATION	53
REFERENCE	54
APPENDIX	56
1. CHECKLIST ACCESS CONTROL SYSTEM INSTALLATION	56
2. INSPECTION AND TEST PLAN OF THE ACCESS CONTROL SYSTEM	
INSTALLATION	58
3. PRE-COMMISSIONING OF ACCESS CONTROL SYSTEM	59
4. CHECKLIST SECURITY ACCESS CONTROL SYSTEM TESTING AND COMMISSIONING	60
5. INSPECTION AND TEST ACCESS CONTROL SYSTEM TESTING AND COMMISSIONING	63
6. AET SCHEMATIC DRAWING	64
7. GROUND AND FIRST FLOOR OFFICE DRAWING	65
8. GROUND FLOOR PRODUCTION	66
9. WORK SCHEDULE	67

LIST OF FIGURES

Figure 1. 1: Radical Internetwork Company Logo's and Certificate's	1
Figure 1. 2: Key Plan - Penang Island	3
Figure 1. 3: Location Plan - Bayan Lepas	3
Figure 1. 4: Site Plan – Radical Internetwork	4
Figure 1. 5: Radical Internetwork Main Office	4
Figure 1. 6: Radical Internetwork Organization Chart's	6
Figure 2. 1: Building Automation System	15
Figure 2. 2: CCTV	17
Figure 2. 3: Access Control System	18
Figure 2. 4: Public Address System	19
Figure 3. 1: Key Plan	25
Figure 3. 2: Location Plan	25
Figure 3. 3: Site Plan	
Figure 3. 4: Card Access	
Figure 3. 5: Alarm System	27
Figure 3. 6: Card Reader and Keypads	
Figure 3. 7: EM Lock	
Figure 3. 8: Field Panel / Controller	29
Figure 3. 9: Fluke DTC-1800 Cable Analyzer	
Figure 3. 10: Splicing Machine	
Figure 3. 11: Digital Multimeter	33
Figure 3. 12: Ladder	33
Figure 3. 13: Scaffolding	33
Figure 3. 14: Commissioning Laptop	
Figure 3. 15: Safety Shoe	
Figure 3. 16: Safety Helmet	
Figure 3. 17: Fluorescent Vest	
Figure 3. 18: Safety Glasses	35
Figure 3. 19: Hand Crimper Tool	35
Figure 3. 20: As per drawing	
Figure 3. 21: Site Location (Ready for installation)	
Figure 3. 22: Installation of the Cabling	
Figure 3. 23: Installation of Card Reader	

Figure 3.	24: Termination	38
Figure 3.	25: Complete Termination	38
Figure 3.	26: Controller (inside)	39
Figure 3.	27: Controller (installation)	39
Figure 3.	28: Installation of exit push button	40
Figure 3.	29: Exit Push Button	40
Figure 3.	30: Door Contact and EM Lock as per drawing	41
Figure 3.	31: Installation of Door Contact and EM Lock at the site	41
Figure 3.	32: Installation of Door Contact and EM Lock at the site (close view)	41
Figure 3.	33: Testing & Commissioning Checklist	42
Figure 3.	34: Ensure the Access Control Panel are connected to the network switch.	42
Figure 3.	35: Check all cable termination	43
Figure 3.	36: Testing and commissioning result	43
Figure 3.	37: Testing the device	44
Figure 3.	38: System Demonstration	46
Figure 3.	39: Emergency Breakglass	49
Figure 4	1. Card Access Reader Coordination	50

i igule 4		U
Figure 4	. 2: Fiber termination work	2

LIST OF TABLE

Table 1. 1: Company's brief	5
Table 1. 2: Radical Internetwork Expert	8
Table 3. 1: Project Information	24

CHAPTER ONE

INTRODUCTION

1.1 COMPANY BACKGROUND



Figure 1. 1: Radical Internetwork Company Logo's and Certificate's

Radical Internetwork Sdn Bhd (RISB) was established in 2010, have always been one of the top design and build network solutions providers in Malaysia. With professional certification, license and insurance, RISB specialise in virtually every aspect of communications infrastructure and management service, from structured cabling systems to ELV (Extra Low Voltage). RISB clients' range from small to medium enterprises to nationally based corporations and institutions from different industries.

Many of our clients have continued to support us since we first started out. We assist small to medium enterprises, large corporations, various government departments and nationally based corporations and institutions. We pride ourselves in our commitment to excellence in delivering trustworthy and high-quality solutions for all your communication needs. RISB is a registered G5 company under the Construction Industry Development Board (CIDB) and also ISO 9001:2015 certified

Most of our clients are mostly System Integrators, IT Solutions Consultants, Building and M&E Consultants as well as Computer Retailers who are looking for a professional cabling contractor for their projects. RISB undertakes first-time installations, upgrades to existing installations, and also ongoing maintenance, where we assist our customers with adds, moves and changes to their communications infrastructure. All of our installations are pro-actively managed and overseen by at least one operations manager and a project leader or team leader. These experienced operational personnel not only provide our customers with project feedback, but they also take responsibility for delivering all project-related documentation and warranties.

With a commitment to excellence and reputation for quality, our experts have the ability and expertise to assist you with the design and installation of your Data, Voice, Fiber-optics, Structured Cabling, Telephone Systems, Audio/Video, Security and Surveillance Networks. We offer a one source solution for all your communication needs.

1.2 SITE AND LOCATION

1.2.1 KEY PLAN




Figure 1. 2: Key Plan - Penang Island

1.2.2 LOCATION PLAN




Figure 1. 3: Location Plan - Bayan Lepas

1.2.3 SITE PLAN



Figure 1. 4: Site Plan – Radical Internetwork



Figure 1. 5: Radical Internetwork Main Office

1.3 COMPANY BRIEF

This company brief is describing the compan	v information
The company she is describing the company	y milorination.

CIDB Grade:	G5 Registration
Company no:	201001041461 (925389-P)
Category:	B04, CE21, E14, M15
Quality Management	ISO 9001 – 12750
system:	ISO 9001 - 1066
Founded:	2010
Headquarters:	Bayan Lepas, Malaysia
Key People:	KM Tan (Managing Director), Felix Tan (Operation Director)
Num. of Employees:	< 50 employees
Website:	https://www.risb.net/
No Tel:	+604 637 0811
Email:	info@risb.net
Area Served:	Malaysia
Services Provided:	Structured Cabling, Extra Low Voltage (ELV), Video
	Surveillance, Fiber Optics, Energy Management, Cable
	Management
Vision:	To be a respected design and build network solutions
	company that delivers.
Mission:	To empower our clients and partners with high-valued
	products in IT infrastructure, while maintaining our passion
	and principles as we continue to grow

Table 1. 1: Company's brief

1.4 ORGANIZATION CHART




Figure 1. 6: Radical Internetwork Organization Chart's

1.5 TRACK RECORD

We are one of the fast growing and experienced ELV Contractor in Penang. Our directive is to provide quality ELV installation and engineering expertise to the government and private sector. Radical internetwork are specialises in virtually every aspect of communication infrastructure design and installation from CAT5e, CAT6, CAT7, Data Cabling and Fiber Optic to an entire suite of structured cabling redesign and ELV services. We have extensive knowledge and practical experience with industry, developers, and governments.

We're well-equipped to deal with the difficulties of fast evolving technology, increased competition, and shifting economic conditions. We have highly qualified individuals with extensive industry knowledge to handle a variety of project natures.

Structured Cabling System	 Data cabling for Cat5e, Cat6, Cat6A and Cat7 solutions Design, Installation, Testing and Commissioning Cable Management Works
	 Cable Management Works Maintenance Cabling Works (Move, Add and Changes to existing infrastructures) Cable Certification Reporting
Fiber Optic Enterprise Network	 Multimode and Singlemode System Air-Blown Fiber and Microduct Solutions Complete Fiber Optic Splicing, Interconnect and Cable Management OLTS and OTDR Fiber Certification Testing
ELV (Extra Low Voltage)	 Network CCTV Cameras and Video Encoders Security Access Control System Network LAN/WAN POE Switches/Routers Public Address System Digital Communication System Wireless Connectivity Solutions SMATV/IPTV Infrastructure

Enclosure, Cabinet and Cable	Complete solution for cabinets and containment
Management	systems for data centers, server rooms and office
	spaces
	Cable pathways and wire mesh tray design and installation
	 Adds and changes to connections for future networking growth and cabling demands
Energy Management System	Building Automation and Control Systems
	Hotel Room Controllers (RCU/GRMS)
	Power Management Systems
	EV Charging Stations


Table 1. 2: Radical Internetwork Expert


1.5.1 LIST OF PREVIOUS PROJECT

YEAR	PROJECT	SCOPE OF WORK	INDUSTRY
	Teleperformance Bayan Baru, Penang	Supply And Install Structured Cabling for Data and Voice	Corporate Office
	Prince Of Wales Island International	Supply And Install Structured Cabling for Data and Voice	Educational
	School		
	Park Royal Hotel Langkawi, Kedah	Supply And Install Structured Cabling for Data and Voice and	Hospitality
		ELV System	
	Gurney Ascott Hotel, Penang	Nominated Sub Contractor (NSC) For ELV Supply and Install	Hospitality
		Contract	
	Towam Sdn Bhd Batu Kawan, Penang	Supply And Install Structured Cabling for Data and Voice	Manufacturing
	Plexus Manufacturing Sdn Bhd	Supply, Install and Maintenance for Add, Move, Changes to	Manufacturing
		Structured Cabling System	
2020	TF-AMD Penang	Supply, Install and Maintenance for Add, Move, Changes to	Manufacturing
		Structured Cabling System	
	Lumileds, Penang	Supply, Install and Maintenance for Add, Move, Changes to	Manufacturing
		Structured Cabling System	
	Ansell, Kedah	Supply and Install Structured Cabling for Data and Voice	Manufacturing
	TreeO by Hunza High Rise Residential,	Supply & Install FTTH and ELV Equipment	Residential
	Penang		
	Penang Hill (Bukit Bendera P.Pinang	Supply and Install Structured Cabling for Data and Voice	Tourism
	NUR Power, Kulim Kedah	Commissioning and Testing of Fiber Optic Cabling for SCADA	Utilities

YEAR	PROJECT	SCOPE OF WORK	INDUSTRY
	Teleperformance Bayan Baru, Penang	Supply and Install Structured Cabling for Data and Voice	Corporate Office
	KDU University Batu Kawan, Penang	Nominated Sub Contractor (NSC) for ELV Supply and Install	Educational
		Contract	
	Quay Hotel (The Prestige)	Supply and Install Structured Cabling for Data and Voice	Hospitality
	Georgetown, Penang	Access Control System and CCTV NVR Servers	
	Park Royal Hotel Langkawi, Kedah	Nominated Sub Contractor (NSC) for ELV Supply and Install	Hospitality
		Contract	
2018	VAT Malaysia Sdn Bhd Batu Kawan,	Supply and Install Structured Cabling for Data and Voice	Manufacturing
-	Penang		
2019	Plexus Manufacturing Sdn Bhd	Supply, Install and Maintenance for Add, Move, Changes to	Manufacturing
		Structured Cabling System	
	TF-AMD Penang	Supply, Install and Maintenance for Add, Move, Changes to	Manufacturing
		Structured Cabling System	
	Hospital Pulau Pinang	Supply and Install Structured Cabling for Data, Voice and	Medical
		ELV Systems	
	Hospital Seberang Jaya	Supply and Install Structured Cabling for Data, Voice and	Medical
		ELV Systems	
	Intel KM6 Kulim, Kedah	Supply & Install PA Systems	Semiconductors














CHAPTER TWO

LITERATURE REVIEW

2.1 INTRODUCTION OF BUILDING AUTOMATION SYSTEM




Figure 2. 1: Building Automation System

As stated by Thomas Novak et al (2007), Building automation and control systems (BACS) are an essential component of today's automated structures. They are increasingly in charge of duties impacting people's safety, security, and health. As a result, the corresponding technology is expected to function consistently, securely, safely, and efficiently. Functional safety and system security (short for safety and security) of both network nodes and communication protocols are crucial elements of such a BACS. Until recently, little effort has been taken to establish a life cycle for a safe and secure BACS, which outlines requirements for the various stages of a BACS's product life. A special emphasis is placed on the similarities between the development of safety and security systems in order to benefit from these similarities in development.

According to Morris Stelcner (2000), A building automation system (BAS) provides heating, ventilation, and air conditioning (HVAC) control, as well as management services, by utilising direct digital-control (DDC) technology. Intelligent building functions are handled by DDC systems, which rely on suitable sensors and are administered by a software-based facility-management system for centralised control. The building automation components of an intelligent building are interconnected and

capable of communicating with one another. Sensors collect and communicate data to controllers, which assure continuous and ideal conditions within the building. Automated tools identify issues, diagnose performance, and take necessary steps. An integrated BAS is intended to optimise operations across all building control systems while also optimising energy usage, directing maintenance activities, and reporting building performance. The objective is to meet the occupants' comfort, health, and safety demands at the lowest possible cost.

2.2 ELV SERVICES

ELV System for Buildings is an abbreviation for Mechanical and Electrical (M&E) Extra-Low Voltage System that is used in residential and commercial buildings to improve control and security. ELVs are systems that operate on low voltages (within 50V AC or 120V DC).

According to the International Electrotechnical Commission (1996), ELV is the terminology used in the construction world in an attempt to electrically define all the systems in a building which need electricity to run but are not part of the building's main electrical system. They do not specify a specific system, but rather refer to a wide variety of seemingly unrelated systems that operate within certain voltage levels. ELV covers all the new modern technologies that are increasingly becoming must-have systems in every building such as data network, CCTV, fire alarm systems, public address systems, audio/video solutions, access control and intrusion detection systems, home automation, WIFI and others.

2.2.1 CLOSED-CIRCUIT TELEVISION (CCTV)



Figure 2. 2: CCTV

Surveillance cameras with closed-circuit television also known as CCTV play an important part in modern police and crime prevention (Welsh & Farrington, 2009). According to Vacharee Prashyanusorn et al (2010), Closed-circuit Television (CCTV) system are now widely used and can be found in building, shop, manufacturing industries, citizens' houses and others. This system can aid in the reduction of crime and the identification of suspects.

CCTV evidence is routinely reviewed by police all around the world in the course of investigations. Officers create event timelines, look for people of interest (such as missing people, victims, and witnesses), and identify suspects as mentioned by J.P. Davis (2018). Lynsey (2005) stated that another function of the CCTV is to monitor so that is no serious accidents occur within the shortest time indirectly can manage to identify the source of the problem. CCTV also used to track the danger and act as the source of the evidence if there is any accident occur.

2.2.2 ACCESS CONTROL SYSTEM



Figure 2. 3: Access Control System

According to Tarun (2014), access control systems are the electronic systems that are designed to control through a network, and they should have access to a network. Access Control System detect, recognizes authenticates and allows a person's admission into the premise, providing total protection and assuring the system's security.

Access control is concerned with determining the permitted actions of genuine users and mediating every attempt by a user to access a system resource. A given information technology (IT) infrastructure can deploy access control systems in a variety of locations and at various levels. Access control is used by operating systems to safeguard files and folders. Systems for managing databases Access control is used by DBMS to manage access to tables and views. Most commercially available application systems provide access control, which is typically independent of the operating systems and/or database management systems on which they are deployed (NISTG, 2006).

2.2.3 PUBLIC ADDRESS SYSTEM



Figure 2. 4: Public Address System

A public address system is made up of electrical equipment that considerably amplifies a speaker's voice so that it may reach a far bigger audience than he could talk to unaided as mentioned by I.W Green and J.P Maxfield (1923). This system amplifies vocals, musical instruments, other sound sources, or recorded sounds or music. The sound enhancement system can be used in public places where announcers, performers, and others need to hear in a distant or large area. A PA system may include multiple microphones or other sources, a mixer to combine and change multiple sources, and multiple amplifiers and speakers to increase volume or spread the sound further. Both the PA system and the intercom system are commonly used in emergency communications systems.

According to Sara C. Folta et al (2006), PA system is used for the daily announcement. However, Neiger B et al (2002) mentioned that the PA system were used in conjunction with signs to help promote the lower price items. PA announcements have also been used as part of larger social marketing interventions in anyplace such as school, shopping mall and other. PA System also used in an emergency term for example to announce the missing of children / thief / fire occur.

2.3 CONCLUSION

Jean-Philippe Vasseur and Adam Dunkels (2010), to conclude, building automation system can link with different functional systems include the ELV services which is to take action to do immediately. Also, it has many benefits on the intelligent building because of energy saving, cost reducing and good monitoring. It provides a better-quality life from the application of the system to be successful. In the future, the technology of the building automation system will become mature, more reliable and less expensive. It will integrate not only in the intelligent building, but it also will apply on the traditional building to change the quality of environment for all people in their life.

CHAPTER THREE

CASE STUDY: ACCESS CONTROL SYSTEM AT MANUFACTURING INDUSTRIES, BATU KAWAN, PENANG.

3.1 INTRODUCTION

Manufacturing industries are those that engage in the transformation of goods, materials or substances into new products. The transformational process can be physical, chemical or mechanical. Manufacturers often have plants, mills or factories that produce goods for public consumption. Machines and equipment are typically used in the process of manufacturing.

Factories lie at the core of the manufacturing industry and are often targeted by opportunist criminals for several reasons that include high-value raw materials, equipment, and machinery inside them, their large size making it difficult to maintain complete visibility throughout the site, and the absence of factory security systems. Crime against the manufacturing industry has always been an issue, disrupting not just the day-to-day factory operations but also adversely affecting their output and contribution to the economy.

Failing to secure premises against unauthorised access may result in theft, antisocial behaviour, and accidents that can harm the people inside and disrupt the flow of operations. Unauthorised access is when an employee or member of the public enters an area that is off-limits to them. It can be done using various means such as entering through an unlocked door, using stolen keys, breaking down a weak door, tailgating, or convincing an authorised party to allow access.

Regardless of how it is done, it can have disastrous consequences for a business and its productivity, and in the case of factories, which are typically large in size, intrusions can easily go undetected until after the damage has been done. Manufacturers and factory owners want a realistic solution for controlling and managing access across the site without relying on keys, which are easily lost, stolen, or copied.

3.2 ADVANTAGES OF THE ACCESS CONTROL SYSTEM AT MANUFACTURING INDUSRIES

Access control systems are keyless entry systems that permit or restrict access to a property or a specified area inside the property using a number of authentication techniques. Access cards, codes, key fobs, biometrics, and smart access are some of the most often used authentication mechanisms. Access control systems enable you manage and regulate access while also providing a slew of additional advantages, such as:

• DETECTING AND PREVENTING INTRUSIONS

Intruders can take any form – workers, employees, visitors, and strangers – and because factories have a large number of people coming and going all day, it is critical for factory owners and managers to implement an effective access control system that not only detects intrusions but also prevents them from occurring in the first place.

CONTROLLING WHO HAS ACCESS TO THE SITE

Factory owners face the challenge of having to manage and control access for many employees and visitors within the premises, all of whom have specific access privileges for certain areas of the factory. Access control systems can be used to customise access permissions according to each individual's needs, allowing the factory owners and managers to control who uses which door of the factory and at what time of the day or night.

• FACTORY AND EQUIPMENT SAFETY

To prevent accidents and injuries, factories, particularly those operating in hazardous settings and with risky equipment and machinery, must guarantee that only trained and authorised employees have access to the primary production area.

• DETERRING CRIMINAL ACTIVITY AND THEFT

Factory and manufacturing plants, like other commercial buildings, confront the ongoing issue of dealing with crime and security risks such as theft, invasions, vandalism, and even burning. Because of the tracking feature that comes with access control systems, it is possible to detect and prevent criminal activity, as well as make it more difficult for criminals to bypass the systems due to a high level of control and features such as two-factor authentication.

• HISTORY LOGGING AND REPORTS

Modern access control systems allow you to track individual access and record every time access is given or refused to them. These thorough reports properly state the user's details, as determined by the authentication credentials used, as well as the time and location of the access request.

• ELIMINATING THE NEED FOR KEYS

Using traditional keys can also be risky since they have the potential to be easily copied, as compared to access control systems that are not only efficient, practical, and easy to use, but also safer and much more secure.

3.3 PROJECT INFORMATION & TEAM

Main Project Title	CADANGAN KERJA-KERJA PENGUBAHSUAIAN
	KILANG SETINGKAT, PEJABAT DUA TINGKAT DI
	ATAS LOT PT 6013, JALAN CASSIA SELATAN 6/4,
	TAMAN PERINDUSTRIAN BATU KAWAN, MUKIM 13,
	SEBERANG PERAI SELATAN
Sub-Con Project Title	SUPPLY, INSTALLATION, TESTING AND
	COMMISSIONING OF EXTRA LOW VOLTAGE (ELV)
	SERVICES
Client	Tetuan Applied Engineering Technology (M) Sdn Bhd
Contract Amount	RM 1,504,903.25
Type of Contract	Turnkey Contract / Design and Build
Contract Period	12 Months
Civil & Structural Engineer	Perunding LW (PG0438671-T)
	A-01-12 Sea View Tower, Jalan Harbour Place,
	12100, Butterworth, Penang.
	Email: <u>eweetan@gmail.com</u>
Mechanical & Electrical	O & A Consult Sdn Bhd (817575-V)
Engineer	381A-2-10, Jalan perak,
	11600, Penang.
	Email: <u>oa.consult@gmail.com</u>
ELV Contractor (Sub)	Radical Internetwork Sdn Bhd (925389-P)
	No. 7, Persara Mahsuri Lima, Taman Melati Jaya,
	11950, Bayan Lepas, Penang.
	Email: <u>info@risb.net</u>
Quantity Surveyor	Kuantibina Sdn Bhd (0119764-M)
	No. 2.1, 2 nd Floor, 405, Jalan Burma,
	Pulau Tikus, 10350, George Town, Penang.
	Email: <u>kuantibina@gmail.com</u>
Main Contractor	IFC Solution Sdb Bhd (754564-M)
	Menara Perdana Level 09-04 & 05,
	101, Jalan Gurdwara, 10300 Penang.
	Email: <u>ifc@ifcgroup.com.my</u>

Table 3. 1: Project Information

3.4 SITE LOCATION

3.4.1 KEY PLAN




Figure 3. 1: Key Plan

3.4.2 LOCATION PLAN



Figure 3. 2: Location Plan

3.4.3 SITE PLAN




Figure 3. 3: Site Plan

3.5 COMPONENT OF ACCESS CONTROL SYSTEM

In many various types of buildings, access control systems are a vital aspect of improving security. These systems are the most effective means of monitoring and restricting access to a full building or specific areas inside a facility. Although these systems appear to be simple, they are made up of several separate components. Below is the components of an access control system.

No	Items	Description
1	Access Card	Keys will be replaced by access
		cards. People will use their access
		cards to obtain entry to the building
		or specific area of the building by
	000	scanning them. Each access card will
	and a second of the second sec	have its own unique code, allowing
	0005720000 025.15072	user to simply regulate access,
		turning it on and off at various times
		or in different regions of the facility.
	Figure 3. 4: Card Access	Access cards are often the size of a
		credit card, making them convenient
		to carry around and store in a wallet.
4	Alarm system	Fire alarms, burglary alarms, and
	See 18	intrusion detection alarms are often
		integrated with access control. If an
		unauthorized person attempts to
		enter the doors controlled by electric
		lock hardware, your access control
	WARNING LIGH	system can signal the alarm to go off.
	The source and a series and a	In the event of an emergency like a
	1 1	fire, in addition to sounding an alarm,
	Figure 3. 5: Alarm System	your access control system can
		temporarily turn off locks that might
		impede quick exit from a building.

2 Card Readers and Keypads	The card reader is the device that
	reads access cards and grants
	access to the user. The number of
	card readers in an access control
	system will be determined by the
	number of entrances to which you
	want limited access. Card readers
	are normally positioned on or next to
(±) (±) (±) (±)	the door that they control.
2820	Another method of entrance is by
	access control keypads. Instead of
	scanning an access card, user use a
	numeric keypad to enter a code. For
	an extra layer of security, a door
HIKVISION	might have a card reader and a
	keypad, requiring an access card
Figure 3. 6: Card Reader and Keypads	and a correct passcode in order to
	gain entry.
3 Electromagnetic Lock	The EM Lock actually locks and
	unlocks the doors is a part of the
	access control system as well. EM
	Lock will electronically unlock door
	after a touch a access card or keypad
	code entry, and electronically lock
	the door again when it closes.
8	
ŝ.	
8	
Figure 3. 7: EM Lock	
Figure 3. 7: EM Lock 5 Field Panel / Controller	Field panels are the control panels
	Field panels are the control panels that connect all other parts of your
	that connect all other parts of your



process access control activity for the whole building. The number of panels will be determined by the size of the building, the size of the system, and the extent to which the system is used. Field panels are typically installed in telephone, electrical, or communication closets.

3.6 METHOD STATEMENT

3.6.1 PURPOSE OF THE INSTALLATION

This Installation method statement covers the Guidance of Installation of the Access Control System which will be installed in the project.

The Access Control System Includes the following:

- Control Panel with Card Reader Modules and Power Supply
- Field Devices (Card Reader, Electromagnetic Lock, Door Contact, Break Glass, Push Button)
- Client / Server Workstation
- Connection to LAN
- Integration with CCTV system
- This procedure is to be read in conjunction with relevant Operators Manual & User's guide.
- SUPPLIER's Engineer will carry out the testing and commissioning of the Access Control Panel along with the MEP sub-contractor commissioning team.

3.6.2 SCOPE OF THE INSTALLATION

This document details the Security access control system Installation for Implementation proposed to the project as follow:

- Preparation of work
- > Delivery and inspection upon arrival of material at site.
- Installation & Inspection of the system.

3.6.3 PURPOSE OF TESTING AND COMMISSIONING

This Commissioning Method Statement covers the Guidance of testing & commissioning of Access Control System in accordance with the approved project quality plan and relevant system specifications.

The Access Control System Includes the following:

- Control Panel with Card Reader Modules and Power Supply
- Field Devices (Card Reader, Electromagnetic Lock, Door Contact, Break Glass, Push Button)
- Client / Server Workstation
- Connection to LAN
- Integration with CCTV system
- 1.1 This procedure is to be read in conjunction with relevant Operators Manual & User's guide.
- 1.2 SUPPLIER's Engineer will carry out the testing and commissioning of the Access Control Panel along with commissioning team.
- 1.3 Purpose of this manual to ensure the methods used for Testing & Commissioning of Access Control described above are correct, acceptable and in line with the consultant quality system procedures to achieve the optimum results.

3.6.4 SCOPE OF TESTING AND COMMISSIONING

In this section will be cover the details of the Access Control system testing and commissioning procedures, for Implementation as follow:


- Pre-commissioning procedure
- > Testing and commissioning of the system.

NO	EQUIPMENT	DESCRIPTION
1	Fluke DTC-1800 Cable Analyzer	Used to test the strength and connectivity of Cat6. Certify multimode and singlemode fiber
	Analyzer	
2	Splicing Machines	Fusion splicing a machine is used to precisely align the two fiber ends then the glass ends are fused or welded together using some type of heat or electric arc. This produces a continuous connection between the fibers enabling very low loss light transmission.
	Figure 3. 10: Splicing Machine	
3	Digital Multimeter for Voltage and Continuity Tests	

3.6.5 EQUIPMENTS

		A continuity test is a quick check to see if a circuit is open or closed. Only a closed, complete circuit (one that is switched ON) has continuity. During a continuity test, a digital multimeter sends a small current through send a small current through the circuit to measure resistance in the circuit.
	Figure 3. 11: Digital Multimeter	
4	Ladder Figure 3. 12: Ladder	Ladder is used for a person to climb on it to do some-work at a higher place.
5	Scaffolding Figure 3. 13: Scaffolding	Temporary platform used to elevate and support workers and materials during the construction, repair or cleaning of a structure or machine.

6	Commissioning Laptop	
		Used to ensure that all systems and components of a building is functioning well.
7	Figure 3. 14: Commissioning Laptop	
7	Safety Shoe	Protect feet from foot injuries and prevent exhaustion.
	Figure 3. 15: Safety Shoe	
8	Safety Helmet	Protect the user's head against: impact from objects falling from above, by resisting and deflecting blows to the head.
	Figure 3. 16: Safety Helmet	
9	Fluorescent Vest	Allow the wearer to be seen and to alert all that a person is present especially in a low visibility situation.
	Figure 3. 17: Fluorescent Vest	



3.6.6 INSTALLATION PROCEDURE OF ACCESS CONTROL SYSTEM




- Drawing for installation of Access Control System shall be approved and shall be coordinated with other services.
- 2. Room clearance & proper access shall be provided as per approved program.
- Location/ area shall be ready for site installation. Prior to the installation, the area where the items to be installed shall be inspected to ensure architectural works and finishing are complete and area is free from dust.
- 4. Wall or ceiling mounting of the product should follow the instructions for the mount used and use approved installation practise appropriate for the structure and material the mount is being attached to.
- 5. Prior Installation, check all cabling as per wiring detail drawings.
- Mark the device / panels location and leave enough length of cable at both ends for termination.
- During installation, drilling operation is required on the wall with proper marking.
- 8. Check the power and control wiring at panel end.
- At panel end make the proper insulation to the wiring to protect insulation to the wiring to protect from cable damage,



Figure 3. 20: As per drawing



Figure 3. 21: Site Location (Ready for installation)



3.6.7 INSTALLATION OF CARD READER

INSTALLATION OF CARD READER

- Exact location of the card reader shall be as per approved Access Control System device Layout Plan.
- The height of the card reader shall be as per approved Access Control System Device Layout Plan.
- Remove mounting plate from the Card reader and fix into concealed back box using screw proper hardware.
- 4. Pull out the field wiring from back box through card reader mounting plate hole.
- 5. For termination, stripe the cable with wire stripper then twist the cable and screw it into the card reader terminal strip as per typical wiring detail diagram.
- Push back all the excess cables into the concealed back box and fix the card reader in the mounting plate.



Figure 3. 23: Installation of Card Reader




Figure 3. 24: Termination



Figure 3. 25: Complete Termination

3.6.8 INSTALLATION OF SINGLE INTERFACE

SINGLE READER INTERFACE

- Exact location of the single reader interface shall be as per approved drawing.
- 2. Single reader interface will be installed as per the access control system approved shop drawing and as per installation manual.
- Install appropriate enclosure power supply onto the wall above false ceiling as mentioned in the approved drawing.
- Fix the single reader interface inside the enclosure. Ensure all the screw fastened and SRI is installed perfectly.
- 5. Bring all the cables from conduit / trunking into the enclosure and then take them out for labelling and termination.
- For termination, stripe the cable with wire stripper then twist the cable and screw it into the card reader controller terminal strip as per typical wiring detail diagram.
- Push back all the excess cables into the concealed back box and fix the card reader controller in the mounting plate.



Figure 3. 26: Controller (inside)



Figure 3. 27: Controller (installation)

3.6.9 INSTALLATION OF EXIT PUSH BUTTON

INSTALLATION OF EXIT PUSH BUTTON

- The request to exit button shall be installed on the secure side of the door.
- 2. The final location of the RTE shall be as per the approved Access Control system layout drawing
- The final mounting height of the RTE shall be as per the approved Access Control System layout drawing.
- Pullout the cable from the 3x3 back box installed embedded on the wall. Terminate the appropriate cableon the RTE and mount the RTE on the 3x3 backbox.
- All the labelling of the devices and cables shall be in acccordance with the approved Access Control layout drawing.



Figure 3. 28: Installation of exit push button



Figure 3. 29: Exit Push Button

3.6.10 INSTALLATION OF DOOR CONTACT AND EM LOCK

INSTALLATION OF DOOR CONTACT AND EM

- Door are monitored by door contact used different types for timber and glass doors.
- The cabled part for door contact will be installed on the door frameand the moving part of the door contacr on the door shutter.
- The final location and mounting distance from the door frame and door type will be as per the approved typical installation drawings.
- 4. All the labelling devices and cables shall be accordance with the access control layout drawing.





Figure 3. 30: Door Contact and EM







Figure 3. 31: Installation of Door Contact and EM Lock at the site



Figure 3. 32: Installation of Door Contact and EM Lock at the site (close view)

3.6.11 PRE-TESTING AND COMMISSIONING WORK PROCEDURE



14. Access Control System should be interface with F.A.S. & C.C.T.V.

Page | 42

3.6.12 CABLE TESTING (FOR EACH PANEL)

CABLE TESTING WORK

AIM:

IMAGES

- Access Control Panel to the Field Devices such as Card Readers, Push Button, Break Glass, Power Supply unit, Network Switch and Electro Magnetic Locks etc. must the tested.
- Ensure the Power Cable Tests between Panel and Power Supply unit and Electro Magnetic Lock to the Power Supply units.

1. Power Up

- 1. Check Mains (PE,N,L) cables
- 2. Check Mains Voltage.
- 3. Check all cable termination.
- 4. Energise the incoming Mains Supply to Control Panels.



Figure 3. 35: Check all cable termination



Figure 3. 36: Testing and commissioning result

3.6.13 TESTING AND COMMISSIONING WORK PROCEDURE

TEST	ING AND COMMISSIONING WORK	IMAGES
Aim:	Functional Check	
1.	Turn-On the Power Supply (Must be equipped	
	with Battery) of Main Access Control Panel and	
	check the faulty notices.	
2.	Use Multimeter and check the output voltage of	
	the Power Supply unit for the ACS Panel and	
	Field Devices.	
3.	Install the Access control software in PC/Server	
	and start communicating the Access Control	
	Panel through the live Network.	
4.	Install, Configure the SQL Server for the	
	Access Database.	
5.	Start Configuring the Access Control Panel and	
	Field devices through the live Network	Figure 3. 37: Testing the device
6.	Once the Access Controllers are	
	communicated, and then assign all the	
	parameters.	
7.	Start the testing with the field Devices by:	
a.	Pressing the Push Button to check the Door	
	Operation through the Magnetic Lock.	
b.	Break Glass to check the Door Operation	
	through the Magnetic Lock & Alarm Generation	
	in the PC.	
C.	Flashing the Smart Card into the Card Readers	
	to check the Door Operation through the	
	Magnetic Lock.	
8.	Ensure all the Field Devices (Card Reader,	
	Push Button, Door Contacts, Break Glass, and	
	Power Supply Units) and Controllers are	
	working properly.	
9.	Ensure Interlocking with Fire Alarm system is	
	verified.	
10.	Ensure all alarms generated are noticed in the	
	graphic loaded monitoring PC/Server.	

 interface with C.C.T.V. system. 12. Ensure from the software that locking hardware functioning correctly. 13. Ensure the I/O configuration is done as per the requirements in the Software. 	
12. Ensure from the software that locking hardware functioning correctly.13. Ensure the I/O configuration is done as per the	
functioning correctly. 13. Ensure the I/O configuration is done as per the	
13. Ensure the I/O configuration is done as per the	
•	
14. All the doors and door equipment's is Label as	
per approved drawings in the graphic loaded	
monitoring PC/Server.	
15. Verify that all the door opening status is	
displayed in the PC/Server.	
16. Ensure all events are report back to the PC	
where Access Control Software installed	
17. Configure the Redundant Server and connect	
to the LAN.	
18. Monitor the Software functionalities (PC/Server	
related) and its operations.	
Task: Battery Connection	
Aim: Functional Check	
Note: the batteries must be connected before the	
mains power.	
Note: the control panel will not operate on batteries	
until the mains power has been applied.	
1. Connecting the batteries to the Control Panel	
should only be performed after the wiring	
checks have been completed successfully.	

3.6.14 POST-TESTING AND COMMISSIONING WORK PROCEDURE

PC	OST-TESTING AND COMMISSIONING	IMAGES
W	ORK	
TA	SK: System Demonstration	
re	otes: After the successful commissioning the sults will be recorded on the testing and ommissioning sheets. After the successful completion of testing & commissioning the system will be ready to be demonstrated to the facility management team and all concerned parties.	
2.	During this period SUPPLIER engineer will assist the involved parties to operate and familiarise with the system.	Figure 3. 38: System Demonstration
3.	All operations will be carried out by the operators and facility team in this period until they are able to handle the system without any doubts.	
4.	One day demonstration will be provided by SUPPLIER engineer and next 3 days will be assumed as familiarisation period to the concerned parties. Any doubts or clarifications they may require to be clarified in these days will be done by SUPPLIER engineer	
С	ommissioning Documentation	-
1.	After completion of commissioning, all test certificates of Commissioning will be submitted in hard copy.	

3.7 HIRARC ASSESSMENT FOR THE ELV- ACCESS CONTROL SYSTEM

	HAZARI	RISK	ANAL	YSIS		RISK CONTROL		
No	Work Activity	Hazard	Which can cause /effect	Existing risk control (if any)	likeli hood	Severity	Risk	Recommended Control Measures
1	Prepare work area and material	Unauthorized / untrained workers	Cuts Abrasions	Safety helmet Safety boots Reflective Vest	2	3	6	DSTI shall be conducted by the foreman / safety officer prior to work commencement. Task specific safety training to be provided. Daily safety inspection should be carried out and eliminate the hazard.
2	Use of hand tools and equipment	Malfunction of the equipment	Noise Cuts	Full PPE	3	4	12	Equipment shall be inspected to confirm in good condition.
3	Clearing unused material	Sharp object	Finger cut	Nil	3	1	3	Use leather glove, use tool
4	While working at night shift	Poor illumination	Sore eyes	Provide a lamp	2	1	2	Adequate lighting shall be provided while working
5	While working in hot weather	Heat stress	Dehydration	Nil	2	1	2	Provide drinking facilities

6	Use of ladder	Uneven floor	Fall from	Housekeeping	3	4	12	Scaffolder and ladder should be inspected.
	/ scaffolder	Obstructing	above	Safety boots				Put plank on floor or anti-slip mat.
		the access	Broken Leg	Safety Helmet				Adequate lighting shall be provided while
		way						working
								Step ladder must fully open and lock the
								devices as per manufacturer
								recommendations.
7	Testing &	Unauthorized	Electric shock	Circuit is not	4	4	16	Electrical work shall not carry out in wet
	commissionin	/ Untrained	Burn	live				condition.
	g	person	Cut	Reflective vest				Lock out tag out (LOTO) procedure to be
		Electrocution	Short circuit	Safety boots				followed during testing & commissioning.
		Broken cable	Death					Disconnect main supply before commencing of
								work.
8	Termination	Unauthorized	Electric shock	Circuit is not	4	4	16	Electrical work shall not carry out in wet
	Work	/ Untrained	Burn	live				condition.
		person	Cut	Reflective vest				Lock out tag out (LOTO) procedure to be
		Electrocution	Short circuit	Safety boots				followed during testing & commissioning.
		Broken cable	Death					Disconnect main supply before commencing of
								work.
								Do not touch the fiber during the termination
								work

3.8 FIRE SAFETY STRATEGY – EMERGENCY BREAKGLASS



Figure 3. 39: Emergency Breakglass

Manufacturing industries always expose to the danger such as fire because of the heavy machineries and chemical substance that are easily burn and etc. Basically there are two type of firefighting system that can be used in manufacturing industries such as active and passive fighting system. Both types have their own advantages and disadvantages and both are value in the overall fire safety design. The fire safety strategy in this case are emergency breakglass.

Emergency breakglass devices are meant for use in an emergency and may affect the approval of an electric locking system. In the case of an emergency, an emergency breakglass will give a physical technique of releasing an electromagnetic lock. In high-security environments, emergency breakglass is generally installed on exit doors. Emergency Breakglass can release a single door or all of the doors on the same circuit, as well as providing an auxiliary contact for remote monitoring, CCTV activation, or alarm activation.


CHAPTER FOUR

CHALLENGES OF THE ELV WORKS

4.1 INTRODUCTION

Based on the project, structured cabling of the ELV Services during the construction work project consists of more risk and problem which cannot be seen as early during the preliminary stage. This problem may affect the project period and cost which need to be tackle and manage during the preliminary stage. There are also contractor and consultant which not familiar with the ELV design and installation that can cause more wastage of the cable.

4.2 CHALLENGES OF THE ELV WORKS



4.2.1 CHALLENGES DURING THE DESIGN STAGES

Figure 4. 1: Card Access Reader Coordination

There are few challenges that are faces in the case study during the installation of the ELV services during the design stage. This happened due to the last minutes changes of the door coordination. Before the door is install, the technical support of the elv services will lay down the cable at the place that had been concealed to install the card access reader. In the safety and design term, the reader, push button, emergency break glass should have on the left-hand side if the door were swing to the right and vise verse.

According to the floor plan, the door is swing to the right and the push button, reader and other should the on the left-hand side, however the main-contractor install the door at the wrong side. Indirectly, will affected the design stage. Hence, the elv subcon need to lay down another cable to pull it until it reaches on the other side. Indirectly this incident will lead to the delay of the project.

4.2.2 CHALLENGES DURING THE TERMINATION WORK

Cable Termination is the connection of the CAT6 or fiber to a device, such as equipment, panels or a wall outlet, which allows for connecting the cable to other cables or devices. This involves the organizing of cables by destination, forming and dressing cables, and proper labelling as well as creating a connection with a copper or fiber conductor. In order to begin, there is planning that must take place. Prepare for the termination by developing a strategy for the cable beginning and end, making sure that have the proper tools to complete the job. The cable connection is not complete until all terminations are properly identified and labelled.




Figure 4. 2: Fiber termination work

While doing the cable termination work, required a skilled labour, because if the termination work is failed it will cause the cable become shorter and will increase the cost due to the wastage. After done the termination work, the labour required to do the testing and commission in order to measure the cable is well function or in either way. If the testing shows fail, the labour need to cut the cable include the RJ45, hence this shows the waste of the material and time. Labour needs to redo until the testing and commission show the result is pass. Next, safety during the termination work is a risky work where if there is a trip probably can cause the electric shock or burning.

CHAPTER FIVE

CONCLUSION AND RECOMMENDATION

5.1 CONCLUSION

In conclusion, ELV Services work is a challenging process where many risk and uncertainties occur during the installation work. A unskilled labour or unexperienced person in the installation of the lev works might failed to manage the project successfully. Based on the current project, a lot of uncertainties found during the project which affected the project cost and also lead to the delay. It is important to appoint experiences contractor in the ELV Services because to control and manage the building project which can produce good services and the building become more secure. In ELV Services work, different project may get different risk and uncertainties that could happen which this only can be handle with the supervision of the experience / skilled labour where the might have rough idea on the site situation and condition.

5.2 RECOMMENDATION

Throughout this practical training report, there are some recommendations that can be made to which to properly manage and choose the right method or approach in this ELV services work in order to make the project success:

- Provide a training to the unskilled labour in order to enhance their skill which can reduce the time management and reduce the wastage indirectly can minimize the cost and increase the time completion.
- Provide a safety procedure to the labour about the lay cable, installation and termination work which is to avoid any accident occur during the work.

REFERENCE

- Vacharee Prashyanusorna, Paiboon Prashyanusornb, Somkuan Kaviyac, Yusaku Fujiid and Preecha P. Yupapine (2010), The Use of Security Cameras with Privacy Protecting Ability, 2nd International Science, Social Science, Engineering and Energy Conference 2010: Engineering Science and Management, Procedia Engineering 8 (2011) pg 301–307
- Van Voorthuijsen, G.; van Hoof, H.; Klima, M.; Roubik, K.; Bernas, M.; Pata, P. (2005). [IEEE Proceedings 39th Annual 2005 International Carnahan Conference on Security Technology - Las Palmas, Spain (2005.10.11-2005.10.14)] Proceedings 39th Annual 2005 International Carnahan Conference on Security Technology - CCTV effectiveness study. Pg 105–108.
- Welsh, Brandon C.; Piza, Eric L.; Thomas, Amanda L.; Farrington, David P. (2019). Private Security and Closed-Circuit Television (CCTV) Surveillance: A Systematic Review of Function and Performance. Journal of Contemporary Criminal Justice,
- Welsh, B. C., & Farrington, D. P. (2009). Public area CCTV and crime prevention: An updated systematic review and meta-analysis. Justice Quarterly, 26, 716–745
- Dubbeld, Lynsey (2005). The role of technology in shaping CCTV surveillance practices. Information, Communication & Society, 8(1), 84–100.
- Josh P Davis, Charlotte Forrest, Felicia Treml and Ashok Jansari (2018), Identification from CCTV: Assessing police super-recogniser ability to spot faces in a crowd and susceptibility to change blindness
- Access Control System
- Schaad, Andreas; Moffett, Jonathan; Jacob, Jeremy (2001). Proceedings of the sixth ACM symposium on Access control models and technologies - SACMAT '01 -The role-based access control system of a European bank.
- Ardagna, C.A., Cremonini, M., De Capitani di Vimercati, S., Samarati. P. (2008), A privacy-aware access control system, Journal of Computer Security, vol. 16, no. 4, pp. 369-397
- National Institute of Standards and Technology Gaithersburg, MD 20899-8930 September 2006
- C.A. Ardagna et al. (2008), A privacy-aware access control system

Tarun Agarwal (2014), Understanding about types of Access Control System

- Sara C. Folta; Jeanne P. Goldberg; Christina Economos; Rick Bell; Stewart Landers; Raymond Hyatt (2006). Assessing the Use of School Public Address Systems to Deliver Nutrition Messages to Children: Shape Up Somerville—Audio Adventures., 76(9), 459–464.
- Green, I. W.; Maxfield, J. P. (1923). Public Address Systems, Bell System Technical Journal, 2(2), 113–142.
- Thackeray R, Neiger B, Leonard H, Ware J, Stoddard G. Comparison of a 5-a-day social marketing intervention and school-based intervention. Am J Health Stud. 2002;18(1):46-54.
- Novak, Thomas; Treytl, Albert; Palensky, Peter (2007). [IEEE 2007 IEEE Conference on Emerging Technologies & Factory Automation (EFTA 2007) - Patras, Greece (2007.09.25-2007.09.28)] 2007 IEEE Conference on Emerging Technologies & Factory Automation (EFTA 2007) - Common approach to functional safety and system security in building automation and control systems., (0), 1141–1148.

APPENDIX

1. CHECKLIST ACCESS CONTROL SYSTEM INSTALLATION

CHECK LIS	ST FOR:										
		Form No: Rev. No :0									
SUBCONTRAC		Page :56 of 1									
SECTION OF WORK: Electrical LOCATION:											
LEVEL:	WIR No.:										
STAGE	ITEM	Check S/C	ked by	NT	Checked by	Date					
	Check Approved Shop drawings/Layouts.										
SETTING OUT	Check Level as per approved Coordination drawings.										
001	Check that material as per approved material submittal.										
MEP/CIVIL	Check for civil clearance										
	1. Check the materials are approved										
trol	2. check the wiring is in correct manner										
con Iatio	 Check the status for all connected controllers and readers 										
stal	4. Check the connection of readers										
Acc n In	5. Check the connection of Door lock.										
Security Access Control System Installation	 Check the connection of the push button with Card reader and Lock. 										
Sec	7. check the panel installation										
	8. Check the identification inside the panel										
s	 Adequate lights are provided in the Work Area prior to installation. 										
UTION	 All terminations cables have been checked for any damage or improper connections. 										
PRECA	 Ensure that barricade & warning boards on the area are available prior to installation. 										
SAFETY PRECAUTIONS	 Ensure all supports have been properly installed & fixed prior to running the pumps. 										
U U	Ensure no obstacles in the area. Maintain proper housekeeping.										

		Ensure all pers shall have prop						
		Ensure all ele	ectrical tools to be not damage.	used in the				
For S/C QA/QC:		Date:	FOR CONTRACTOR QA/QC:	Date:	For CON	NS. Rep.:	Date:	
Name:		Sign:	Name:	Sign:	Name:		Sign:	

2. INSPECTION AND TEST PLAN OF THE ACCESS CONTROL SYSTEM INSTALLATION

		PF	ROJECT NAME		INSPECTION & TEST PLAN							
							REF. NO.					
						REV. NO. 0						
						DATE :						
						PAGE :		1 OF 1				
ACTIVITY: AREA/LOCATION:	Access Control System Installation											
ITP approved by CONT	RACTOR'S QA/QC:		ITP approved by Consultant:									
Signature:			Signature:									
Date:			Date:									
	DESCRIPTION	ERECUENCY	ODECIFICATION / ODITEDIA			NSPECT	ION LEV	EL				
SERIAL NO.	DESCRIPTION	FREQUENCY	SPECIFICATION / CRITERIA	:	S/C	CONTR	ACTOR	Cons	sultant	VERIFICATION RECORD		
1	DOCUMENTATION											
	Pre-Qualification subcontractor	Once (Approval prior to submit the submittal)	Project Specifications and drawings.	Н		Н		R				
1.2	Shop Drawing Approval	Each Shop Drawing	Project Specifications and drawings.	Н		Н		R				
1.3	Material Approval	Each MAR (prior to order the material).	Project Specifications and drawings.	н		н		R				
1.4	Method Statement Approval	Once (Approval prior to start of activity)	Project Specifications and drawings.	Н		н		R				
2	MATERIAL INSPECTION											
	Check the Material as per approved submittal.	Each Delivery	Project Specifications and drawings.	н		н		н				
3	Installation											
3.1	Installation of the system	Each Area where applicable (As per Consultant requirements)	Project Specifications and drawings.	н		н		н				
	·	LEGEND: H: HC										
			ITP Sign-Off post completion of Works									
	CONTRACTOR APPROVAL		Consultant APPROVAL									
	NAME :		NAME :									
	SIGN :		SIGN :									
	DATE:		DATE:									

3. PRE-COMMISSIONING OF ACCESS CONTROL SYSTEM

CHECK LIS	ST FOR:									
	Fo	Form No:								
		Rev.No:0 Page :1 of 1								
	(Pre-Commissioning – Visual Inspection)									
SUBCONTRACTOR X CONTRACTOR										
SECTION OF V	VORK: Electrical		LOCATION:							
LEVEL:		WIR No	o.:							
STAGE		ITEM	-		ked by	Checked by	Date			
	1 0			S/C	CONT	CONS.				
	1. Commissioning pr									
	2. Operation and mat	intenance information	1							
F	3. System Completer									
LEN	4. Location of Control		,							
LSΥ	5. Control panel envi manufacturer's gu									
OL S	6. Ensure that the Re									
IRC	installed and term									
NC	 Reader location sh Drawings. 	ould be properly sho								
s Ci	8. All the Controllers	s at field to be proper	ly tagged.							
CES	9. Ensure permanent		e provided to							
ACC	controllers and Lo	ck hardware.								
OF	10. All wires in the c									
oning OF ACCESS CONTROL SYSTEM	 Ensure Interlocki activated. 	ng with Fire Alarm s	ystem is							
oni	12. Ensure the I/O co	onnection is done as p								
issi	requirements	C' (1								
шu	13. Check the panel of components and w		angement of							
Pre-Commissi	14. Check that the in		upplied from							
-re-	UPS 15. Ensure the Acces	a Control Panala ara	connected to							
4	the secured Netwo		connected to							
	16. Ensure the softwa		are connected							
	to the Secured Net 17. Ensure the system		S & CCTV							
For S/C QA/Q	÷	Date:	For CO	NS. Rep.:	Date:					
For S/C QA/QC: Date: FOR CONTRACTOR Date: QA/QC:					•					
Name:	Sign:	Name:	Sign:	Name:		Sign:				
. turner	<u>э</u> .р		2. ⁰			51511.				

4. CHECKLIST SECURITY ACCESS CONTROL SYSTEM TESTING AND

COMMISSIONING

CHECK LIST FOR: Security Access Control Sys	tem Testing a	and commi	issioning	Form No:
(Commissio		Rev. No : 0 Page : 60 of 2		
SUBCONTRACTOR X				
SECTION OF WORK: Electrical		LOCATIO	N:	
LEVEL:		WIR No.:		
Details				
Control unit manufacturer :				
Building Name:				
Panel location:				
CONTROL PANEL				
Check	Yes	No		Comments
Installation of Termination boards				
Proper identification of cables				
Proper termination of data/Ethernet cables				
Proper termination of power cables				
Status of Alarm indicators				
Status of Alarm Sounders				
Status of fault indicators				
Status of power failure				
Status of Battery failure				
Status of Fire alarm interface				
Other (specify)				
FIELD DEVICES				
Check	Yes	No		Comments
Status of Access Card Reader				
Status of Push Button				
Status of Electro Magnetic Lock				
Status of Break Glass				


Status of Power Supply Units										
Status of Network Switch										
Status of Door Contacts										
Status of Server and Work Station										
SYSTEM POWER SUPPLY										
a) Primary (main) : Nomina	al voltage230	Amps								
Over current protection : Type	FUSEAmps_13_									
Location (Primary Supply Panel Board)										
b) Secondary (Standby) :										
Storage Battery : AmpHr. Rating										
Calculated capacity inA	Calculated capacity in Amp Hr to operate system for									
Type of Battery : Lead Acid										
CHECK LIST : PRIOR TO ANY TESTING										
Description	Yes	No	Comments							
Notifications are made to										
Building Occupants										
Building Management										
Others (specify)										
SYSTEM TESTS AND INSPECTIONS	I									
Туре	Visual	Functional	Comments							
Control Panel										
Interface with FA System		1								
Interface with rA system										
Interface with CCTV system										

Fuses				
Primary Power Supply				
Fault Indication				
SECONDARY POWER				
Battery condition				
Load Voltage				
Charger Test				
For S/C QA/QC: Date:	FOR CONTRACTOR QA/QC:	Date:	For CONS. Rep.:	Date:
Name: Sign:	Name:	Sign:	Name:	Sign:


5. INSPECTION AND TEST ACCESS CONTROL SYSTEM TESTING AND COMMISSIONING

		PROJEC	T NAME & DETAILS				I	NSPEC	TION & T	EST PLAN		
								REF. NO.				
						REV. NO. 0						
						DATE :						
						PAGE :		1 OF 1				
ACTIVITY:	Security Access Control System Testing a	nd commissioning										
AREA/LOCATION:												
ITP approved by CONT	RACTOR'S QA/QC:		ITP approved by Consultant:									
Signature:			Signature:									
Date:			Date:									
					11	NSPECT	ON LEV	EL				
SERIAL NO. DESCRIPTION F		FREQUENCY	SPECIFICATION / CRITERIA	S	S/C	CONTR			ultant	VERIFICATION RECORD		
1	DOCUMENTATION											
	Pre-Qualification subcontractor	Once (Approval prior to submit the submittal)	Project Specifications and drawings.	н		Н		R				
1.2	Shop Drawing Approval	Each Shop Drawing	Project Specifications and drawings.	н		н		R				
1.3	Material Approval	Each MAR (prior to order the material).	Project Specifications and drawings.	н		Н		R				
1.4	Method Statement Approval	Once (Approval prior to start of activity)	Project Specifications and drawings.	н		н		R				
2	Testing and Commissioning											
2.1	Pre-commissioning of the system	Each Area where applicable (As per Consultant requirements)	Project Specifications and drawings.	w		w		w				
2.2	Testing and commissioning of the system	Each Area where applicable (As per Consultant requirements)	Project Specifications and drawings.	w		W		н				
		LEGEND: H: HC							•			
			ITP Sign-Off post completion of Works									
	CONTRACTOR APPROVAL		Consultant APPROVAL									
	NAME :		NAME :									
	SIGN :		SIGN :									
	DATE:		DATE:									

6. AET SCHEMATIC DRAWING




7. GROUND AND FIRST FLOOR OFFICE DRAWING



utor			
	274 274	T all and a second s	
-			
-	20.1	CANDA I BOISSACED VI UDAL BALLET IDAGA USED I-300084082-12	
	ACADER CORD. C	COESS CONTROLLER	
ž		(HOME COLORS)	
1		LIC-BL SDOLET (RUHS) E (SATA PT)	
-	¥ŝ.	THE DEPOSE	
		AND HER (HO PH) Share Miller, Milanda Homes Miller, Milanda	-
題	a 13		
			+
	+		
DATE	MIV.	DESCRIPTION.	
		NIDERNG BORNLIGT M.S.	
MINAR	A PERGAN	LUTIONS SDN. 1	(1404-30
PAX-00	4.224.343		
TMAR.		NAMES OF A DESCRIPTION OF	ALC: NO.
08		ONSULT SDN.	BHD.
	0	A 1814.2.16 Jul.4	
	0	A INSTRUCT	
		o t y tonal transition	
BAY BE			
6	D	and the second se	SN BHD
	צי		-
SHOW			
elv MS	TALLAT		
CRAMER CONTRACT		ST FLOOR OFFICE LANOUT	2.0
		AT FLOOR OF THE LANGUE	
PROFILE			
CABANG	ON EXCELLA	ALERIA PENDERARKANAN KELAN KAT DI KING LOT PENDA	
IALINE CO	NAMES AND A	AT 1014-4 TAMON PERMITSTRAN	05
10766	ALL A	8.401	
-080		ALEX RAVI	BATE-
Distanti NGALI		404599 1.158	2946CT 2021
DEARDS			

8. GROUND FLOOR PRODUCTION



9. WORK SCHEDULE

1 2 3 4	0	Mode			Start	Finish	redecessor	% Complete 2021	14 19 24 29 1	ember 2021 3 8 13 18 1	December 2 23 28 3 8
3 4			APPLIED ENGINEERING TECHNOLOGY (M) SDN BHD ELV PROJECT PROPOSED WORK SCHEDULE (SUBJECT	66 days?	Fri 22/10/21	Fri 21/1/22		67%	1		
3 4		-	TO APPROVAL) PRELIMINARIES	19 days	Fri 22/10/21	Wed 17/11/21		90%			
4	~	-	SUBMIT MATERIAL LIST FOR APPROVAL	1 day	Fri 22/10/21	Fri 22/10/21		100%	a 22/10	•	
	~		SITE VISIT AND MEASUREMENT	1 day	Mon 1/11/21		3	100%	· 1	/11	
	<u>,</u>						-		୍ <u>କ୍</u>		
	<u> </u>	-	RECEIVE APPROVAL FOR MATERIAL LIST	1 day	Wed 3/11/21		4FS+3 days				
	~	-	ORDER MATERIAL	1 day	Wed 3/11/21		555	100%			
7		-	PREPARE SITE MATERIALS & EQUIPMENTS	3 days	Fri 5/11/21	Tue 9/11/21	-	50%			
_	<u> </u>	-	CCTV	1 day	Fri 5/11/21	Fri 5/11/21	6	100%		1	
	 		CARD ACCESS	1 day	Sat 6/11/21	Mon 8/11/21	8	100%		-	
10		*	AP DEVICES	1 day	Tue 9/11/21	Tue 9/11/21	9	0%		C ^{III}	
11		*	HP SWITCHES DELIVERY TO SITE BY PENTECH	1 day	Tue 9/11/21	Tue 9/11/21	1055	0%		91	
12		-4	PREPARE SHOP DRAWING, SUBMISSION AND APPROVAL	10 days	Thu 4/11/21	Wed 17/11/21	755	100%			
13	 Image: A second s	-4	MS TRUNKING & BRACKETS DELIVERY TO SITE	1 day	Thu 4/11/21	Thu 4/11/21	1255	100%	<u>ب</u>	h	
14	 Image: A second s	-4	CABLES & COMPONENTS DELIVERY TO SITE	1 day	Thu 11/11/21	Thu 11/11/21	1655+4 day	100%			
15		-4	INSTALLATION	57 days?	Fri 22/10/21	Mon 10/1/22		74%			
16	~	-4	METAL TRUNKING & PVC PIPE	6 days	Fri 5/11/21	Fri 12/11/21	13	100%	Li	*	
17	 Image: A second s	-4	UTP CABLES	5 days	Thu 11/11/21	Wed 17/11/21	1455	100%			
18	~	-4	BACKBONE FIBER CABLES	2 days	Thu 18/11/21	Fri 19/11/21	17	100%		(*	
19	1		CCTV (PRODUCTION AREA)	7 days	Mon 22/11/21		18	100%		+	
20	1	-4	CARD ACCESS (PRODUCTION AREA)	7 days	Mon 22/11/21		1855	100%			
21	1	-4	FTTH FIBER CABLES	2 days	Thu 25/11/21		18	100%			
22	1	-	TESTING FIBER & UTP CABLES	6 days	Mon 29/11/21		21	100%			
23	1	-	CCTV (OFFICE AREA)	4 days	Fri 3/12/21	Wed 8/12/21	19FS+2 day				+
	1	-	CARD ACCESS (OFFICE AREA)	4 days	Fri 3/12/21	Wed 8/12/21 Wed 8/12/21	2355	100%			
25	•	*	AP DEVICES (OFFICE AREA)	7 days		Mon 10/1/22	2333	0%			
26		*	AP DEVICES (OFFICE AREA)	7 days		Mon 10/1/22	2555	0%			
27		*	SWITCHES				2333	0%			
_		-		1 day?	Fri 22/10/21						
	<		TERMINATION	6 days	Mon 29/11/21		24	100%			
		*	TERMINATION OF TESTING FIBER & UTP CABLES	6 days	Mon 29/11/21		21	100%			
30		-	TESTING AND COMMISSIONING	63 days	Fri 22/10/21			0%			
	dë"	-4	CCTV	6 days		Tue 18/1/22	26	0%			
32		-4	CARD ACCESS	6 days		Tue 18/1/22	3155	0%			
33		-4	TRAINING	1 day		Fri 22/10/21		0%			
34		-4	FINAL CHECK	3 days	Wed 19/1/22			0%			
35		-4	TROUBLESHOOTING AND FINE TUNE SYSTEM	2 days	Wed 19/1/22	Thu 20/1/22	31	0%			
36		-4	HANDOVER	1 day	Fri 21/1/22	Fri 21/1/22	35	0%			

Prepared by: Siti Nadiah

