



**DEPARTMENT OF BUILDING
UNIVERSITI TEKNOLOGI MARA
(PERAK)**

RC PILE AND PILE CAP CONSTRUCTION

**Prepared by:
NUR ZULAIKHA BINTI MOHD RAZIP
2016458712**

DEPARTMENT OF BUILDING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA
(PERAK)

DECEMBER 2018

It is recommended that the report of this practical training provided

By

NUR ZULAIKHA BINTI MOHD RAZIP

2016458712

Entitle

RC Pile And Pile Cap Construction

Be accepted in partial fulfilment of requirement for obtaining Diploma in Building

Report Supervisor : Dr. Kamarul Syahril ~~Bin Haji~~ Kamal

Practical Training Coordinator : En. Muḥammad Naim Bin Mahyuddin

Programme Coordinator : Dr. Dzulkarnaen Bin Ismail

DEPARTMENT OF BUILDING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA
(PERAK)

DECEMBER 2018

STUDENT'S DECLARATION

I hereby declare that this report is my own work, except for extract and summaries for which the original references stated herein, prepared during a practical training session that I underwent at Jabatan Kerja Raya Negeri Selangor for duration 14 weeks starting from 3 September 2018 and end on 7 December 2018. It is submitted as one of the prerequisite requirement of DBG307 and accepted as a partial fulfilment of the requirements for obtaining the Diploma in Building.

Name : Nur Zulaikha Binti Mohd Razip

UiTM ID No : 2016458712

Date : 18/12/2018

ACKNOWLEDGEMENT

Alhamdulillah, praise to Allah.

I would like to extend my heartfelt gratitude for the guidance, advice and help rendered throughout the period of training by the following group of amazing individuals. First and foremost, I would like to thank Ir. Abdul Khalid S. Abdullah for the opportunity given, to conduct my training in Jabatan Kerja Raya Negeri Selangor. He helps me to learn and develop my understanding, knowledge and feel of real time projects and the theory involved management, building and civil works. He also responsible towards streamlining and assessing my training. Also to the site personnel in Masjid Seksyen 24, Shah Alam who have extended their cooperation and help to further enhance my ability in understanding the procedures in construction and site administration, tests procedures, site safety and best practices in the industry. It is an honour for me to be given the opportunity to ‘work’ with all of you.

I would also like to thank all the UiTM lecturers that have taught and nurtured me in becoming a better student and person. I would also like to extend my deepest appreciation to the lecturers who are directly involved during my training stint. To Dr. Kamarul Syahril Bin Haji Kamal as a Supervising Lecturer, En Muhammad Naim bin Mahyuddin as a Practical Training Coordinator and Dr. Dzulkarnaen Bin Ismail. as a Programme Coordinator, I value the time, effort, encouragement and ideas that they have contributed towards the successful completion of my training, this report and the valuable knowledge that have been shared over the last few semesters.

Last but not least, my special thanks to my beloved parents for their sacrifices over the years.

Thank you.

ABSTRACT

Pile and pile cap one of the most important structures in construction. The main topic discussed in this report is related to the structure that located below ground level based on project Cadangan membina dan menyiapkan Masjid Seksyen 24 Shah Alam, Selangor Darul Ehsan.. This report describes the type, materials, equipment used for during construction of reinforcement concrete pile and pile cap. This report also explained the construction method of reinforcement concrete pile. It also determines the construction method of pile cap. To complete this report requires observation and interviews with related individuals. In conclusion this report contains all elements related to reinforcement concrete pile and pile cap that are according to specification such as the method conducted type of structure used size of structure according to specifications.

| CONTENTS | PAGE NO |
|---|----------------|
| Acknowledgements | i |
| Abstract | ii |
| Contents | iii |
| List of Figures | iv |
| List of Photo | v |
| List of Table | vi |
| | |
| CHAPTER 1.0 INTRODUCTION | |
| 1.1 Introduction | 1 |
| 1.2 Objectives and Scope of Study | 2 |
| 1.3 Methods of Study | 4 |
| CHAPTER 2.0 COMPANY BACKGROUND | |
| 2.1 Introduction of Company | 5 |
| 2.2 Company Profile | 7 |
| 2.3 Organization Chart | 8 |
| 2.4 List of Project | |
| 2.4.1 Completed Projects | 9 |
| 2.4.2 Project in Progress | 12 |
| | |
| CHAPTER 3.0 CASE STUDY | |
| 3.1 Introduction to Case Study | 15 |
| 3.2 Method Construction of Reinforcement concrete | 18 |
| 3.3 Plant and machineries | 27 |
| CHAPTER 4.0 CONCLUSION | |
| 4.1 Conclusion | 30 |
| | |
| REFERENCES | |

LIST OF FIGURES

| | |
|-----------------|----|
| Figure 1.1..... | 3 |
| Figure 2.1..... | 5 |
| Figure 2.2..... | 7 |
| Figure 3.1..... | 16 |
| Figure 3.2..... | 16 |
| Figure 3.3..... | 17 |
| Figure 3.4..... | 17 |
| Figure 3.5..... | 18 |
| Figure 3.6..... | 23 |

LIST OF PHOTO

| | |
|-----------------|----|
| Photo 2.1..... | 5 |
| Photo 3.1..... | 15 |
| Photo 3.2..... | 19 |
| Photo 3.3..... | 19 |
| Photo 3.4..... | 20 |
| Photo 3.5..... | 20 |
| Photo 3.6..... | 21 |
| Photo 3.7..... | 21 |
| Photo 3.8..... | 22 |
| Photo 3.9..... | 22 |
| Photo 3.10..... | 23 |
| Photo 3.11..... | 24 |
| Photo 3.12..... | 24 |
| Photo 3.13..... | 25 |
| Photo 3.14..... | 25 |
| Photo 3.15..... | 26 |
| Photo 3.16..... | 26 |
| Photo 3.17..... | 27 |
| Photo 3.18..... | 27 |
| Photo 3.19..... | 28 |
| Photo 3.20..... | 28 |
| Photo 3.21..... | 29 |

LIST OF TABLE

| | |
|----------------|----|
| Table 2.1..... | 5 |
| Table 2.2..... | 9 |
| Table 2.3..... | 12 |

CHAPTER 1: INTRODUCTION

A pile can be defined as a column inserted in the ground to transmit the structural loads to a lower level of subsoil. A pile is basically a long cylinder of a strong material such as concrete that is pushed into the ground to act as a steady support for structures built on top of it. The piles are cast underneath the corners and intersection of load bearing walls and at regular intervals between to reduce the span and depth of the reinforced ground beam, which transfers the wall and buildings loads to the foundation (Stephen Emmitt, 2005). The construction process of pile can be broadly characterized by the installation and testing. However, there are many proprietary types of piles and the testing process for each type differed. Pile may be classified by the way they are formed i.e. Displacement piles and non-displacement piles.

Displacement piles refer to piles that are driven, thus displacing the soil, and include those piles that are preformed, partially preformed or cast in place. This is the most cost efficient piling method but may not be suitable for areas sensitive to noise, vibration and dust. Displacement piles cause the soil to be displaced radially as well as vertically as the pile shaft is driven or jacked into the ground (R. Cudley, 2012). Non-displacement piles soil is removed and the resulting hole filled with concrete or sometimes a precast concrete pile is dropped into the hole and grouted in. Clay are especially suitable for this type of pile formation as in clay the bore hole walls only require support close to the ground surface. When boring through more unstable ground, such as gravels, some form of casing or support, may be required. Alternatively, grout or concrete can be intruded from an auger rotated into a granular soil.

There are many types of pile but in this assignment will more focus on reinforced concrete pile. Reinforced concrete pile is commonly used in construction nowadays. The advantages of reinforced concrete piles are reinforcement used in the pile is not liable to change its place or get disturbed and the defects in pile can be easily identified after the removal of form, these defects such as the presence of cavity and hole can be repaired before installation. Next, the cost of manufacturing will be less, as a large number of piles are manufactured at a time and precast concrete piles can be driven under water. If the subsoil water contains more sulphate, the concrete of cast in situ piles would not set. Thus, precast concrete piles have added advantage in such a circumstance. Furthermore, precast concrete piles are highly resistant to biological and chemical action to the sub soil and also this piles can be constructed in various cross-sectional such as circular, octagonal or square. (Suryakanta, 2015)

There are many types of piles used in construction, so the aim of this assignment is to show the construction of reinforced concrete pile at Masjid Seksyen 24, Shah alam.

1.1 Objectives

- 1) To describe the method of installation for Reinforcement Concrete pile and construction of pile cap.
- 2) To determine the types of machineries that used.

1.2 Scope of study



Figure 1.1 Location of case study

Source: Google Maps (2014)

The case study carried out at Seksyen 24. Seksyen 24 is in Shah Alam, Selangor. Case Study will more focus on method of Reinforcement Concrete pile construction. In this case study, not only methods but also including materials and machineries used during construction.

1.3 Method of study

1. Observation

This method is be done by one week training at site construction. Observed the construction of pile cap start from first step until last step. Observed slump test and cube test for concrete. It gave more knowledge and experience more about reality on site during construction. Observation was done for one week and collected many important data. Each progress was recorded by pictures and written short notes.

2. Interviews

This method is be done by interview an engineer and a site supervisor. With this method, a relevant information can be gather as a references to complete this assignment. The engineer and site supervisor help a lot by explained more detail about the procedure of piling and pile cap because they know the best answer for the procedure details.

3. Documents reviews

This method is be done by referred a few documents at the office and also in site office. The documents are construction drawing, progress report and pictures that belongs to others also standard operating procedures. The documents content a lot of information and data that required for this assignment.

CHAPTER 2: COMPANY BACKGROUND

2.1 Introduction of Company

Jabatan Kerja Raya (JKR) Malaysia has been established ever since 1872 and operates as the technical expert to the Government of Malaysia. JKR is responsible in establishing development projects and infrastructure preservation to the various boards of ministries, departments, statutory bodies and state governments, such as roads, buildings, airports, harbours and piers.

JKR is responsible for planning, design and construction of infrastructure ventures such as roads, government buildings, airports, harbours, piers and related engineering works. Maintenance of roads and selected government buildings and Technical advisory services to the Federal Government, as well as states and districts.



Figure 2.1: Logo of company.

Source: Google Image



Photo 2.1: Kompleks Ibu Pejabat JKR Selangor.

Vision:

To become a world-class service provider and centre of excellence in asset management, project management and engineering services for the development of the nation's infrastructure through creative and innovative human capital and state-of-the-art technology.

Mission:

- Helping our customers grasp the basic information and providing services through collaborations as a strategic partner.
- Standardized our procedures and systems to deliver results dependable services.
- Provides asset management services and an effective and pioneering project.
- Strengthen existing engineering expertise.
- Developing human capital and new competencies.
- Prioritizing integrity in delivering the service.
- Fostering a well-proportioned relationship with the community.
- Preserving the environment in service delivery.

2.2 Company Profile


Table 2.1 Company Profile

| | |
|--------------------|---|
| Company Name | Jabatan Kerja Raya Negeri Selangor |
| Address | Kompleks Ibu Pejabat, Jabatan Kerja Raya Negeri Selangor, Persiaran Jubli Perak, Seksyen 17, 40200 Shah Alam. |
| Nature of Business | Government |
| Phone Number | 03-55454388 |
| Fax | 03-55452392 |
| Email | Jkr.gov.my |
| City | Shah Alam |
| State | Selangor |
| Postcode | 40300 |



Figure 2.2: Company Site Location

Source: Google Maps (2018)





2.4 Listed of Project

2.4.1 Completed Projects

Table 2.2: Completed Projects.

| Project | Client | Cost (RM) | Start Date | Deadline |
|---|--------------------------|---------------|------------|------------|
| <p>Cadangan Membina dan Menyiapkan Kompleks Islam Kuala Selangor</p>  <p>Kompleks Islam Kuala Selangor</p> | Jabatan Agama Islam Jais | 21,815,930.00 | 26-03-2014 | 22-09-2016 |
| <p>Cadangan Menaiktaraf Masjid Jamek Pekan Kajang</p>  <p>Masjid Jamek Pekan Kajang</p> | Jabatan Agama Islam Jais | 2,000,000.00 | 11-11-2015 | 3-01-2017 |

| | | | | |
|---|---------------------------------|----------------------|-------------------|-------------------|
| <p>Cadangan Membina dan Menyiapkan Masjid Al-Islah Sementa</p>  <p>Masjid Al-Islah</p> | <p>Jabatan Agama Islam Jais</p> | <p>10,000,000.00</p> | <p>11-06-2013</p> | <p>12-05-2015</p> |
| <p>Cadangan Membina dan Menyiapkan Baki Kerja Masjid Seksyen 7 Shah Alam</p>  <p>Masjid Seksyen 7</p> | <p>Jabatan Agama Islam Jais</p> | <p>7,000,000.00</p> | <p>25-07-2013</p> | <p>02-04-2014</p> |


| | | | | | |
|---|---|---------------------------------|----------------------|-------------------|-------------------|
| <p>Cadangan Membina dan Meyiapkan Masjid Dato Haji Kamaruddin</p> |  | <p>Jabatan Agama Islam Jais</p> | <p>15,000,000.00</p> | <p>20-12-2012</p> | <p>11-09-2014</p> |
| <p>Masjid Dato Haji Kamaruddin</p> | | | | | |

2.4.2 Projects in Progress

Table 2.3: Projects in progress.

| Project | Client | Cost (RM) | Start Date | Dateline |
|--|------------------------------|---------------|------------|------------|
| <p>Cadangan Membina dan Menyiapkan Masjid Seksyen 24</p>  <p>Masjid Seksyen 24</p> | Jabatan Agama Islam Selangor | 14,000,000.00 | 28-11-2017 | 26-05-2020 |
| <p>Cadangan Membina dan Menyiapkan Masjid Putra Height</p>  <p>Masjid Putra Height</p> | Jabatan Agama Islam Selangor | 27,000,000.00 | 09-11-2017 | 07-05-2020 |

| | | | | |
|---|-------------------------------------|----------------------|-------------------|-------------------|
| <p>Cadangan Membina dan Menyiapkan Masjid Setia Alam</p>  | <p>Jabatan Agama Islam Selangor</p> | <p>18,000,000.00</p> | <p>07-03-2017</p> | <p>20-08-2020</p> |
| <p>Masjid Setia Alam</p> <p>Cadangan Membina dan Menyiapkan Maahad Integrasi Tahfidz Sains Bagan Lalang, Sepang.</p>  | <p>Jabatan Agama Islam Selangor</p> | <p>20,000,000.00</p> | <p>15-09-2017</p> | <p>13-09-2020</p> |

| | | | | |
|--|-------------------------------------|----------------------|-------------------|-------------------|
| <p>Cadangan Membina dan Menyiapkan Masjid Ar-Rahman (RTB) Kuala Langat</p>  <p>Masjid Ar-Rahman</p> | <p>Jabatan Agama Islam Selangor</p> | <p>16,000,000.00</p> | <p>27-02-2018</p> | <p>31-12-2019</p> |
|--|-------------------------------------|----------------------|-------------------|-------------------|

3.0 Case Study

3.1 Introduction to Case Study

Seksyen 24, Shah Alam is a location for case study. It is a project under Jabatan Agama Islam Selangor. The location of the masjid is near to the residential area and also other facilities such as Kompleks Warga Emas, Kolam Pancing Seksyen 24 and also school. Seksyen 24 already have a mosque but due to the number of residents keep going increasing, existing mosque is not enough to support people. Existing mosque originally is a surau that already did a few renovation until became masjid. So, the residents there apply to Jabatan Agama Islam for a new mosque.

For this project, the value cost RM 14,000,000.00 and the date of completion is on 26 May 2020. Masjid Seksyen 24 can support around 2000 – 3000 people at the same time. The contractor that handle this project is Wira Muhibbah. For civil and structure is from Roadnett Solution Sdn. Bhd. In site office, there a few workers which is Project Manager, Residential Engineer, Quantiti Surveyor, Site Supervisor and also Site Safety Supervisor.

The foundation for this project is using Reinforcement Concrete pile with size 250mm x 250mm. The depth is 21m to reach to the hard layer. It used an end bearing pile. This project also has retaining wall. Retaining walls are made because there a small river beside the location of side. The retaining walls length are 16m that cover along the river.



Photo 3.1: Project Signboard.

Masjid Seksyen 24, Shah Alam.



Figure 3.1: Aerial view.



Figure 3.2: Main Courtyard.



Figure 3.3: Exterior VIP.




Figure 3.4: Interior Mihrab.

3.2 Method Statement of Construction for Reinforcement Concrete pile.




Figure 3.5: Sequence of work.

Method of Reinforcement Concrete Pile Construction

1. The pile position is set out on site using steel pin. There are two references steel pins would be installed equidistant from pile Centre location pin (about 500mm away). The pile would then be pitched and positioned into the exact pile position such that the reference pins are equidistant from the pile face.

Notes: Setting out shall be carried out using data and reference points as shown on the Drawing. The pile position shall be marked with suitable identifiable pins, peg or markers at least 300 mm length. The pins, pegs or markers should be driven to ground level and the location marked with contrasting materials.



Photo 3.2: Pile Point.

1. Each 250 mm x 250 mm RC piles marked with red ink at 1000mm intervals along its length to enable the jacked in pressure or force to be record at every 1000mm depth of pile penetration.



Photo 3.3: Marked pile.

2. The pile lifted and inserted into the Jack-In machine by crane to proceed the installation. The pile position was into the 'grip' of the equipment and gripped the pile body. Piles was lifted by using a crane.



Photo 3.4: Lifting pile.

3. The pile was installed by jacked-in machine which is using injection method. Each pile is jacked-in continuously until the required resistance or penetration is reached. The starter for piling is 12 m. During pile installation, the hydraulic pressure of main jacks measured by the pressure gauge and the corresponding pile penetration are recorded by means of welding.



Photo 3.5: Jacked-in pile.

- The pile was extended 6 m by using butt-welding the steels plate on the pile heads. During welding, the slag was chipped off and wire brushed to receive anti-rust paint.




Photo 3.6: Welding.

- Excavated the soil and then cut off pile to the specific level based on calculation by engineer. Backhoe loader is needed to excavate the soil and hydraulic pile cutter is required to cut the piles.

Notes: When a pile has been driven to the required set or depth, the head of the pile shall be cut off to the level specified or shown on the drawing. This shall be done carefully to avoid shattering or otherwise damaging the rest of the pile.



Photo 3.7: Excavation




Photo 3.8: Cut off pile.

6. Pile driving analyzer (PDA) and Maintained Load Test (MLT) was carried out. Pile driving analyzer was carried out on 20 no's and Maintained Load Test was for 2 no's of pile. The number of tested RC pile for Pile driving analyzer (PDA) and Maintained Load Test (MLT) was decided by JKR.

Notes: In order to verify the working load, the Contractor shall carry out pile load test as shown on the Drawing or as instructed by S.O. The Contractor shall give at least 48 hours notice of commencement of construction of any preliminary pile which is to be test loaded.



Photo 3.9: Pile Driving Analyzer (PDA).




Figure 3.6: Illustration of Pile Driving Analyzer (PDA).



Photo 3.10: Maintained Load Test (MLT).

Method of Pile Cap Construction Size 1300 mm x 550 mm.

1. Setting out the position of pile cap based on survey result by land surveyor. Setting a grid line for pile cap by using a thread as a guide.



Photo 3.11: A thread for grid line.

2. Put a 50 mm lean concrete grade 15 and prepared the reinforcement bar for pile cap. The size of the reinforcement bar is 25 mm for 1300 mm x 550 mm size of pile cap.



Photo 3.12: 50 mm Lean Concrete



Photo 3.13: Basket of Reinforcement bar.

3. Formwork of pile cap was installed sufficiently rigid with according size of pile cap 13000 mm x 550mm. Put the spacing bar and the reinforcement and starter bars was installed inside the formwork. The size of reinforcement is based on the JKR Building Specification and also drawing.

Notes: Formwork (including support) shall be sufficiently rigid o maintain the forms in their correct position, shape, profile and dimensions. The supports shall be designed to withstand the worst combination of forces due to self-weight, formwork weight, formwork forces, reinforcement weight, wet concrete weight, construction and wind loads, together with all incidental dynamic effects caused by placing, vibrating and compacting the concrete.



Photo 3.14: Formwork of pile cap.

- Concrete was poured into the formwork of pile cap. The concrete is ready mix with grade 30. The concrete must be left about 7 days to get the strong concrete. Last step was uninstalled the formwork of the pile cap.

Notes: Before commencing to construct pile caps, the Contractor shall check and verify the eccentricities and the cut-off levels all piling works in the ground are as provided in the Drawing, and shall notify the S.O. in the event of any discrepancy.

The Contractor shall straighten the steel reinforcement projecting above the piles for anchoring pile caps, carry out excavation, erect formwork and temporary timbering for the construction of pile caps and ground beam.



Photo 3.15: Concrete Mixer Truck



Photo 3.16: Condition of pile cap size 1300 mm x 550 mm after formwork was uninstalled.

3.3 Plant and Machineries.

1. Hydraulic Jack-In Machine.

Function: Commonly used for medium loaded structures such as residential or commercial buildings. Does not produce as much noise or vibration as compared to the other piling machineries. It is suitable to use for projects in urban areas where residents are sensitive to noise and vibrations.



Photo 3.17: Hydraulic Jack-In Machine.

2. Crane.

Function : It is also used for during Pile Driving Analyzer (PDA) and also during Maintain Load Test (MLT) was carried out. It is also for lifting the Reinforcement Concrete Pile during process for installation of pile.



Photo 3.18: Crane

3. Excavator

Function: Excavator runs on two endless tracks (chain wheel system). These types of excavators are used in hilly areas where risks of sliding of machinery are on the verge. It has low ground pressure because of spreading of load on large area. Therefore, it is also used where soil support is weak. It is suitable for excavation and digging work.



Photo 3.19: Excavator

4. Concrete mixer truck

Function: A device that homogeneously combines cement, aggregate such as sand or gravel, and water to form concrete. A typical concrete mixer uses a revolving drum to mix the components.



Photo 3.20: Concrete Mixer Truck

5. Pile cutter.

Function: It is use during cut-off pile work. Usually for piles that have small size.




Photo 3.21: Pile cutter

4.0 Conclusion

4.1 Conclusion

At the end of the report, based on the study that clearly understand in practical and in details on how the piling is constructed and the procedure that being carried out on the site. Next, from case study can identify the type of piling used which is in this project they used reinforcement concrete pile. The size used is only 250mm x 250mm only. From the study also types of plants and machineries that is used for the piling during installation and pile cap work processes such as hydraulic jack in, excavator, concrete mixer, crane and also pile cutter. This equipment and machineries will give new experience and knowledge for student practical. The surroundings of site construction full with equipment like nail, hammer, and reinforcement bar. This situation will created intention to learn something new and develop this skill using these equipment for benefit.

Based on the case study, a real practical is a quite same with the theory. A little bit different from theory is a method and also specification. During design stage, the people who are involved must follow a new specification based on JKR Standard Specifications For Building Works 2014. Start from 2017, JKR had started using EURO CODE. So, all the contractors have to follow and alert with the new specification. Lastly, a conclusion that can made is all the objective are achieved. All the objectives that had been explained is based carefully based on during the case study was carried out.

Lastly, for safety and health. It can be conclude that construction site area is safe to enter. Although, there are certain worker not wearing personal protective equipment (PPE) and protective clothing, there are no injuries or fatal cases that occur during the construction work process. Therefore, it is recommended to all parties to taken safety precaution regarding the construction of reinforcement concrete part to minimize other contribution factor in building defect and human injury.

References

Book:

1. Chudley. R (2012) *“Advanced Construction Technology”* 5th ed. Oxford.
2. Stephen Emmitt (2005) *“Introduction to Construction of Buildings”*. United Kingdom, Pearson.
3. Jabatan Kerja Raya (2014) *“Standard Specifications For Building Works 2014”*. Malaysia.

Article:

1. Suryanka (2015) *“What Are The Advantages And Disadvantages of Precast Concrete Pile”*.

SPC ENGINEERING SDN BHD (360417-M)

Daily Piling Record

Project Name : MASJID BER 24, 8744 ALAM Pile Running No : 12+676+6+6
 Pile Location : F15 Date : 08/6/2018
 Pile No : 111 Cylinder Size : 125-600
 Type of Pile : RC 300mm x 250mm Machine No : 260

| Depth (m) | Pressure mpa | Cyl. | Depth (m) | Pressure mpa | Cyl. | Depth (m) | Pressure mpa | Cyl. | Depth (m) | Pressure mpa | Cyl. | R.L OF G.L : |
|-------------|--------------|------|-------------|--------------|------|-------------|--------------|------|-------------|--------------|------|--------------|
| 0 - 0.5 | | | 15.0 - 15.5 | | | 30.0 - 30.5 | | | 45.0 - 45.5 | | | |
| 0.5 - 1.0 | 6 | | 15.5 - 16.0 | 6 | | 30.5 - 31.0 | 15 | | 45.5 - 46.0 | | | |
| 1.0 - 1.5 | | | 16.0 - 16.5 | | | 31.0 - 31.5 | | | 46.0 - 46.5 | | | |
| 1.5 - 2.0 | 6 | | 16.5 - 17.0 | 6 | | 31.5 - 32.0 | 15 | | 46.5 - 47.0 | | | |
| 2.0 - 2.5 | | | 17.0 - 17.5 | 10 | | 32.0 - 32.5 | | | 47.0 - 47.5 | | | |
| 2.5 - 3.0 | | | 17.5 - 18.0 | 12 | | 32.5 - 33.0 | 16 | | 47.5 - 48.0 | | | |
| 3.0 - 3.5 | 6 | | 18.0 - 18.5 | | | 33.0 - 33.5 | | | 48.0 - 48.5 | | | |
| 3.5 - 4.0 | | | 18.5 - 19.0 | 10 | | 33.5 - 34.0 | 17 | | | | | |
| 4.0 - 4.5 | 6 | | 19.0 - 19.5 | | | 34.0 - 34.5 | | | | | | |
| 4.5 - 5.0 | 6 | | 19.5 - 20.0 | 8 | | 34.5 - 35.0 | 20 | 10 | | | | |
| 5.0 - 5.5 | | | 20.0 - 20.5 | | | 35.0 - 35.5 | | | | | | |
| 5.5 - 6.0 | 6 | | 20.5 - 21.0 | 8 | | 35.5 - 36.0 | | 11 | | | | |
| 6.0 - 6.5 | | | 21.0 - 21.5 | | | 36.0 - 36.5 | | 36m | | | | |
| 6.5 - 7.0 | 7 | | 21.5 - 22.0 | 8 | | 36.5 - 37.0 | | SP | | | | |
| 7.0 - 7.5 | | | 22.0 - 22.5 | | | 37.0 - 37.5 | | | | | | |
| 7.5 - 8.0 | 7 | | 22.5 - 23.0 | 8 | | 37.5 - 38.0 | | | | | | |
| 8.0 - 8.5 | | | 23.0 - 23.5 | | | 38.0 - 38.5 | | | | | | |
| 8.5 - 9.0 | 6 | | 23.5 - 24.0 | 11 | | 38.5 - 39.0 | | | | | | |
| 9.0 - 9.5 | | | 24.0 - 24.5 | | | 39.0 - 39.5 | | | | | | |
| 9.5 - 10.0 | 6 | | 24.5 - 25.0 | 12 | | 39.5 - 40.0 | | | | | | |
| 10.0 - 10.5 | | | 25.0 - 25.5 | | | 40.0 - 40.5 | | | | | | |
| 10.5 - 11.0 | 6 | | 25.5 - 26.0 | 13 | | 40.5 - 41.0 | | | | | | |
| 11.0 - 11.5 | | | 26.0 - 26.5 | | | 41.0 - 41.5 | | | | | | |
| 11.5 - 12.0 | 7 | | 26.5 - 27.0 | 12 | | 41.5 - 42.0 | | | | | | |
| 12.0 - 12.5 | | | 27.0 - 27.5 | | | 42.0 - 42.5 | | | | | | |
| 12.5 - 13.0 | 7 | | 27.5 - 28.0 | 12 | | 42.5 - 43.0 | | | | | | |
| 13.0 - 13.5 | | | 28.0 - 28.5 | | | 43.0 - 43.5 | | | | | | |
| 13.5 - 14.0 | 7 | | 28.5 - 29.0 | 13 | | 43.5 - 44.0 | | | | | | |
| 14.0 - 14.5 | | | 29.0 - 29.5 | | | 44.0 - 44.5 | | | | | | |
| 14.5 - 15.0 | 7 | | 29.5 - 30.0 | 14 | | 44.5 - 45.0 | | | | | | |

08/6/2018

BL F15

PIL 111

36m

del

10m

3m

4m

CONVERSION TABLE FORM

Conversion from Tons to PSI : Formula : $\frac{\text{Tons required} \times 2204}{\text{Effective RAM area}} = \text{PSI}$

Project : MASJID SEKSYEN 24, SHAH ALAM
 Pile Size : 250mm x 250mm RC pile
 Working Load (WL) : 50 Ton
 Test Load (2 WL) : 100 Ton
 Hydraulic jack : CLS Series Capacity : 200 tons
 Effective ram area : 41.31 sq.in

1st cycle

| Percentage of Working Load (%) | Tonnage (Ton) | Time Required | PSI |
|--------------------------------|---------------|---------------|------|
| 25 | 12.50 | 1 hour | 667 |
| 50 | 25.00 | 1 hour | 1334 |
| 75 | 37.50 | 1 hour | 2001 |
| 100 | 50.00 | 1 hour | 2668 |
| 75 | 37.50 | 1 hour | 2001 |
| 50 | 25.00 | 1 hour | 1334 |
| 25 | 12.50 | 1 hour | 667 |
| 0 | 0.00 | 1 hour | 0 |

2nd Cycle

| Percentage of Working Load (%) | Tonnage (Ton) | Time Required | PSI |
|--------------------------------|---------------|---------------|------|
| 100 | 50.00 | 1 hour | 2668 |
| 125 | 62.50 | 1 hour | 3335 |
| 150 | 75.00 | 1 hour | 4001 |
| 175 | 87.50 | 1 hour | 4668 |
| 200 | 100.00 | 24 hours | 5335 |
| 150 | 75.00 | 1 hour | 4001 |
| 100 | 50.00 | 1 hour | 2668 |
| 50 | 25.00 | 1 hour | 1334 |
| 0 | 0.00 | 1 hour | 0 |
| | | 40 hours | |

The calibration base on RAM area 41.31 in² by using ENERPAC RAM model. The holding of load up to 40 hours



BORANG PEMERIKSAAN KERJA UJIAN BEBAN CERUCUK (PRODUK SIAP)

Nama Projek : CADDANGAN MEMBINA DAN MENYIAPKAN MASJID BEKUPEN 2A SHAH ALAM

Lokasi : P111

Rujukan Lukisan No : Rujukan Spesifikasi : Standard Specifications For Building Works 2014

Borang pemeriksaan ini perlu dirujuk bersama spesifikasi/dan lukisan projek.

| Butiran Pemeriksaan | Standard/Keperluan Teknikal | Pengukuran/ *Penilaian Tapak Oleh Kontraktor | *Pengesahan JKR/ **Perunding | Catatan/ No. NCP |
|--|-----------------------------|---|--|---------------------|
| Pemeriksaan proses ujian | Seksyen C | | | |
| 1. Rekod keputusan ujian dan kelulusan selepas ujian tamat. | | / | / | |
| 2. Graf beban melawan enapan, beban melawan masa, enapan melawan masa. | | / | | |
| 3. Cerucuk dianggap gagal jika:- 3.1 Baki mendapan setelah semua beban dibuang melebihi 6.50mm; atau 3.2 Jumlah mendapan dibawah beban rekabentuk melebihi 12.50mm; atau 3.3 Jumlah mendapan di bawah dua kali beban rekabentuk melebihi 38.0mm, atau 10% dari garispusat/lebar cerucuk, yang mana terendah | | / | ✓ Settlement 1.60mm < 6.0mm. ok! | |
| 4. Penilaian keputusan ujian dan penetapan prosedur untuk perlantikan cerucuk selanjutnya jika perlu. | | . | | |

| | | |
|-----------|----|--|
| Nota: | √ | jika mematuhi lukisan / spesifikasi |
| *Tandakan | x | jika tidak mematuhi lukisan / spesifikasi (rujuk borang NCP) |
| | TB | jika tidak berkaitan |
| ** | | Bagi projek-projek yang diselia oleh perunding |
| *** | | Bagi projek-projek Reka dan Bina |



JKR MALAYSIA

**PROSEDUR
PEMBINAAN DAN
PENYELIAAN TAPAK BINA**

No. Dokumen : JKR.PK(O).04-SKC.AS.4B
No. Keluaran : 05
No. Pindaan : 00
Tarikh : 1 Jun 2017
Muka Surat : 1 / 1

BORANG PEMERIKSAAN KERJA UJIAN BEBAN CERUCUK (PROSES PEMBINAAN)

Nama Projek : *CADANGAN MEMBINA DAN MENYIAPAN MASJID SEKUTYEDU 2A PAKH ALAM*


Lokasi : *P 111*

Rujukan Lukisan No : *SSR/PIK NO (MSP. SKSW 2A) SA 1001*
Rujukan Spesifikasi : Standard Specifications For Building Works 2014

Borang pemeriksaan ini perlu dirujuk bersama spesifikasi/dan lukisan projek.

| Butiran Pemeriksaan | Standard/ Keperluan Teknikal | Pengukuran/ *Penilaian Tapak Oleh Kontraktor | *Pengesahan JKR/ **Perunding | Catatan/ No. NCP |
|--|---|---|------------------------------------|---------------------|
| Pemeriksaan proses ujian | | | | |
| 1. Laksanakan ujian ke atas cerucuk | Section B6 - SSBW | / | / | |
| 2. Kenaikan beban keatas cerucuk | Section B6 Klausa 8.2 - SSBW | / | / | |
| 3. Rekodkan bacaan (Rujuk : JKR.PK(O).04- SKC.AS.4B-1) | Section B6 Klausa 8.2 / 8.2.4 -SSBW | / | / | |
| 4. Plotkan graf | Section B6 Klausa 8.2.2 - SSBW | / | / | |
| 5. Peningkatan beban seterusnya | Section B6 Klausa 8.2.2 - SSBW | / | / | |
| 6. <i>Maintain maximum load</i> | Section B6 Klausa 8.2.3 - SSBW | / | / | |
| 7. Pengurangan beban | Section B6 Klausa 8.2.4 - SSBW | / | / | |

| | | |
|-----------|--|--|
| Nota: | √ | jika mematuhi lukisan / spesifikasi |
| *Tandakan | x | jika tidak mematuhi lukisan / spesifikasi (rujuk borang NCP) |
| | TB | jika tidak berkaitan |
| ** | Bagi projek-projek yang diselia oleh perunding | |
| *** | Bagi projek-projek Reka dan Bina | |

| | | |
|--|---|------------------------------|
|  JKR MALAYSIA | PROSEDUR PEMBINAAN DAN PENYELIAAN TAPAK BINA | No. Dokumen : JKR.PK(O).04-4 |
| | | No. Keluaran : 05 |
| | | No. Pindaan : 00 |
| | | Tarikh : 1 Jun 2017 |
| | | Muka Surat : 1 / 1 |

LAMPIRAN 4

BORANG KALIBRASI PERALATAN

Sila senaraikan semua peralatan yang telah dikenalpasti yang perlu kalibrasi (rujuk Pelan Kualiti Pembinaan). Lampirkan salinan sijil bagi kalibrasi peralatan berkenaan dari makmal yang diiktiraf bagi tujuan rekod.

| Bil | Jenis Peralatan | No. Siri | No Sijil Kalibrasi | *Tarikh Tamat Tempoh Sijil Kalibrasi | *Tarikh Kalibrasi Peralatan |
|-----|-----------------|----------|--------------------|--------------------------------------|-----------------------------|
| 1. | Pressure Gauge. | 12257 | | 12/9/2019 | |
| 2. | Dial Gauge. | 9XH 673 | | 12/9/2019 | |
| 3 | Dial Gauge. | KD9 492 | | 12/9/2019 | |
| 4. | Dial Gauge. | KD9 371 | | 12/9/2019 | |
| 5. | Dial Gauge. | KD9 411 | | 12/9/2019 | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

Nota: Pastikan bahawa *tarikh kalibrasi peralatan tersebut berada dalam *tempoh yang telah ditetapkan. Rujuk Spesifikasi bagi julat ketepatan kalibrasi yang diperlukan/dibenarkan.

PROJECT TITLE: CADANGAN MEBINA DAN MENYIAPKAN MUKJID SEK-24 S-ALAM

PILE REF: P-111

BLOCK: MAIN Block

PILE SIZE: 250x250mm C.C.Pile

PENETRATION: 36.0m

SET: 1mm

| DATE | TIME | | LOAD CELL TON/KN | PRESSURE GAUGE | DIAL GAUGE READING | | | | AVERAGE | SETTLEMENT | LEVELS ON RULER | | REMARK |
|------------|------|----|---------------------|-------------------|--------------------|-------|-------|-------|---------|------------|-----------------|-------|--------|
| | | | | | A | B | C | D | | | JACK | TBM | |
| 30/06/2018 | 30 | Pm | | | 5.71 | 6.22 | 5.45 | 5.13 | 5.63 | 0.63 | | | |
| | 45 | | | | 5.69 | 6.19 | 5.42 | 5.10 | 5.60 | 0.60 | | | |
| | 8 | 0 | | | 5.69 | 6.19 | 5.42 | 5.10 | 5.60 | 0.60 | 100.5 | 100.0 | |
| | 8 | 0 | 50.0 | 2668 | 10.04 | 10.16 | 9.37 | 9.37 | 9.74 | 4.74 | 105.0 | 100.0 | |
| | 15 | | | | 10.07 | 10.20 | 9.39 | 9.40 | 9.77 | 4.77 | | | |
| | 30 | | | | 10.10 | 10.22 | 9.40 | 9.41 | 9.78 | 4.78 | | | |
| | 45 | | | | 10.11 | 10.22 | 9.40 | 9.41 | 9.79 | 4.79 | | | |
| | 9 | 0 | | | 10.12 | 10.23 | 9.40 | 9.42 | 9.79 | 4.79 | 105.0 | 100.0 | |
| | 9 | 0 | 62.50 | 3335 | 11.65 | 11.70 | 10.92 | 11.00 | 11.32 | 6.32 | 106.5 | 100.0 | |
| | 15 | | | | 11.71 | 11.76 | 10.98 | 11.07 | 11.38 | 6.38 | | | |
| | 30 | | | | 11.76 | 11.81 | 11.01 | 11.10 | 11.42 | 6.42 | | | |
| | 45 | | | | 11.73 | 11.84 | 11.03 | 11.13 | 11.43 | 6.43 | | | |
| | 10 | 0 | | | 11.75 | 11.85 | 11.04 | 11.15 | 11.45 | 6.45 | 106.5 | 100.0 | |
| | 10 | 0 | 75.00 | 4001 | 13.39 | 13.36 | 12.49 | 12.68 | 12.98 | 7.98 | 108.0 | 100.0 | |
| | 15 | | | | 13.47 | 13.41 | 12.53 | 12.72 | 13.03 | 8.03 | | | |
| | 30 | | | | 13.52 | 13.45 | 12.57 | 12.76 | 13.08 | 8.08 | | | |
| | 45 | | | | 13.55 | 13.48 | 12.60 | 12.78 | 13.10 | 8.10 | | | |
| | 11 | 0 | | | 13.58 | 13.51 | 12.61 | 12.79 | 13.12 | 8.12 | 108.0 | 100.0 | |
| | 11 | 0 | 87.50 | 4668 | 15.46 | 15.38 | 14.32 | 14.58 | 14.94 | 9.94 | 110.0 | 100.0 | |

RECORDED BY:

PROJECT TITLE: CADANGAN MEMBINA DAN MENYIAPKAN MASJID SEK 24 S. ALAM

PENETRATION: 36.0 mm

PILE SIZE: 300 X 250 mm Y.C

BLOCK: MAIN Block

PILE REF: P-111

| DATE | TIME | LOAD CELL TON/KN | PRESSURE GAUGE | DIAL GAUGE READING | | | | AVERAGE | SETTLEMENT | LEVELS ON RULER | | REMARK |
|------------|------|---------------------|-------------------|--------------------|-------|------|------|---------|------------|-----------------|-------|--------|
| | | | | A | B | C | D | | | JACK | TBM | |
| 30/06/2018 | 45 | | | 10.24 | 10.08 | 9.50 | 9.60 | 9.86 | 4.86 | | | |
| | 00 | | | 10.25 | 10.10 | 9.51 | 9.60 | 9.87 | 4.87 | 105.0 | 100.0 | |
| 4 | 00 | | | | | | | | | | | |
| | 00 | 37.50 | 2001 | 10.10 | 10.01 | 9.43 | 9.58 | 9.78 | 4.78 | 105.0 | 100.0 | |
| | 15 | | | 10.10 | 10.01 | 9.43 | 9.58 | 9.78 | 4.78 | | | |
| | 30 | | | 10.10 | 10.01 | 9.43 | 9.58 | 9.78 | 4.78 | | | |
| 5 | 45 | | | 10.10 | 10.01 | 9.43 | 9.58 | 9.78 | 4.78 | 105.0 | 100.0 | |
| | 00 | | | 10.10 | 10.01 | 9.43 | 9.58 | 9.78 | 4.78 | | | |
| 5 | 00 | | | | | | | | | | | |
| | 00 | 2500 | 1334 | 9.64 | 9.56 | 8.91 | 9.07 | 9.30 | 4.30 | 104.5 | 100.0 | |
| | 15 | | | 9.62 | 9.53 | 8.88 | 9.03 | 9.27 | 4.27 | | | |
| | 30 | | | 9.60 | 9.51 | 8.87 | 9.00 | 9.25 | 4.25 | | | |
| 6 | 45 | | | 9.60 | 9.50 | 8.87 | 9.00 | 9.24 | 4.24 | 104.5 | 100.0 | |
| | 00 | | | 9.60 | 9.50 | 8.87 | 9.00 | 9.24 | 4.24 | | | |
| 6 | 00 | | | | | | | | | | | |
| | 00 | 12.50 | 667 | 8.56 | 8.51 | 7.79 | 7.94 | 8.20 | 3.20 | 103.0 | 100.0 | |
| | 15 | | | 8.54 | 8.49 | 7.78 | 7.94 | 8.19 | 3.19 | | | |
| | 30 | | | 8.52 | 8.47 | 7.77 | 7.93 | 8.17 | 3.17 | | | |
| 7 | 45 | | | 8.52 | 8.47 | 7.77 | 7.93 | 8.17 | 3.17 | 103.0 | 100.0 | |
| | 00 | | | 8.51 | 8.46 | 7.77 | 7.93 | 8.17 | 3.17 | | | |
| 7 | 00 | | | | | | | | | | | |
| | 00 | 0 | 0 | 5.91 | 6.42 | 5.67 | 5.36 | 5.84 | 0.84 | 101.0 | 100.0 | |
| | 15 | | | 5.75 | 6.26 | 5.50 | 5.18 | 5.67 | 0.67 | | | |

RECORDED BY :

PROJECT TITLE: CADANGAN MEMBINA DAN MENYIAPKAN MABAND STATION 2A S-ACTM
 FILE REF: P 111
 BLOCK: MAIN BOLL

PILE SIZE: 250 X 250 mm R.C Pile
 PENETRATION: 36.07

| DATE | TIME | LOAD CELL TON/KN | PRESSURE GAUGE | DIAL GAUGE READING | | | | AVERAGE | SETTLEMENT | LEVELS ON RULER | | REMARK |
|-----------|----------|------------------|----------------|--------------------|-------|------|------|---------|------------|-----------------|-------|--------|
| | | | | A | B | C | D | | | JACK | TBM | |
| 30/6/2018 | 12 00 Pm | 0 | 0 | 5.00 | 5.00 | 5.00 | 5.00 | 5.00 | 0.00 | 100.0 | 100.0 | |
| | 12 00 Pm | 12.50 | 66.7 | 6.12 | 6.12 | 5.83 | 5.78 | 5.96 | 0.96 | 101.0 | 100.0 | |
| | 15 30 | | | 6.18 | 6.17 | 5.88 | 5.81 | 6.01 | 1.01 | | | |
| | 30 45 | | | 6.18 | 6.17 | 5.88 | 5.81 | 6.02 | 1.02 | | | |
| | 45 00 | | | 6.19 | 6.18 | 5.88 | 5.81 | 6.02 | 1.02 | 101.0 | 100.0 | |
| | 00 00 | | | 6.20 | 6.19 | 5.88 | 5.81 | 6.02 | 1.02 | 102.0 | 100.0 | |
| | 00 15 | 25.00 | 133.4 | 7.39 | 7.31 | 6.88 | 6.88 | 7.12 | 2.12 | | | |
| | 15 30 | | | 7.43 | 7.35 | 6.90 | 6.91 | 7.15 | 2.15 | | | |
| | 30 45 | | | 7.47 | 7.38 | 6.90 | 6.91 | 7.17 | 2.17 | | | |
| | 45 00 | | | 7.47 | 7.38 | 6.90 | 6.91 | 7.17 | 2.17 | 103.0 | 100.0 | |
| | 00 15 | 37.50 | 200.1 | 8.68 | 8.56 | 8.06 | 8.13 | 8.36 | 3.36 | 103.5 | 100.0 | |
| | 15 30 | | | 8.74 | 8.60 | 8.09 | 8.17 | 8.40 | 3.40 | | | |
| | 30 45 | | | 8.77 | 8.63 | 8.12 | 8.19 | 8.43 | 3.43 | | | |
| | 45 00 | | | 8.79 | 8.64 | 8.13 | 8.20 | 8.44 | 3.44 | | | |
| | 00 15 | | | 8.80 | 8.65 | 8.13 | 8.20 | 8.45 | 3.45 | 103.5 | 100.0 | |
| | 30 45 | 50.0 | 266.8 | 10.13 | 9.96 | 9.39 | 9.51 | 9.75 | 4.75 | 105.0 | 100.0 | |
| | 45 00 | | | 10.18 | 10.02 | 9.45 | 9.56 | 9.80 | 4.80 | | | |
| | 00 15 | | | 10.22 | 10.06 | 9.48 | 9.58 | 9.84 | 4.84 | | | |



CERTIFIED BY:

CHECKED BY:

RECORDED BY:


PROJECT : CADANGAN MEMBINA & MENYIAPKAN MASJID SEKSYEN 24, SHAH ALAM
 PILE SIZE : 250MM X 250MM RC PILE
 LOAD TEST NO.2 (PILE REF : P111)
 DATE : 30/6 - 2/7/2018

LOAD AND SETTLEMENT VS TIME



PROJECT : CADANGAN MEMBINA & MENYIAPKAN MASJID SEKSYEN 24, SHAH ALAM
PILE SIZE : 250MM X 250MM RC PILE
LOAD TEST NO.2 (PILE REF : P111)
DATE : 30/6- 2/7/2018

SETTLEMENT VS LOAD GRAPH



● 1st cycle
▲ 2nd cycle



JKR MALAYSIA

**PROSEDUR
PEMBINAAN DAN
PENYELIAAN TAPAK BINA**

No. Dokumen : JKR.PK(O).04-SKC.AM.3
No. Keluaran : 05
No. Pindaan : 00
Tarikh : 1 Jun 2017
Muka Surat : 1/1

BORANG PERMOHONAN PEMERIKSAAN/PENGUJIAN/BAHAN/MOCK UP (RFI)

Nama Projek : CADANGAN MEMBINA DAN MENYIAPKAN MASJID SECUPEN 29 BAHSA ALOR

Bidang : Sivil Struktur Senibina Mekanikal Elektrik Lain-Lain _____

Keterangan Kerja: PERCUBAAN LOAD TEST (NO 2)

Kerja/Alatan sedia untuk diperiksa/diujiterima pada 8.30am (masa) 30/6/2018 (tarikh)

No. RFI : _____ Tarikh Permohonan: 29/6/2018 RFI Baru Ulangan

No. RFI lama: _____

(Jika Ulangan)

| Bil. | Borang Pemeriksaan / Pengujian / Bahan / Mock-up | No.Siri | Tarikh Kelulusan | Lokasi (Jika berkaitan) | Grid |
|------|--|---------|------------------|-------------------------|------|
| 1. | PERCUBAAN LOAD TEST. | | | P 111 | F/5 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

| Maklumbalas Kelulusan Pemeriksaan / Pengujian / Bahan / Mock-up | | JKR (Sila tanda v diruang berkaitan) |
|---|--|---|
| A. | Lulus. Kontraktor dibenarkan untuk memulakan kerja | <input checked="" type="checkbox"/> |
| B. | Pembaikan kerja diperlukan semula dan diperiksa/diuji semula | <input type="checkbox"/> |
| C. | Kerja tidak bersedia untuk diperiksa/diuji. Mohon semula menggunakan borang RFI yang baru. | <input type="checkbox"/> |

Ulasan:

JKR (PTB): _____

Disahkan Oleh JKR: _____



FREYSSINET PSC (M) SDN BHD (9902-X)
 NO. 9, JALAN 2/137B, RESOURCE IND. CENTRE,
 OFF 5TH FLOOR, JALAN KLANG LAMA,
 58000 KUALA LUMPUR, MALAYSIA.
 TEL: +6-03-7982-8599 FAX: +6-03-7981 5530
 EMAIL: admin@fpscmalaysia.com
 (GST ID No. 000104611840)

CERTIFICATE OF CALIBRATION

CERTIFICATE NO.: D/2017/November/1923
 ISSUED BY: Joklai Bte Kuin (Pauline)
 DATE OF ISSUED: 14/11/2017

PAGE 2 OF 2
 APPROVED SIGNATORY
 Jamie Heng Wai Kheng

UNIT TO USE: mm
 RANGE: 0-50 mm
 RESOLUTION: 0.001 mm
 READABILITY: 0.0005 mm

INSRUMENTAL ERROR

| RANGE mm | FORWARD, mm | | BACKWARD, mm | |
|-------------|-------------|------------|--------------|------------|
| | Read | Correction | Read | Correction |
| 0 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| 5 | 4.9950 | 0.0010 | 4.9950 | 0.0010 |
| 10 | 10.0000 | 0.0000 | 10.0000 | 0.0000 |
| 15 | 14.9960 | 0.0040 | 14.9960 | 0.0040 |
| 20 | 19.9980 | 0.0020 | 19.9980 | 0.0020 |
| 25 | 24.9950 | 0.0050 | 24.9950 | 0.0050 |
| 30 | 29.9970 | 0.0030 | 29.9970 | 0.0030 |
| 35 | 35.0000 | 0.0000 | 35.0000 | 0.0000 |
| 40 | 39.9950 | 0.0050 | 39.9950 | 0.0050 |
| 45 | 44.9940 | 0.0060 | 44.9940 | 0.0060 |
| 50 | 49.9950 | 0.0050 | 49.9950 | 0.0050 |

| No. | Parameters | Data |
|-----|--|-------|
| 1.) | Indication error over any 1/10 revolution | 0.003 |
| 2.) | Indication error over any 1/2 revolution | 0.003 |
| 3.) | Indication error over any one (1) revolution | 0.003 |
| 4.) | Indication error over the whole measuring | 0.010 |
| 5.) | Retrace Error | 0.001 |
| 6.) | Repeatability | 0.001 |

Expanded uncertainty = ±0.002 mm where k = 2, at about 95% confidence level.

NOTE:

NOMINAL VALUE

A value to designate a characteristic of a device or to give a guide to its intended use

CORRECTION

Correction = Nominal value - Read indication

TRUE VALUE

True value = Read + correction

UNCERTAINTY

Parameters, associated with the result of a measurement, that characteristic the dispersion of the value that could reasonably be attributed to the measured. The estimation of this value is based on ISO guide to the expression of uncertainty in measurement, 1995.

The calibration and measurement results given are only related to the calibrated item(s) at the time of calibration unless otherwise stated.

This certificate is issued in accordance with the conditions of accreditation granted by SAMM which has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realized at the corresponding national standards laboratory. Copyright of this certificate is owned by the issuing laboratory and may not be reproduced other than in full except with the prior written approval of the Head of the issuing laboratory



FREYSSINET PSC (M) SDN BHD (9902-X)

NO. 9, JALAN 2/137B, RESOURCE IND. CENTRE,
OFF 5TH MILE, JALAN KIANG KAMA,
58000 KUALA LUMPUR, MALAYSIA

EMAIL: admin@fpscmalaysia.com
(GST ID No. 00010461830)

CERTIFICATE OF CALIBRATION

CERTIFICATE NO.: D/2017/November/1926
ISSUED BY: Joklai Bte Kuin (Pauline)
DATE OF ISSUED: 14/11/2017

| | | | |
|----------------------|---|----|---|
| PAGE | 2 | OF | 2 |
| APPROVED SIGNATORY | | | |
| Jamie Heng Wai Kheng | | | |

UNIT TO USE: mm
RANGE: 0-50 mm
RESOLUTION: 0.001 mm
READABILITY: 0.0005 mm

INSRUMENTAL ERROR

| RANGE mm | FORWARD, mm | | BACKWARD, mm | |
|-------------|-------------|------------|--------------|------------|
| | Read | Correction | Read | Correction |
| 0 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| 5 | 5.0020 | -0.0020 | 5.0020 | -0.0020 |
| 10 | 10.0010 | -0.0010 | 10.0010 | -0.0010 |
| 15 | 15.0000 | 0.0000 | 15.0000 | 0.0000 |
| 20 | 19.9960 | 0.0040 | 19.9970 | 0.0030 |
| 25 | 24.9980 | 0.0020 | 24.9980 | 0.0020 |
| 30 | 29.9980 | 0.0020 | 29.9980 | 0.0020 |
| 35 | 34.9980 | 0.0020 | 34.9960 | 0.0020 |
| 40 | 39.9950 | 0.0050 | 39.9950 | 0.0050 |
| 45 | 44.9970 | 0.0030 | 44.9970 | 0.0030 |
| 50 | 49.9950 | 0.0050 | 49.9960 | 0.0040 |

| No. | Parameters | Data |
|-----|--|-------|
| 1.) | Indication error over any 1/10 revolution | 0.004 |
| 2.) | Indication error over any 1/2 revolution | 0.005 |
| 3.) | Indication error over any one (1) revolution | 0.005 |
| 4.) | Indication error over the whole measuring | 0.005 |
| 5.) | Retrace Error | 0.001 |
| 6.) | Repeatability | 0.001 |

Expanded uncertainty= ±0.002 mm where k = 2, at about 95% confidence level.

NOTE:

NOMINAL VALUE

A value to designate a characteristic of a device or to give a guide to its intended use.

CORRECTION

Correction = Nominal value - Read indication

TRUE VALUE

True value = Read + correction

UNCERTAINTY

Parameters, associated with the result of a measurement, that characterize the dispersion of the value that could reasonably be attributed to the measured. The estimation of this value is based on ISO guide to the expression of uncertainty in measurement, 1995.

The calibration and measurement results given are only related to the calibrated item(s) at the time of calibration unless otherwise stated.

This certificate is issued in accordance with the conditions of accreditation granted by SAMM which has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realized at the corresponding national standards laboratory. Copyright of this certificate is owned by the issuing laboratory and may not be reproduced other than in full except with the prior written approval of the Head of the issuing laboratory.



FREYSSINET PSC (M) SDN BHD (9902-X)

NO. 9, JALAN 2/137B, RESOURCE IND. CENTRE,
OFF 5TH MILE, JALAN KLANG LAMA,
58000 KUALA LUMPUR, MALAYSIA.

EMAIL: admin@fpsscmalaysia.com
(GST ID No. 000104611840)

CERTIFICATE OF CALIBRATION

CERTIFICATE NO.: D/2017/November/1925
ISSUED BY: Joklai Bte Kuin (Pauline)
DATE OF ISSUED: 14/11/2017

PAGE 2 OF 2
APPROVED SIGNATORY
Jamie Heng Wai Kheng

UNIT TO USE: mm
RANGE: 0-50 mm
RESOLUTION: 0.001 mm
READABILITY: 0.0005 mm

INSRUMENTAL ERROR

| RANGE mm | FORWARD, mm | | BACKWARD, mm | |
|-------------|-------------|------------|--------------|------------|
| | Read. | Correction | Read. | Correction |
| 0 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| 5 | 5.0040 | -0.0040 | 5.0040 | -0.0040 |
| 10 | 9.9970 | 0.0030 | 9.9970 | 0.0030 |
| 15 | 15.0030 | -0.0030 | 15.0030 | -0.0030 |
| 20 | 19.9930 | 0.0070 | 19.9930 | 0.0070 |
| 25 | 25.0000 | 0.0000 | 25.0000 | 0.0000 |
| 30 | 29.9960 | 0.0040 | 29.9970 | 0.0030 |
| 35 | 35.0000 | 0.0000 | 35.0000 | 0.0000 |
| 40 | 39.9940 | 0.0060 | 39.9940 | 0.0060 |
| 45 | 45.0000 | 0.0000 | 45.0000 | 0.0000 |
| 50 | 49.9950 | 0.0050 | 49.9950 | 0.0050 |

| No. | Parameters | Data |
|-----|--|-------|
| 1.) | Indication error over any 1/10 revolution | 0.004 |
| 2.) | Indication error over any 1/2 revolution | 0.005 |
| 3.) | Indication error over any one (1) revolution | 0.007 |
| 4.) | Indication error over the whole measuring | 0.011 |
| 5.) | Retrace Error | 0.001 |
| 6.) | Repeatability | 0.001 |

Expanded uncertainty= ±0.002 mm where k = 2, at about 95% confidence level.

NOTE:

NOMINAL VALUE

A value to designate a characteristic of a device or to give a guide to its intended use

CORRECTION

Correction = Nominal value - Read indication

TRUE VALUE

True value = Read + correction

UNCERTAINTY

Parameters, associated with the result of a measurement, that characteristic the dispersion of the value that could reasonably be attributed to the measured
The estimation of this value is based on ISO guide to the expression of uncertainty in measurement, 1995

The calibration and measurement results given are only related to the calibrated item(s) at the time of calibration unless otherwise stated.

This certificate is issued in accordance with the conditions of accreditation granted by SAMM which has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realized at the corresponding national standards laboratory
Copyright of this certificate is owned by the issuing laboratory and may not be reproduced other than in full except with the prior written approval of the Head of the issuing laboratory



FREYSSINET PSC (M) SDN BHD (9902-X)

NO. 9, JALAN 2/137B, RESOURCE-IND. CENTRE,
OFF 5TH FLOOR, JALAN KLANG LAMA,
58000 KUALA LUMPUR, MALAYSIA.

EMAIL: admin@fpsscmalaysia.com
(GST ID No. 000104611840)

CERTIFICATE OF CALIBRATION

CERTIFICATE NO.: D/2017/November/1924
ISSUED BY: Joklai Bte Kuin (Pauline)
DATE OF ISSUED: 14/11/2017

PAGE 2 OF 2
APPROVED SIGNATORY
Jamie Heng Wai Kheng

UNIT TO USE: mm
RANGE: 0-50 mm
RESOLUTION: 0.001 mm
READABILITY: 0.0005 mm

INSRUMENTAL ERROR

| RANGE mm | FORWARD, mm | | BACKWARD, mm | |
|-------------|-------------|------------|--------------|------------|
| | Read | Correction | Read | Correction |
| 0 | 0.0000 | 0.0000 | 0.0000 | 0.0000 |
| 5 | 4.9930 | 0.0070 | 4.9930 | 0.0070 |
| 10 | 9.9980 | 0.0020 | 9.9980 | 0.0020 |
| 15 | 14.9910 | 0.0090 | 14.9920 | 0.0080 |
| 20 | 19.9960 | 0.0040 | 19.9960 | 0.0040 |
| 25 | 24.9910 | 0.0090 | 24.9910 | 0.0090 |
| 30 | 29.9980 | 0.0020 | 29.9980 | 0.0020 |
| 35 | 34.9920 | 0.0080 | 34.9920 | 0.0080 |
| 40 | 39.9970 | 0.0030 | 39.9970 | 0.0030 |
| 45 | 44.9990 | 0.0010 | 44.9990 | 0.0010 |
| 50 | 49.9960 | 0.0040 | 49.9960 | 0.0040 |

| No. | Parameters | Data |
|-----|--|-------|
| 1.) | Indication error over any 1/10 revolution | 0.009 |
| 2.) | Indication error over any 1/2 revolution | 0.009 |
| 3.) | Indication error over any one (1) revolution | 0.006 |
| 4.) | Indication error over the whole measuring | 0.015 |
| 5.) | Retrace Error | 0.003 |
| 6.) | Repeatability | 0.001 |

Expanded uncertainty= ±0.002 mm where k = 2, at about 95% confidence level

NOTE:

NOMINAL VALUE

A value to designate a characteristic of a device or to give a guide to its intended use

CORRECTION

Correction = Nominal value - Read indication

TRUE VALUE

True value = Read + correction

UNCERTAINTY

Parameters, associated with the result of a measurement, that characteristic the dispersion of the value that could reasonably be attributed to the measured
The estimation of this value is based on ISO guide to the expression of uncertainty in measurement, 1995

The calibration and measurement results given are only related to the calibrated item(s) at the time of calibration unless otherwise stated.

This certificate is issued in accordance with the conditions of accreditation granted by SAMM which has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realized at the corresponding national standards laboratory. Copyright of this certificate is owned by the issuing laboratory and may not be reproduced other than in full except with the prior written approval of the Head of the issuing laboratory.



FREYSSINET PSC (M) SDN BHD (9902-X)

NO. 9, JALAN 2/137B, RESOURCE IND. CENTRE,
OFF 5TH MILE, JALAN KLANG LAMA,
58000 KUALA LUMPUR, MALAYSIA.

EMAIL: admin@fpcsmalaysia.com
(GST ID No. 000104611840)

CERTIFICATE OF CALIBRATION

Certificate Reference No.: D/2017/November/1924

PAGE 1 OF 2

Issued By: Joklai Bte Kuin (Pauline)
Date of Issued: 11/11/2017

APPROVED SIGNATORY
Jamie Heng Wai Kheng

Customer: SPC Engineering Sdn Bhd
Job No.: C/W/3622/2017

Tel. No. 03-78465240 Fax No. 03-78465250

Description: Dial Gauge

Model: 3058S-1e

Manufacturer: Mitutoyo

Serial No.: GXH 673

Capacity/Range: 0-50mm

Condition of Instrument
Before Calibration: Good Physical Condition
After Calibration: Calibrated and Serviceable

Date of Calibration: 13/11/2017
Recommended Due Date: - (Specified by customer)

Calibration Method: Calibration Procedure No. FPSC/C/W/002

Calibration Venue: FPSC Calibration Room

Calibration Results: This result as following page(s). The expanded uncertainties are based on an estimated confidence probability of not less than 95% and have a coverage factor of k=2 unless stated otherwise.

ENVIRONMENTAL CONDITIONS

AMBIENT TEMPERATURE: 20 - 20 °C
RELATIVE HUMIDITY: 55 - 61 %RH

REFERENCE STANDARD(S) USED:

| DESCRIPTION | SERIAL NO. | DUE DATE | TRACEABLE TO |
|----------------------------------|--------------|------------|---------------------|
| Thermohygrograph | ADB410707-29 | 12/09/2019 | PSYP-17055596 |
| Mitutoyo Dial Calibration Tester | 400532 | 19/03/2018 | SST/SA/R/2016C/1375 |

CALIBRATED BY: Jinggut Anak Maluda

APPROVED SIGNATORY:

Calibration Sticker No. 0002901 (Jamie Heng Wai Kheng)

The calibration and measurement results given are only related to the calibrated item(s) at the time of calibration unless otherwise stated.

This certificate is issued in accordance with the conditions of accreditation granted by SAMM which has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realised at the corresponding national standards laboratory. Copyright of this certificate is owned by the issuing laboratory and may not be reproduced other than in full except with the prior written approval of the Head of the issuing laboratory.

**FREYSSINET PSC (M) SDN BHD (9902-X)**NO. 9, JALAN 2/137B, RESOURCE IND. CENTRE,
OFF 5TH MILE, JALAN KLANG LAMA,
58000 KUALA LUMPUR, MALAYSIAEMAIL: admin@fpscmalaysia.com
(GST ID No. 000104514840)**CERTIFICATE OF CALIBRATION**

Certificate Reference No.: D/2017/November/1925

PAGE 1 OF 2

Issued By: Joklai Bte Kurin (Pauline)
Date of Issued: 14/11/2017APPROVED SIGNATORY
Jamie Heng Wai KhengCustomer: SPC Engineering Sdn Bhd
Job No.: C/W/3622/2017

Tel. No. 03-78465240 Fax No. 03-78465250

Description: Dial Gauge

Model: 3058S-19

Manufacturer: Mitutoyo

Serial No.: KDG 492

Capacity/Range: 0-50mm

Condition of Instrument
Before Calibration: Good Physical Condition
After Calibration: Calibrated and ServiceableDate of Calibration: 13/11/2017
Recommended Due Date: - (Specified by customer)

Calibration Method: Calibration Procedure No. FPSC/C/W/002

Calibration Venue: FPSC Calibration Room

Calibration Results: This result as following page(s). The expanded uncertainties are based on an estimated confidence probability of not less than 95% and have a coverage factor of k=2 unless stated otherwise.

ENVIRONMENTAL CONDITIONSAMBIENT TEMPERATURE: 20 - 20 °C
RELATIVE HUMIDITY: 57 - 61 %RH

REFERENCE STANDARD(S) USED:

| DESCRIPTION | SERIAL NO. | DUE DATE | TRACEABLE TO |
|----------------------------------|--------------|------------|---------------------|
| Thermohygrograph | ADB410707-29 | 12/09/2019 | PSYP-17055596 |
| Mitutoyo Dial Calibration Tester | 400532 | 19/03/2018 | SST/SA/R/2016C/1375 |

CALIBRATED BY: Jinggut Anak Maluda

APPROVED SIGNATORY:

Calibration Sticker No: 0002902

(Jamie Heng Wai Kheng)

The calibration and measurement results given are only related to the calibrated item(s) at the time of calibration unless otherwise stated.

This certificate is issued in accordance with the conditions of accreditation granted by SAMM which has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realised at the corresponding national standards laboratory. Copyright of this certificate is owned by the issuing laboratory and may not be reproduced other than in full except with the prior written approval of the Head of the issuing laboratory



FREYSSINET PSC (M) SDN BHD (9902-X)

NO. 9, JALAN 2/137B, RESOURCE IND. CENTRE,
OFF 5TH MILE, JALAN KLANG LAMA,
58000 KUALA LUMPUR, MALAYSIA.

EMAIL: admin@fpscmalaysia.com
(GST ID No. 000104611820)

CERTIFICATE OF CALIBRATION

Certificate Reference No.: D/2017/November/1923

PAGE 1 OF 2

Issued By: Joklai Bte Kuin (Pauline)
Date of Issued: 14/11/2017

APPROVED SIGNATORY
Jamie Heng Wai Kheng

Customer: SPC Engineering Sdn Bhd
Job No.: CW/3622/2017

Tel. No. 03-78465240 Fax No. 03-78465250

Description: Dial Gauge

Model: 3058S-19

Manufacturer: Mitutoyo

Serial No.: KDG 411

Capacity/Range: 0-50mm

Condition of Instrument

Before Calibration: Good Physical Condition
After Calibration: Calibrated and Serviceable

Date of Calibration: 13/11/2017
Recommended Due Date: (Specified by customer)

Calibration Method: Calibration Procedure No. FPSC/C/WI/002

Calibration Venue: FPSC Calibration Room

Calibration Results: This result as following page(s). The expanded uncertainties are based on an estimated confidence probability of not less than 95% and have a coverage factor of k=2 unless stated otherwise.

ENVIRONMENTAL CONDITIONS

AMBIENT TEMPERATURE: 20 - 20 °C
RELATIVE HUMIDITY: 57 - 62 %RH

REFERENCE STANDARD(S) USED:

| DESCRIPTION | SERIAL NO. | DUE DATE | TRACEABLE TO |
|----------------------------------|--------------|------------|---------------------|
| Thermohygrograph | ADB410707-29 | 12/09/2019 | PSYP-17055596 |
| Mitutoyo Dial Calibration Tester | 400532 | 19/03/2018 | SST/SA/R/2016C/1375 |

CALIBRATED BY: Jinggut Anak Maluda

APPROVED SIGNATORY:

Calibration Sticker No: 0002900

(Jamie Heng Wai Kheng)

The calibration and measurement results given are only related to the calibrated item(s) at the time of calibration unless otherwise stated.

This certificate is issued in accordance with the conditions of accreditation granted by SAMM which has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realized at the corresponding national standards laboratory. Copyright of this certificate is owned by the issuing laboratory and may not be reproduced other than in full except with the prior written approval of the Head of the issuing laboratory.



FREYSSINET PSG (M) SDN BHD (9902-X)

NO. 9, JALAN 2/137B, RESOURCE IND. CENTRE,
OFF 5TH MILE, JALAN KLANG LAMA,
58000 KUALA LUMPUR, MALAYSIA.

EMAIL: admin@fpscmalaysia.com
(GST ID No. 000104611840)

CERTIFICATE OF CALIBRATION

CERTIFICATE NO.: P/2017/November/1228
ISSUED BY: Joklai Bte Kuin (Pauline)
DATE OF ISSUED: 20/11/2017

PAGE 2 OF 2

APPROVED SIGNATORY

Ng Ming Khin (Jason)

UNIT TO USE: psi
RANGE: 0-10,000 (psi)
RESOLUTION: 100 psi
READABILITY: 50 psi
SPECIFICATION (±): 1.5 %FS

| Test Point | Ref. Value | Series 1 (UUT) | Series 2 (UUT) | Repeatability Error (±) | Mean UUT | Linearity Correction | Specification(±) |
|------------|------------|----------------|----------------|-------------------------|----------|----------------------|------------------|
| 2000 | 2000.0 | 2000 | 2000 | 0 | 2000 | 0 | 150.0 |
| 4000 | 4003.5 | 4000 | 4000 | 0 | 4000 | 0 | |
| 6000 | 6005.1 | 6000 | 6000 | 0 | 6000 | 5 | |
| 8000 | 8006.6 | 8000 | 8000 | 0 | 8000 | 7 | |
| 10000 | 10008.0 | 10000 | 10000 | 0 | 10000 | 8 | |
| 8000 | 8006.0 | 8000 | 8000 | 0 | 8000 | 6 | |
| 6000 | 6004.8 | 6000 | 6000 | 0 | 6000 | 5 | |
| 4000 | 4003.3 | 4000 | 4000 | 0 | 4000 | 3 | |
| 2000 | 2001.7 | 2000 | 2000 | 0 | 2000 | 2 | |

Expanded uncertainty = ±28 psi where k = 2, at about 95% confidence level

Hysteresis Test

| Test Point | Mean UUT | | Error (±) |
|------------|-------------------|-------------------|-----------|
| | Increase Pressure | Decrease Pressure | |
| 2000 | 2000 | 2000 | 0 |
| 4000 | 4000 | 4000 | 0 |
| 6000 | 6000 | 6000 | 0 |
| 8000 | 8000 | 8000 | 0 |
| 10000 | 10000 | 10000 | 0 |

Hysteresis Error: 0

NOTE:

NOMINAL VALUE

A value to designate a characteristic of a device or to give a guide to its intended use.

CORRECTION

Linearity Correction = Reference value - Mean UUT

ERROR VALUE

Error value = Mean UUT - Nominal (Test Point)

UNCERTAINTY

Parameters, associated with the result of a measurement, that characterize the dispersion of the value that could reasonably be attributed to the measured. The estimation of this value is based on ISO guide to the expression of uncertainty in measurement, 1995

The calibration and measurement results given are only related to the calibrated item(s) at the time of calibration unless otherwise stated.

This certificate is issued in accordance with the conditions of accreditation granted by SAMM which has assessed the measurement capability of the laboratory and its traceability to recognized national standards and to the units of measurement realized at the corresponding national standards laboratory. Copyright of this certificate is owned by the issuing laboratory and may not be reproduced other than in full except with the prior written approval of the Head of the issuing laboratory.



MS ISO 9001: 2000
 REF: 7.5.1 & 7.5.2

FIELD SHEET FOR DYNAMIC PILE TESTING

DOC REF:
 TBSB/OPS/PDA

Client Name : SPC Piling Date : _____
 Project Name : Masjid, 24 Seksyen

Test Personnel : FJR / Razak
 PDA Equipment Set No: Pak - 5 Transducers & Accelerometer Set No: 10

| Pile ID | P382 | P283 | P364 | | |
|---------------------------------|--------------------|------------|------------|-----------|-----------|
| Pile Details | | | | | |
| Pile Type | RC | RC | RC | RC | RC |
| Pile Size (mm) | 250 x 250 | 250 x 250 | 250 x 250 | 250 x 250 | 250 x 250 |
| Temporary Casing (m) | - | - | - | - | - |
| Permanent Casing (m) | - | - | - | - | - |
| Section Area (cm ²) | 625 | 625 | 625 | 625 | 625 |
| Material Strength (MPa) | 45 | 45 | 45 | 45 | 45 |
| Total Pile Length (m) | 26.5 37.0 cut 33 | 30.0 | 30.0 | 45 | 45 |
| Penetration Length (m) | 26.5 30.0 exc 32.5 | 29.5 (2xc) | 29.5 (2xc) | - | - |
| Length Below Gauges (m) | 26.5 30.5 32.7 | 29.7 | 29.7 | - | - |
| Pile Make-up (m) (top-btm) | 6+6+6+6+12 | 6+6+6+12 | 6+6+6+12 | - | - |
| Working load (tonne) | 50 | 50 | 50 | 50 | 50 |
| Required Test Load (tonne) | 100 | 100 | 100 | 100 | 100 |

Hammer Details

| | | | | | |
|--------------------|-----|--|--|--|--|
| Hammer Type | DH | | | | |
| Ram Weight (tonne) | 1.5 | | | | |
| Drop Height (m) | 1.0 | | | | |

Results below are indicative. CAPWAP Analysis required to be carried out on collected wave traces

PDA Field Results

| | | | | | |
|---------------------------|------|------------|------|------|--|
| RMX (tonne) | 120 | 120 | 120 | | |
| RSU (tonne) / RA2 (tonne) | 193 | 212 | 184 | | |
| FMX (tonne) | 167 | 120 | 129 | | |
| EMX (t-m) | 1.21 | 1.05 | 0.77 | | |
| CSX (Mpa) | 26.2 | 18.8 | 20.3 | | |
| TSX (Mpa) | 5.0 | 6.6 | 6.7 | | |
| Pile Integrity | BTA | BTTC 27.7m | 100% | 100% | |
| | BT2 | | 100% | 100% | |


MOHD ISMAIL BIN JANTAN
 RESIDENT ENGINEER
 ROADNET SOLUTION SDN BHD

Supplemental Data

| | | | | | |
|------------------------------|-------------|-------------|-------------|-------------|-------------|
| Wave Speed (m/s) | 3800 | 3800 | 3800 | 3800 | 3800 |
| Density (t/cm ³) | 2.45 | 2.45 | 2.45 | 2.45 | 2.45 |
| Measured DFN (mm) | 1mm / blows | 1mm / blows | 1mm / blows | 1mm / blows | 1mm / blows |
| Date Driven/ Casting | 26/6/18 | 26/6/18 | 18/6/18 | 1 blows | 1 blows |


TESTING WITNESSED BY :

Company : WIRA MUHIBBAH SHAFIE Sdn Bhd Company : SPC ENGINEERING Sdn Bhd
 Name : WIRA MUHIBBAH SHAFIE Name : MOHD ISMAIL BIN JANTAN
 Signature : [Signature] Signature : [Signature]




PILING LAYOUT PLAN



- SCALE 1:150
- NOTES :-
1. ALL PILES SHALL BE 250x250 R.C SQUARE PILE GRADE 45.
 2. SAFE WORKING LENGTH OF A PILE IS 500 MM WITH PROVISIONAL LENGTH OF 24.0 M
 3. ALL PILES SHALL BE INSTALLED TO A SET BY HYDRAULIC ABUTMENT METHOD. THE CONTRACTOR IS TO SUBMIT INSTALLATION WORK METHOD STATEMENT FOR APPROVAL.
 4. SCHEDULE OF TESTS :-
 - i. U.T = 2 NOS.
 - ii. P.M. TEST = 20 NOS.



J.K.R. Negeri Selangor D.E.

| | |
|--|------------------------|
| PELANGGAN JAMBATAN AGAMA ISLAM SELANGOR | |
| PENGARAH IR. RUSLAN BIN ABUL AZIZ | |
| TIMBALAN PENGARAH BAHAH BINI AB. AZIZ | |
| ARKITEK PENGUASA | |
| ARKITEK GAMARAH BINI ABDUL SHUKOR | |
| PROJEK CADANGAN MEMBINA DAN MENYIAPKAN MASJID SEKSYEN 24 SHAH ALAM, DALAM DAERAH PETALING, SELANGOR DARUL EHSAN | |
| PERUNDING ARKITEK RIZAL OSMAN ARCHITECT • R O A 7-2 Jalan PAU 7/7A Multisara Damansara 47800 Petaling Jaya Selangor Darul Ehsan Email : osman@rosarchitect.com Tel : 603 7731 1144 | |
| KONSULTAN UKUR - BAHAN HAH ASSOCIATES 42-2 Jalan Wangsa Setia 4 Wangsa Melawati 53300 Kuala Lumpur | |
| JURUTERA SIVIL DAN STRUKTUR "Saya memperingati dalam-dalam dalam pelan-pelan ini adalah mengikat kehandak-kehandak Aktis 133 Jalan, Part II & Bangunan 1974 dan saya setuju terima tanggungjawab penuh dengan saya/jermy" | |
|  <p>Ir. ROFIE BIN SARBINI C110240 MALAYSIA</p> | |
| Ir. ROFIE BIN SARBINI ROADNET SOLUTIONS SDN BHD (793352-7) Consulting Engineers & Project Manager Civil, Structural and Traffic No.53B, Jalan BSP 1/4, Bukit Rahwan Palm, 47000 Sungai Buloh, Selangor Darul Ehsan Tel: 03-6150 0757, Fax: 03-6157 5852 H/P: 015 - 2712 142 Email: roadnetsolutions@gmail.com | |
| PERKARA STRUCTURAL PILING LAYOUT PLAN | |
| UKURAN : AS SHOWN | DISEMAK : WAN/SITI |
| DILUKIS : mZ | TARIKH : NOVEMBER 2017 |
| NO. LUKISAN : RSSB/JKR/MSJ24/ST/PLN/01 | NO. FAIL : |

CONSTRUCTION DRAWING



| FLOOR | C1. | C2. | C3. | C4. | C5. | C6. | C7. | C8. | C9. | C10. | C11. | ST1. | ST2. | COB.1 | COB.2 | COB.3 | COB.4 | C12. | |
|-----------------------|------------|------------|-------------------------|------------|-----------------|----------|----------|----------|----------|---------|---------|------|------|---------|---------|---------|---------|------------|--|
| ROOF LEV. 2 TO 3 | | | | 600 600 | | | | | | | | | | | | | | | |
| ROOF LEV. 1 TO LEV. 2 | | | 6H10 H10-250 'U' BAR | 600 600 | 3H10-175 | 3H10-175 | 3H10-175 | 3H10-175 | 3H10-175 | 12H16 | 10H16 | | | 12H16 | 10H16 | 8H16 | | 600 600 | |
| CB - ROOF LEV. 1 | 450 450 | 300 450 | 6H10 H10-250 'U' BAR | 600 600 | 3H10-175 | 3H10-175 | 3H10-175 | 3H10-175 | 3H10-175 | 12H16 | 10H16 | | | 12H16 | 10H16 | 8H16 | | 600 600 | |
| STUMP | 450 450 | 300 450 | 600 600 | 600 600 | 600x600/200x600 | 600x1000 | 600x600 | 300x300 | 450x450 | 300x300 | 300x300 | | | 450x450 | 300x450 | 300x300 | 300x300 | 600 600 | |

| TARIKH | BUTIRAN | RUJUKAN |
|----------|---------------------------------|---------|
| 06/12/17 | REVISED REINFORCEMENT SIZE | R1 |
| 25/06/18 | ADDED PILECAP DETAIL 3P-A | R2 |
| 01/08/18 | REVISED STUMP C3 & C12 SCHEDULE | R3 |

COLUMN REINF. SCHEDULE

CONSTRUCTION DRAWING



J.K.R. Negeri Selangor D.E.

PELANGGAN
JABATAN AGAMA ISLAM SELANGOR
PENGARAH
IR. RUSLAN BIN ABUL AZIZ
TIMBALAN PENGARAH
RABIAH BINTI AB. AZIZ

ARKITEK
QAMARAH BINTI ABUL SHUKOR

PROJEK
CADANGAN MEMBINA DAN MENYIAPKAN
MASJID SEKSYEN 24 SHAH ALAM, DALAM
DAERAH PETALING, SELANGOR DARUL
EHSAN

PERUNDING ARKITEK
RIZAL OSMAN ARCHITECT • R O A
7-2 Jalan PJU 7/7A,
Mutiara Damansara
47800 Petaling Jaya
Selangor Darul Ehsan
Email : admin@roaarchitect.com
Tel : 603 7731 1144

KONSULTAN UKUR BAHAN
HAH ASSOCIATES
42-2 Jalan Wangsa Setia 4
Wangsa Melawati
53300 Kuala Lumpur

JURUTERA SIVIL DAN STRUKTUR
"Saya memperakui detail-detailed dalam pelan-pelan ini adalah mengikut
kehendak-kehendak Atla 133 Jalan, Parit & Bangunan 1574 dan saya
setuju terima tanggungjawab penuh dengan sejawatnya"



Ir. ROFIE BIN SARBINI
ROADNET SOLUTIONS SDN BHD (793352-7)
Consulting Engineers & Project Manager
Civil, Structural and Traffic
No.53B, Jalan BRP 1/4, Bukit Rimah Putra,
47000 Sungai Buloh, Selangor Darul Ehsan
Tel: 03-6150 0757, Fax: 03-6157 5852
H/P: 019 - 2712 142 Email : roadnetsolutions@gmail.com

PERKARA
STRUCTURAL
PILECAPS & COLUMN REINF. SCHEDULE

| | |
|---------------------------------------|---------------------|
| UKURAN : | |
| DILUKIS : mZ | DISEMAK : WAN/SITI |
| TARIKH : NOVEMBER 2017 | NO. FAIL : |
| NO. LUKISAN : RSSB/JKR/MSJ24/ST/CS/01 | NO. LUKISAN : 11213 |