FINAL YEAR PROJECT REPORT ADVANCED DIPLOMA IN CIVIL ENGINEERING SCHOOL OF ENGINEERING MARA INSTITUTE OF TECHNOLOGY SHAH ALAM

STUDY ON THE BEHAVIOUR OF THE CONCRETE SLEEPER

BY: MOHAMAD KAMAL IDRIS MAY 1993

ACKNOWLEDGEMENTS

I would like to express my sincere thanks to my advisor Puan Siti Hawa Hamzah and Puan Afidah Abu Bakar for their highly valuable guidance, advice and encouragement in carring out this thesis.

Thanks are also due to the staff of the Department of Civil Engineering for their assistance in the performance of the experiments, directly or indirectly towards the completion of the experimental works.

Finally I wish to express my special gratitude to my mum and dad who have given their encouragement and support during my period of study in ITM.

SYNOPSIS.

This experimental project consists of preparing, fabricating and testing of prestressing post-tensioning concrete sleeper. The test specimen is tested simply supported and two point loads placed on the location of rail seats. The load applied until the prestressed post-tensioned concrete sleeper fails.

In this study only two samples of concrete sleeper is prepared and tested. The experimental results will be compared to the finite element programe "ANALYSIS SYSTEM" (ANSYS).

The test specimen load-deflection relationship, load-strain relationship will be produced, and the location of cracking will be shown.

TABLE OF CONTENTS

,		PAGE NO.
SYNOPSI	i	
ACKNOW	ii	
TABLE O	iii	
LIST OF FIGURES		v
LIST OF TABLES		vii
CHAPTE	CR 1	
1.0	Introduction.	1
1.1	Structural behaviour.	3
1.2	Prestressed concrete sleeper.	6
		_

C

1.0	Introduction.	1
1.1	Structural behaviour.	3
1.2	Prestressed concrete sleeper.	6
	1.21 Post-tensioning concrete sleeper.	8
	1.22 Pretensioning concrete sleeper.	13
1.3	Advantages of concrete sleeper track.	14
1.4	Railroad component.	16
1.5	Objective and scope.	19

CHAPTER 2

2.0	Analysis and design.	21
2.1	General.	21
2.2	Redesign the concrete sleeper.	24
2.3	Concrete mix design.	26
	2.31 Mix design calculation.	28

1.0 INTRODUCTION

Generally prestressing can be defined as the application of a predetermined force or moment to a structural member in such a manner that the combined internal stresses in the member, resulting from this force or moment and from any anticipated condition of external loading, will be confirmed within specific limit (after James R. Libby, 1977).

Prestressed concrete goes two steps beyond reinforced concrete :

- i. all the concrete on the tensile side of neutral axis is put under an initial compressive stress of such a magnitude that all design loads which are to be applied to the structure in the future can reduce this stress but will not put the concrete in tension.
- the prestress is applied in such a manner that it creates a moment of opposite sign to those which will be produced by applied dead and live loads.

In the ideal design this negative moment carries all the dead loads and creates the maximum allowable compressive stress in the concrete on the tensile side of the member.

The principles of prestressing have been applied to steel, timber, concrete and other materials. Both axially loaded and flexural members can be prestressed. Whether prestressing is applied to concrete, steel or orthes, its ultimate purpose is two folds :

1