



**DEPARTMENT OF BUILDING SURVEYING  
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING  
UNIVERSITI TEKNOLOGI MARA**

**THE USE OF LOW HEAT CONCRETE IN PILE CAPS  
CONSTRUCTION**

**CASE STUDY:  
THE CONSTRUCTION OF A NEW BUILDING AT  
KOMPLEKS KOTA DARULNAIM, KOTA BHARU, KELANTAN.**

**MUHAMMAD NAZIF BIN BAHARUDDIN  
2011641662  
DIPLOMA IN BUILDING SURVEYING**

**PRACTICAL TRAINING REPORT  
DECEMBER 2013 – APRIL 2014**

DECLARATION:

I hereby admit that this report is the result of my own efforts, except for the certain parts that are attached from sources that specified in reference chapter.

Prepared By:

.....  
( )

Date:

Approved By:

.....  
( )

Supervising Lecturer

Date:

## **ACKNOWLEDGEMENT**

Regard to blessing from Allah finally, I successfully completed practical training in Kelantan Public Works Department for 14 weeks starting from 25 November 2013 until 29 March 2014 as determined by the faculty. First of all, I would like to thank the involved who guide, encouragement and ideas given to me during my industrial training in this department. Indeed, all the knowledge and guidance may be used to best for my future and will be used in later the working environment.

Other than that, I also would like to thank to Mrs. Intan Bayani Binti Zakaria for full supported and responsibility as a good supervisor and lecturer who has given me a lot of knowledge until I completed my practical training report. An exposure to the introduction of the report and showed their effort to prepare me a basic knowledge before I start with my report. I appreciated to all who involved and given a support either directly or indirectly to help this research complete, thanks a lot.

Besides that, I would like to thank to Ir. Hj. Zakaria Bin Semail as Assistant Director of the Department of Building and Kelantan PWD staffs on construction project new building of the Kelantan State Secretary, En. Mohd Taha Bin Suman as Civil Engineer, En. Aswami Bin Ariffin as Assistant Civil Engineer and En. Hj. Wan Azmi Bin Wan Sulaiman as Technician to guide and entertained me with some related information about this construction project to complete and finished our case study.

I pray may this report may credits with high mark and also as the references to others in the future. May ALLAH S.W.T. give HIS bless to me,

Insyallah, Thank you...

NO.	CONTENTS	PAGE
1.	<b>CHAPTER 1 : COMPANY BACKGROUND</b> 1.0 Introduction 1.1 Organization Structure 1.2 Organization Background 1.3 Location Plan 1.4 Organization Chart 1.5 Vision and Mission 1.6 Department's Scope of Work 1.7 Chapter Summary	2 2 3 5 6 7 8 11
2.	<b>CHAPTER 2 : LITERATURE REVIEW</b> 2.0 Introduction 2.1 Composition of Concrete 2.2 Classification of Concrete Mixes 2.3 Concrete Production 2.4 Quality of Concrete 2.5 Testing of Concrete 2.6 Controlling Temperature of Concrete 2.7 Problem of Concrete Structure 2.8 Chapter Summary	13 14 16 17 20 21 25 28 29
3.	<b>CHAPTER 3 : CASE STUDY</b> 3.0 Introduction 3.1 Parties Involves 3.2 Organization Chart Construction Site 3.3 Location Site 3.4 Type of Concrete Used 3.5 Location of Low Heat Concrete Application 3.6 Method Statement of Construction Pile Caps 3.7 Controlling Temperature of Concrete 3.8 Chapter Summary	31 32 33 35 36 38 39 56 60
4.	<b>CHAPTER 4 : PROBLEMS AND RECOMMENDATIONS</b> 4.0 Introduction 4.1 Problems 4.2 Recommendations 4.3 Chapter Summary	62 63 64 65
5.	<b>CHAPTER 5 : CONCLUSION</b>	67
6.	<b>REFERENCES</b>	69
6.	<b>APPENDICES</b>	70

## LIST OF FIGURE

NO. FIGURE	TITLE	PAGE
Figure 1.1	Show the Kelantan Public Works Department	3
Figure 1.2	Location Plan of Kelantan Public Works Department	5
Figure 1.3	Organization chart of Building Department	6
Figure 2.1	Show the slump test equipment.	21
Figure 2.2	Slump test method	22
Figure 2.3	Show the concrete cube equipment	23
Figure 3.1	The construction of a new building State Secretariat	31
Figure 3.2	Location of the construction site	35
Figure 3.3	Proposed Design Mix from Real Mix Concrete Sdn. Bhd.	37
Figure 3.4	Show the pile caps	38
Figure 3.5	Show the installation of lean concrete	39
Figure 3.6	Show the installation of formwork	41
Figure 3.7	Work to bend steel reinforcements	42
Figure 3.8	Show the installation of steel reinforcement in the pile cap	43
Figure 3.9	Show the installation of concrete spacer and tying wire.	43
Figure 3.10	Position of thermocouple sensor wire on the pile cap	44
Figure 3.11	The thermocouple wires placed in PVC pipes	45
Figure 3.12	Position of PVC pipes in the pile cap	45
Figure 3.13	Show the thermocouple wires connected to the data logger	46
Figure 3.14	Data logger (CAMPBELL SCIENTIFIC CR10X).	46
Figure 3.15 (a) and (b)	Inspection carried out by the PWD and the contractor	47
Figure 3.16	Show the concrete truck arrived at the construction site	48
Figure 3.17	Show the concrete filled into the mold	49
Figure 3.18	Showing every layer is compacted using a rod	49
Figure 3.19	Showing measure slump	50
Figure 3.20	The slump test fails	50
Figure 3.21	Show the mold coated with oil	51
Figure 3.22	Show the concrete filled and stamped by 35 times	51
Figure 3.23	Show the top surface of the cube flattened.	52