



DEPARTMENT OF BUILDING SURVEYING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA

TITLE
(ARCHITECTURAL FINISHING WORK)

RAIS ADLAN BIN RUZAIDI
(2011847844)
DIPLOMA IN BUILDING SURVEYING

PRACTICAL TRAINING REPORT
NOVEMBER 2013 – MARCH 2014

DEPARTMENT OF BUILDING SURVEYING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING

ARCHITECTURAL FINISHING WORK

NOVEMBER 2013–MARCH 2014

This practical training report is fulfillment of the practical training course

PREPARED BY : RAIS ADLAN BIN RUZAIDI

SUPERVISING LECTURER: Sr. MOHD ZAKI BIN SAMSUDDIN

DECLARATION

I hereby admit that this report is the result of my own efforts, except for certain parts that are attached from sources that specified in reference chapter.

Prepared by:

.....

(Rais Adlan Bin Ruzaidi)

Date :

Approved by:

.....

(Sr. Mohd Zaki B Samsuddin)

Date :

ABSTRACT

In any construction, finishing work play the role of impression to the public instead of providing comfort and safety. People will conduct the first credit for any structure or building by having a look through the design, types and finishes of building. Thus, the people manage to decide in their mind either the building is attractive or lame.

Apart from that, there are more functions of the finishing works and also act as a vital stages in any building construction which divided into floor finishing, wall finishing and ceiling finishing in order to complete the view and symbolic of the element itself.

Meanwhile, brickwall is the common used material that fitted to propose the external wall and plastering and paint as its finishes for construction in Kelantan. Besides that, mostly building in Kelantan has its own symbolic facade in virtue to accomplish “The Islamic Town” by constructing dome shape arch.

During the practical period in Kelantan where the site is specifically located in Pekan Rantau Panjang under the Binaraya PKINK company, the construction works are fully done through the structural work since the practical started. What is only left are finishing work and cleaning work. Thus, it is a constraint and limitation to develop the knowledge in construction.

By hook or by crook, during the period, the study of architectural finishing work is the topic gained for increasing the knowledge.

ACKNOWLEDGEMENT

First and above all, I praise Allah, the almighty for providing me this opportunity and granting me the capability to proceed successfully. This report in its current form due to the assistance and guidance of several people. I would therefore like to offer my sincere thanks to all of them throughout the training period starting from 25th November 2013 until 29th March 2013.

I want to express my deep thanks to my esteemed supervisor lecturer Sr. MOHD ZAKI B. SAMSUDDIN for the trust, the insightful discussion, offering valuable advice, for your support during the whole period of training, and especially for your patience and guidance during the discussion process.

My deepest appreciation goes to my supportive site supervisor EN. WAN HANAPI B. WAN HASSAN for his excellent advises, detailed review during the preparation of this report and his friendly assistance with various problems all the time, especially showing me and sharing with me his experiences and knowledges about the development of construction work. Along with this opportunity, I would like to apologize on behalf of any inconveniences from me to him as well as his knowledge in guiding me is sincere.

Apart from that, I would like to propose my gratitude to Binaraya PKINK company for the cooperation, comfortable services and acceptance in bringing me in to learn and gain knowledges as much as it could and experiences in facing the real situation of construction work during the training period.