DEPARTMENT OF BUILDING SURVEYING FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING UNIVERSITI TEKNOLOGI MARA CAWANGAN PERAK KAMPUS SERI ISKANDAR

FLOOR FINISHES

DECEMBER 2016 – MARCH 2017

This practical training report is fulfilment of the practical training course.

PREPARED BY	:	EDDIE FIRDAUS BIN FARID
SUPERVISING LECTURER	:	SR. MOHD NURFAISAL BAHARUDDIN

DECLARATION:

I hereby admit that this report is the result of my own efforts, except for the certain parts that are attached from sources that specified in reference chapter.

Prepared By:

(EDDIE FIRDAUS BIN FARID)

Approved By:

(SR MOHD NURFAISAL BAHARUDDIN)

Date:

Date:

TABLE OF CONTENTS

ACKNOWLEDGEMENT	
ABSTRACT	2
INTRODUCTION OF PROJECT / ORGANIZATION REVIEW	
A. Introduction of company	3
B. Vision and Sustainability	4
C. Awards and Achievement	5
D. Organization	7
E. Project	9
F. Summary	12
CHAPTER 1.0: THEORICAL STUDY / LITERATURE REVIEW	
1.1 Introduction of floor finishes	13
1.2 Type of floor finishes	15
1.3 Definition of tiles	16
1.4 Criteria of selecting flooring	22
1.5 Operations required before taking up flooring work	24
1.6 Method Statement	25
1.7 Inspection and Testing Plan	33
1.8 Quality Assurance and Quality Control	
1.9 Summary	40
CHAPTER 2.0: CASE STUDY	
2.1 Introduction Case Study	41
2.2 Type of floor finishes	42
2.3 Tools and Equipment	43
2.4 Work process for tiling work	46
2.5 Work process for tactile	48
2.6 Method Statement	50



PROJEK MASS RAPID TRANSIT LEMBAH KELANG - JAJARAN SUNGAI BULOH - KAJANG



ACKNOWLEDGEMENT

Alhamdulillah, praise to Allah, the Most Merciful, the Most Graceful.

First of all, I would like to disclose my heartfelt to some amazing individuals for the guidance, and advice throughout 5 months, the period of my internship at MMC Gamuda (PDP) Sdn Bhd. The most important is, I would like to thanks to Mr Razlan Ramali (Senior Engineer) for the chance given being my main supervisor for 5 months and conduct me for the this project. Not forget also thanks to Mr Yeow Yew Chee (Construction Manager) as second supervisor for give me many new experience including develop my understanding, knowledge, and feel of the real situation of site working, and some information of architectural finishes and civil work in theory form. Then, I could like to give my sincere credit to the site personnel and officemates who have extend their cooperation and help for me to learn and understanding more about the project. It is a big honour for me to be one of PDP team even though it is only for 5 months.

I also like to extend my thanks to all the UiTM lecturer who have taught me and my fellow friend to become a better student and youth in future, InshaAllah. My big appreciation goes to the lecture who involve directly during my training session to En. Sr. Mohd Nurfaisal Baharuddin as supervising lecturer. I appreciate your time, effort and ideas given to us for the sake of finishing this semester with successfully. Insha Allah.

Last but not least, my special thanks to my great supporters, which is my beloved family. Because of their moral support, I can complete my industrial training without any trouble or harm. Thank you so much.



PROJEK MASS RAPID TRANSIT LEMBAH KELANG - JAJARAN SUNGAI BULOH - KAJANG



ABSTRACT

This report explains about process and how to install floor finishes. Tiling is an important element in the super structural, which is determine the aesthetic of the building. This report is divided into several parts and start from introduction of company. From the observation, tiling work is not easy to install because it is finishes and must wait others work done before install it if not the tile must be break and install new. In this project, there are using 5 type of floor finishes in different room and different place. This report can explain in more detail about the process and method to install floor finishes.