



**DEPARTMENT OF BUILDING SURVEYING
FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING
UNIVERSITI TEKNOLOGI MARA**

**CONSTRUCTION OF SHEAR WALL AT PROJEK PERUMAHAN
RAKYAT (PPR) DAERAH HILIR PERAK**

**MUHAMMAD EZAUDIN BIN ABD RAZAK
2012219458
DIPLOMA IN BUILDING SURVEYING**

**PRACTICAL TRAINING REPORT
DECEMBER 2014 – APRIL 2015**

DECLARATION:

I hereby admit that this report is the result of my own efforts, except for the certain parts that are attached from sources that specified in reference chapter.

Prepared By:

.....

(MUHAMMAD EZAUDIN BIN ABD RAZAK)

Date: 6 APRIL 2015

Approved By:

.....

(EN. MOHD DZULKARNAEN BIN SUDIRMAN)

Supervising Lecturer

Date: 6 APRIL 2015

ACKNOWLEDGEMENT

بِسْمِ اللَّهِ الرَّحْمَنِ الرَّحِيمِ

First of all, a full gratitude to Allah S.W.T., I have been given the opportunities to complete the Practical Training Report perfectly on the stipulated time given. I would like to dedicate my appreciations for those who had sacrifice a lot and spend much time to lend a helping hand, giving a supportive advices and constructive criticism and opinions in finishing this practical training report especially to En. Mohd Dzulkarnaen Bin Sudirman who has been a very encouraging supervising lecturer for guiding me throughout the completion of this report.

Special thanks also dedicated to those who are directly involved in helping me experiencing my practical training phase in JKR Hilir Perak especially to the all staff in Department of Senggara Persekutuan who have been very cooperative and supportive during my practical training by giving me beneficial advices and knowledge. Also, thousands of thanks also dedicated to Encik Mohd Hafiz, site engineer of the project who have been very helpful guiding me along in my training phase and to the district engineer, En. Ahmad Roslan Bin Bidin for giving me the opportunity to undergo practical training in JKR for about 4 months. Millions thanks also dedicated to Encik Nor Amin Mohd Radzuan ,the practical training coordinators and all the lecturers of Building Surveying Department that have been extremely helpful all the way

ABSTRACT

Generally, this report describes the practical information about all the processes and methods in the construction of shear walls in Projek Perumahan Rakyat (PPR). Practical training report is provided by the day to obtain all the information about the construction of shear walls in PPR about 4 months of practical training in JKR Hilir Perak. Practical training report begins with an explanation of the company's background and the background of the project. According to a study, there are several steps that should be taken during the construction of the shear wall is done. These steps should be followed to avoid any damage or defect occurs when the building is completed to build. Further, the report also explains about the materials used to build shear walls and equipment used during construction work done. In addition, there are several problems that can be encountered in construction work of shear wall such as factor of safety for workers. Also described in this report together with the appropriate measures for the solution. As a conclusion, this practical training reports can expound on shear wall construction from beginning to end.

LIST OF CONTENT

CONTENT	PAGES
ACKNOWLEDGEMENT	I
ABSTRACT	III
LIST OF CONTENT	IV
1.0 COMPANY BACKGROUND	1
1.1 History of JKR Hilir Perak	2
1.2 Information of JKR Hilir Perak	3
1.3 Location of JKR Hilir Perak	4
1.4 Company Profile	5
1.4.1 Vision	5
1.4.2 Mission	5
1.4.3 Objective of JKR	6
1.4.4 Charter of JKR	6
1.4.5 Quality Policy	7
1.4.6 Motto of JKR	7
1.5 Logo of JKR	8
1.5.1 Description of Logo	8
1.5.2 Colour	9
1.5.3 Colour Code	9
1.6 Function of JKR	9
1.7 Organization Chart of JKR	10
2.0 LITERATURE REVIEW	11
2.1 Introduction of Shear Wall	12
2.1.1 Concrete shear wall	13
2.1.2 Strength of Shear Wall	13
2.1.3 Material of Shear Wall	13
2.2 Types of Shear Wall	17
2.2.1 Positioning of shear wal	19
2.3 Introduction of IBS	21
2.4 Types of IBS	23
2.5 Advantages of Shear Wall	25
2.6 Disadvantages of Shear Wall	27