



اَوْنُوْزِ سِيْتِيْ بِاَتِيْكَوْ لُوْ كِيْ بِاِنْبَارَا
UNIVERSITI
TEKNOLOGI
MARA

FACULTY OF CIVIL ENGINEERING

INDUSTRIAL TRAINING REPORT

MUHAMMAD AFIF BIN ABU TALIB

(2016616536)

DEWAN BANDARAYA KUALA LUMPUR

JABATAN KEJURUTERAAN AWAM DAN PENGANGKUTAN BANDAR

TINGKAT 8, MENARA DBKL 2, JALAN RAJA LAUT, 50350,

KUALA LUMPUR

JULAI – SEPTEMBER 2019

ABSTRACT

The purposes of written this report is to explain about the Industrial Training. The scope of study is engineering and the various environments at Jabatan Kejuruteraan Awam Dan Pengangkutan Bandar.

The importance of internship is to give exposure to the students the real situation in engineering professions. Besides, it also can build and increase positive and critical thinking when overcoming engineering problems with the suitable and rational solution.

Jabatan Kejuruteraan Awam Dan Pengangkutan Bandar responsible for the road in Kuala Lumpur and the DBKL project. Every road closure, maintenance of the road and transportation including construction project will be handle by JKAPB.

At JKAPB, the entire applicants for road closure need to submit their form to this department for the approval. If the applicants close the road without getting the approval, Jabatan Penguatkuasa will fine them. This seems small issue, but it is important to ensure everybody comforts and to avoid any complain from the road users. Furthermore, JKAPB also does open tender for road marking after prepared the Bill of Quantities. After that, all of the tender will be process and the contractor will be picked based on their experience with the infrastructure works.

Last but not least, during the Industrial Training, students are well exposed to the real working environment and challenges in many natures of works such as in JKAPB. Through many situations and problems encountered, the students can obtained a lot of new inputs and skills which is useful under the guidance of experienced people.

ACKNOWLEDGEMENT

First and foremost, I like to express my gratitude to Allah for giving me the health and time to complete my Industrial Training in this department. I also would like to thanks Institut Latihan Dewan Bandaraya (IDB) for accepting me as their practical students and placed me at JKAPB during my 8 weeks of training from 5 July 2019 until 1 September 2019. I also like to express my thanks to Encik Amirul Ain Bin Amran because the willingness to accept me under his guidance and supervise. I also like to express my gratitude to Encik Sulaiman Bin Ramli as my guidance when Encik Amirul Ain absence. Also, all the employee at Jabatan Kejuruteraan Awam Dan Pengakutan Bandar for helping me during my Industrial Training. Furthermore, my thanks to other practical students at the department that willingly helps me during my journey at JKAPB. Lastly, all the people that have help me unconsciously during my Industrial Training.

CHAPTER 1: INTRODUCTION

1.1 Introduction

The Industrial Training (IT) begin on 5 July 2019 until 1 September 2019. There were a few days of delay on reporting day as on 5 July 2019, the final examination still does not finish as UiTM Pasir Gudang experienced gas attack and need to be close for their student safety. Therefore, the delay letter was sent to the Institut Latihan Dewan Bandaraya (IDB) to inform the delay. The reporting day was change to 18 July 2019 and I was placed at Menara DBKL 2, Jalan Raja Laut. The person that was in charged in supervising me was Encik Amirul Ain Bin Amran, one of the Senior Engineer at the office.

1.2 Background Company

The department that I was placed is Jabatan Kejuruteraan Awam Dan Pengangkutan Bandar (JKAPB). This department mostly in charged in road marking, road closure for event or contruction and transportation. A few members of Agensi Pengangkutan Awam Darat (APAD) also was placed there to assist on the transportation part. Every issue regarding road closure need to be approve by this department and the organizer need to get permit on road closure from this department if the work or event inside of Kuala Lumpur.

1.3 Organizational Structure




FIGURE: ORGANIZATION CHART OF JKAPB

1.4 Nature of Business

As I have explained in the introduction, JKAPB mostly will handled all the road closure, road marking, road furniture and transportation. Other than that, JKAPB also will handled all the DBKL project in Kuala Lumpur. Every contractor or event organizer that want to close the road in Kuala Lumpur for their project, required the permit of approval from this department. Therefore, this department is quite important in Dewan Bandaraya Kuala Lumpur to ensure all the road in Kuala Lumpur does not troubled the user.

1.5 Conclusion

As a conclusion, this department will take care of every road in Kuala Lumpur in terms of road improvement and closure. Without this department, Kuala Lumpur will be hustle and bustle than it already be.

CHAPTER 2: TRAINING ATTENDED

2.1 Introduction

The operation hours were divided into three timing which is the first one from 7.30 am until 4.30 pm, the second one from 8.00 am until 5.00pm and the last one from 8.30 am until 5.30 pm. The time that I have chosen was from 8.00 am until 5.00 pm. All the practical student has been assigned a punch card to ensure that the attendance will always be recorded.

2.2 Exposure Level

During the duration of Industrial Training, I have experienced every aspect that I has learned in class but mostly I have improved on managing skills. All the time that I have spent on the Industrial Training at Jabatan Kejuruteaan Awam Dan Pengangkutan Bandar (JKAPB) mostly was doing management task. I mostly handling the Task Force meeting. The Task Force meeting actually was more complicated to handle than it seems as it needed communication skills, scheduling and accuracy. This is because every organizer and the contractor need to be contacted to inform them regarding the time, date and matter that will be discuss. Other than that, the Task Force panel need to be informed also. The panel consist of Timbalan Pengarah Encik Jeyapalan A/L K.Selvadurai, Encik Amirul Ain, Encik Sulaiman, representative from Malaysian Institute of Road Safety Research (MiROS), representative from PDRM and representative from Jabatan Penguatkuasa. All the panel will be receiving letter via fax. This will become the problem where the fax machine on the receiving end was under maintenance, it will result in the absence of the panel in the meeting. The way to overcome the problem by calling each of the panel to inform them to ensure they get the message because every panel has their respective roles and very important. The absence of the panel will result in delay of the approval. For event organizer, it may seems not much, but for contractor, it actually matter because the delay of the approval will result in the delay of the completion time of the project. Therefore, handling Task Force meeting teach me the accuracy of every work and how to manage and handle every problem persist as quickly as possible.



FIGURE: TASK FORCE MEETING

Other than that, I also have completed a few Bill of Quantities for road marking. During this task, I was required to capture a few pictures of the condition of road marking at the site. Therefore, I need to go to the site myself. The Bill of Quantities for road marking must be precise as the allocations for road marking only a few millions per year. Therefore, the allocation needs to be used up because it will be easier for the release of the tender. From this Bill of Quantities, I also learned that precision is important because during my Industrial Training, there a few problems persist for road furniture unit where the expense was more than the allocations. This proves that even smallest number can become great problem later on.



FIGURE: CONDITION OF ROAD FOR BILL OF QUANTITIES

Lastly, for the weeks that I was assigned at the construction site at Jalan Jelatek, I have been exposed on design and their flaws. This is because; the bridge project was delayed because of the overlapped with DUKE FASA 3 Project. This project limit of work has consumed the limit of work for the bridge project. The surveyor for DUKE project has miscalculated the distance for their pilling. The bridge project cannot be continued until the middle of September to wait the DUKE project to overcome their problem. From these problems, I have understood that real work of civil engineer was not an easy task that everybody can carry out. One problem can make others people life miserable.



FIGURE: VISIT TO CONSTRUCTION SITE

2.3 Conclusion

As a conclusion, every engineer required the accuracy, precision, managing skills and communication skills mastered in themselves as these is compulsory skill to go through life as an engineer. From this Industrial Training that I understand this field was crucial in the world and not an easy field to dive yourself in. Engineers basically bear countless responsibilities during the project.

3.4 Conclusion

As a conclusion, Jabatan Kejuruteraan Awam dan Pengangkutan Bandar plays a huge role in managing Kuala Lumpur in DBKL behalf. Without JKAPB, no department will handle the road closure, the maintenance of the road and all the DBKL project. So, by attending Industrial Training at JKAPB really teaches me that the real world was not easy as it seems.

REFERENCES

1. Industrial Training Handbook
2. Minute Meeting of RB6305 – CADANGAN MENGGANTIKAN JAMBATAN KONKRIT SEDIA ADA KEPADA JAMABTAN KONKRIT MERENTANGI SUNGAI KELANG DI JALAN JELATEK, KUALA LUMPUR.
3. Perkara Yang Anda Tidak Perlu Tahu Untuk Pengurusan Jalan Jilid 3 (Jabatan Kerja Raya)
4. Bahagian 10 – Section 9A – Concrete (UHPC)
5. Bahagian 10 – Section 10 – Piling Works

APPENDICES

List of appendix

Appendix A : Form/Letter

1. Industrial Training Placement Information Form (UiTM.FKA.LI-01)
2. Industrial Training Application Letter (UiTM.FKA.LI-02)
3. Example Of Resume (CV) (UiTM.FKA.LI-03)
4. Industrial Training Placement Confirmation Form (UiTM.FKA.LI-04)
5. IT Report Duty Form (UiTM.FKA.LI-05)
6. Current Location Information Form (UiTM.FKA.LI-06)

Appendix B: Assessment

1. IT Report Evaluation Form (UiTM.FKA.LI-07)
2. IT Log Book Evaluation Form (UiTM.FKA.LI-08)
3. Industrial Supervisor Evaluation Form (UiTM.FKA.LI-09)
4. Faculty Supervisor Evaluation Form (UiTM.FKA.LI-10)

Appendix C: Course Outcomes

INDUSTRIAL TRAINING PLACEMENT INFORMATION FORM
(*Borang Matlumat Penempatan Latihan Industri*)

A) STUDENT INFORMATION (*Matlumat Pelajar*)

Name (*Nama*) : :
Programme : **UiTM No.** (*No. UiTM*)
(program) : **ID No.** (*No. k/p*)
Session (*sesi*) : **Semester** (*Semester*) :
Address (*alamat*):

Phone (*Telefon*) : **Mobile No.**(*No. h/p*) :

Email (*emel*) :

B) HEIRS (*Waris*)

Name (*Nama*) :
Address (*alamat*):

Phone (*Telefon*) : **Mobile No.**(*No. h/p*) :

C) PLACEMENT OPTIONS (*Pilihan penempatan*)

No. (Bil.)	State (Negeri)	City (Bandar)
1.
2.

C) ORGANIZATION INFORMATION (*Matlumat organisasi*)

Name (*Nama*) :
Address (*alamat*):

Contact Person (*Pegawai yang boleh dihubungi*) :

Designation (*Jawatan*) :

Phone (*Telefon*) : **Mobile No.**(*No. h/p*) :

Fax No. (*No. Fax*) : **Email** (*emel*) :

.....
 Signature (*Tandatangan*) Date (*tarikh*)

Office use:	Checked by:	Approved by:
--------------------	--------------------	---------------------

UiTM.FKA.LI-02

Surat Kami : 100-UiTMKPG(FKA14/3/4)
Tarikh :

.....
.....
.....
.....
.....
.....

Tuan,

**PERMOHONAN PENEMPATAN LATIHAN INDUSTRI BAGI PROGRAM DIPLOMA
KEJURUTERAAN AWAM (EC110)**

Nama: :
No. Kad Pengenalan: :
No. Pelajar UiTM :
Program :
Semester :

2. Saya dengan ini mengesahkan bahawa butir-butir peribadi dan akademik di atas adalah seorang pelajar di Fakulti Kejuruteraan Awam, UiTM , Pasir Gudang.

3. Sukacitanya jika pihak Tuan dapat menerima pelajar tersebut untuk menjalani Latihan Industri untuk tempoh **LAPAN (8)** minggu bermula pada sehingga sebagai pra-syarat untuk lulus. Sebagai makluman, pelajar dilindungi oleh insurans sepanjang tempoh latihan.

4. Jika Tuan bersetuju untuk penempatan pelajar ini, saya memohon jasa baik pihak Tuan untuk memaklumkan kepada pihak saya dengan melengkapkan "Borang Pengesahan Penerimaan" (lampiran UiTM.FKA.LI-04) dalam tempoh **DUA (2)** minggu daripada tarikh surat ini. Jika tidak ada sebarang maklum balas daripada pihak Tuan, permohonan ini dianggap **TIDAK BERJAYA**.

5. Latihan industri yang akan dijalankan selama 8 minggu adalah sangat pendek, tetapi ia sangat bermakna untuk membantu Universiti dalam menghasilkan bakal jurutera yang berdedikasi, cekap dan berdaya saing selepas tamat pengajian.

6. Fakulti Kejuruteraan Awam UiTM Kampus Pasir Gudang amat menghargai kerjasama pihak Tuan dalam semua hal yang berkaitan dengan latihan industri pelajar Fakulti Kejuruteraan Awam UiTM Kampus Pasir Gudang.
Terima kasih.

Yang benar,

Koordinator Latihan Industri
Fakulti Kejuruteraan Awam
UiTM Cawangan Johor
Kampus Pasir Gudang.

s.k 1) Ketua Pusat Pengajian Kejuruteraan Awam, UiTM Pasir Gudang

Example of Resume (CV) (UITM.FKA.LI-03)

RESUME**PERSONAL DETAILS**

Name :
 Identification No. :
 Date of Birth :
 Place of Birth :
 Age :
 Sex :
 Marital Status :
 Race :
 Religion :
 Citizenship :
 Postal Address :
 Mobile Phone No. :
 E-mail :

EDUCATIONAL BACKGROUND

Year / Period	Institution	Level	Achievement / Award

EXTRA-CURRICULAR ACTIVITIES

Year / Period	Programme / Activity	Location	Participation

WORKING EXPERIENCE

Year / Period	Organisation	Designation	Responsibilities

SKILLS

Language skills :

Language	Written	Speaking

Computer Literacy:

Other skills :

HOBBIES

No.	Description

ACADEMIC REFEREES

1. Name :
 Designation :
 Organisation :

2. Name :
 Designation :
 Organisation :

Tel. No. :
 Email :

Tel. No. :
 Email :



UiTM.FKA.LI-04

Rujukan Kami : 100-
 UiTMKPG(FKA14/3/4)
 Tarikh :

Koordinator Latihan Industri
 Fakulti Kejuruteraan Awam
 UiTM Johor Kampus Pasir Gudang,
 Jalan Purnama 81750 Masai Johor.
 (u/p: **Mohamed Khafif Tawaf**, mohdkhatif@johor.uitm.edu.my)
 Fax: 07-3818141

PENGESAHAN PENERIMAAN PELAJAR EC110 UNTUK LATIHAN INDUSTRI TAHUN

Merujuk kepada surat/faks Tuan yang bertarikh adalah disahkan pihak kami ***menerima / tidak menerima** pelajar Tuan ' bernama dan nombor pelajar untuk menjalani latihan industri mulai hingga **(8 minggu)** di organisasi /syarikat kami.

Butiran Latihan:

Tarikh melaporkan : _____
Masa melaporkan : _____
Alamat melaporkan / : _____
ditempatkan : _____

Kami juga bersedia untuk menyediakan kemudahan berikut**:

1. Penginapan
2. Pengangkutan
3. Makanan dan minuman
4. Elaun bulanan
5. Kemudahan lain (sila nyatakan jika ada): _____

Ada	Tiada

Sekian, terima kasih.

Yang benar,

(NAMA DAN COP ORGANISASI/SYARIKAT)

Sila faks / emailkan kembali surat ini kepada Fakulti Kejuruteraan Awam, UiTM Pasir Gudang selewat-lewatnya 2 minggu dari tarikh surat permohonan ini.

* Potong mana tidak berkenaan.

**sila tandakan (√) bagi yang berkaitan

Fakulti Kejuruteraan Awam
Faculty of Civil Engineering
Tel : 607-3818309 / 8339 / 8328
Fax: 607-3818141

UNIVERSITI TEKNOLOGI MARA
CAWANGAN JOHOR
Kampus Pasir Gudang, 81750 Masai, Johor.
Te: 607- 3818000 Fax: 607- 3818141



UITM.FKA.LI-05

Our Reference: 100-UITMKPG(FKA14/3/4)
Date:

To:
Industry Training Coordinator,
Faculty of Civil Engineering
Universiti Teknologi MARA
Cawangan Johor Kampus Pasir Gudang
Jalan Purnama 81750 Masai Johor

Dear Sir / Madam

**INDUSTRIAL TRAINING REPORT DUTY VERIFICATION
SESSION**

The above matter is referred.

Please be informed that the following students has reported for Industrial Training to our company / organization on _____ (completed by the company/ organization) as stated.

STUDENT NAME :
STUDENT NO. :
ID NO. :
PROGRAMME :
SEMESTER :
REPORT DATE :
INDUSTRIAL TRAINING ADDRESS :

DURATION / PERIOD :

Thank you.

Yours sincerely,

.....
(Signature and Company /Organization Stamp)



CURRENT LOCATION INFORMATION FORM
(Borang Matlumat Penempatan Semasa)

A) STUDENT INFORMATION *(Matlumat Pelajar)*

Name *(Nama)* : **UiTM No.** *(No. UiTM)* :
Programme *(program)* : **ID No.** *(No. k/p)* :
Session *(sesi)* : **Semester** *(Semester)* :
Address *(alamat)* :
Phone *(Telefon)* : **Mobile No.** *(No. h/p)* :
Email *(emel)* :

B) ORGANIZATION INFORMATION *(Matlumat organisasi)*

Name *(Nama)* :
Address *(alamat)* :
Contact Person *(Pegawai yang boleh dihubungi)* :
Designation *(Jawatan)* :
Phone *(Telefon)* : **Mobile No.** *(No. h/p)* :
Fax No. *(No. Fax)* : **Email** *(emel)* :

.....
 Signature *(Tandatangan)*

.....
 Date *(tarikh)*

* Kindly mail this form to the Faculty of Civil Engineering, UiTM Pasir Gudang via fax/post/email within a week to:

*Industry Training Coordinator,
 Faculty of Civil Engineering
 Universiti Teknologi MARA
 Cawangan Johor Kampus Pasir Gudang
 Jalan Purnama 81750 Masai Johor*

Office use:	Checked by:	Approved by:	
-------------	-------------	--------------	--

(u / p: Mohamed Khatif Tawaf, fax to: 607-3818141 or email: mohdkhatif@johor.uitm.edu.my)



INDUSTRIAL TRAINING STUDENT PLACEMENT REPORT
 (Report Evaluation Form)

A) Student Information

Name :
 Programme :
 Session :
 Date of Commencement :
 UiTM No. :
 ID No. :
 Semester :
 Date of Completion :

B) Organization Information

Organization :
 Name of Supervisor :
 Designation :


C) Faculty Supervisor Information

Name :
 D) Marks

No.	Criteria	CO1-PO5	TOTAL MARKS
1.	Abstract	/5	
2.	Introduction	/5	
3.	Report content	/5	
4.	Conclusion and Recommendation for Industrial Training	/5	
5.	Writing Quality	/5	
CO-PO MARKS		/25	/25

Signature & Official Stamp
 (Faculty Supervisor)

Date





No.	Criteria	5 (Excellent)	4 (Good)	3 (Satisfactory)	2 (Average)	1 (Weak)
4.	Conclusion and Recommendation for Industrial Training <ul style="list-style-type: none"> Conclude the findings of Industrial Training Evaluations on outcomes of training & suitability of the placement. (CO1-PO5) 	<input type="checkbox"/> Able to conclude & evaluate the training outcomes & placement clearly	<input type="checkbox"/> Able to conclude & evaluate the training outcomes & placement with substantial clarity	<input type="checkbox"/> Able to conclude and evaluate the training outcomes & placement with moderate clarity	<input type="checkbox"/> Able to conclude & evaluate the training outcomes & placement with minimal clarity	<input type="checkbox"/> No conclusion on the achievement of training & provide no evaluations on both training outcomes & placement
5.	Writing Quality <ul style="list-style-type: none"> Writing Style Plagiarism as stated in UITM Policy (CO1-PO5) 	<input type="checkbox"/> The report is well organized and supported with sufficient and relevant information	<input type="checkbox"/> The organization of the report is good and supported with substantial evidence	<input type="checkbox"/> The organization of the report is good and supported with satisfactory evidence	<input type="checkbox"/> The organization of the report is satisfactory with minimal support	<input type="checkbox"/> The report is poorly organized and lacked of supporting evidence

*Please tick (✓) at appropriate scale

Percentage earned from Report = Total Marks Earned from Report X 20%

= %

For Faculty Supervisor Response

- i. Would you **recommended** this workplace for future Industrial Training Student Yes No
- ii. If **NO**, please specify the reason



INDUSTRIAL TRAINING LOGBOOK
 (Logbook Evaluation Form)

A) Student Information

Name : UITM No. :
 Programme : ID No. :
 Session : Semester :
 Date of Commencement : Date of Completion :

B) Organization Information

Organization :
 Name of Supervisor:
 Designation :

C) Faculty Supervisor Information


Name :

D) Marks

No.	Criteria	CO1-PO5	TOTAL MARKS
1.	Verification from supervisor	/5	
2.	Attendance	/5	
3.	Technical content	/5	
4.	Allocate problems & analysis	/5	
CO-PO MARKS		/20	/20

Signature & Official Stamp

Date



Logbook Evaluation Form



No.	Criteria	5 (Excellent)	4 (Good)	3 (Satisfactory)	2 (Average)	1 (Weak)
1.	Verification from supervisor. (CO1 – PO5)	<input type="checkbox"/> More than 9 signatures	<input type="checkbox"/> At least 9 signatures	<input type="checkbox"/> At least 8 signatures	<input type="checkbox"/> At least 7 signatures	<input type="checkbox"/> Less than 7 signatures
2.	Attendance. (CO1-PO5)	<input type="checkbox"/> 100%	<input type="checkbox"/> At least 90 %	<input type="checkbox"/> At least 80 %	<input type="checkbox"/> At least 50 %	<input type="checkbox"/> Less than 50 %
Attendance must be at least 40 days including public holidays (if attendance is less than 40 days, the student will fail unless the Industrial Training with a legitimate reason)						
3.	Content at least 80% engineering technical with additional technical specification (drawing, design calculation, picture and safety awareness). (CO1-PO5)	<input type="checkbox"/> All elements are clearly stated with evidence.	<input type="checkbox"/> Engineering and technical specification are described but some details are missing	<input type="checkbox"/> Engineering and technical specification are described but major details are missing	<input type="checkbox"/> Engineering content is described but technical specification is not clearly described	<input type="checkbox"/> Engineering content is not clearly described
4.	Allocate problems & analysis to formulation & solution to real-life. (CO1-PO5)	<input type="checkbox"/> Able to allocate problems & analysis related to real-life and clearly described	<input type="checkbox"/> Able to allocate problems & analysis related to real-life but minor description are missing	<input type="checkbox"/> Able to allocate problems & analysis related to real-life but major description are missing	<input type="checkbox"/> Able to allocate problems & analysis related to real-life but not clearly described	<input type="checkbox"/> Unable to allocate problems & analysis related to real-life.

*Please tick (✓) at appropriate scal

Percentage earned from Logbook = Total Marks Earned from Logbook X 10%

20

= %



PROGRESS REPORT FOR INDUSTRIAL TRAINING
 (Industrial Supervisors Evaluation Form)

A) Student Information

Name : UITM No.
 Programme : ID No.
 Session : Semester
 Date of Commencement : Date of Completion

B) Organization Information

Organization :
 Name of Supervisor:
 Designation :

C) Faculty Supervisor Information


Name :


D) Marks

No.	Criteria	CO1-PO5	CO2-PO8	CO3-PO4	CO4-PO2	TOTAL MARKS
1.	Attendance verification	/5				
2.	Punctuality and Attitude	/5				
3.	Quality of work	/5				
4.	Learning capability		/5			
5.	Application of knowledge		/5			
6.	Co-operation			/5		
7.	Discussion with supervisor/co-workers				/5	
8.	Communication Ability				/5	
9.	Oral and written presentation skills			/5		
10.	Organization skills				/5	
11.	Scope of work and relate to theoretical knowledge	/5				
12.	Safety	/5				
CO-PO MARKS		/25	/10	/10	/15	/60

Signature & Official Stamp

Date





No.	Criteria	5 (Excellent)	4 (Good)	3 (Satisfactory)	2 (Average)	1 (Weak)
1.	Attendance verification (CO1 - PO5)	<input type="checkbox"/> Constantly verified by supervisor.	<input type="checkbox"/> Satisfactory verified by supervisor.	<input type="checkbox"/> Moderately verified by supervisor.	<input type="checkbox"/> Fairly verified by supervisor.	<input type="checkbox"/> No verification by supervisor.
2.	Punctuality and Attitude. (CO1-PO5)	<input type="checkbox"/> Punctual with outstanding adherence to rules and regulations	<input type="checkbox"/> Punctual with good adherence to rules and regulations	<input type="checkbox"/> Punctual with satisfactory adherence to rules and regulations	<input type="checkbox"/> Moderate punctuality with minimal adherence to rules and regulations	<input type="checkbox"/> Poor punctuality and unable to adhere to rules and regulations
3.	Quality of work (task assigned). (CO1-PO5)	<input type="checkbox"/> Accomplish the tasks before the deadline with no correction	<input type="checkbox"/> Accomplish the tasks on time with no correction	<input type="checkbox"/> Accomplish the task on time with minimum correction	<input type="checkbox"/> Able to accomplish part of the tasks with delay	<input type="checkbox"/> Fail to accomplish tasks assigned
4.	Learning capability. (CO2-PO8)	<input type="checkbox"/> Demonstrate outstanding measures and proactive learning capability	<input type="checkbox"/> Able to act and learn with minimum supervisions	<input type="checkbox"/> Able to learn with supervisions	<input type="checkbox"/> Able to learn with substantial supervision	<input type="checkbox"/> Unable to learn despite with supervision
5.	Application of knowledge. (CO2-PO8)	<input type="checkbox"/> Excellent demonstration of theoretical knowledge application at work place	<input type="checkbox"/> Able to apply substantial amount of theoretical knowledge at work place	<input type="checkbox"/> Able to apply acceptable amount of theoretical knowledge at work place	<input type="checkbox"/> Able to apply minimal theoretical knowledge at work place	<input type="checkbox"/> Unable to apply theoretical knowledge at work place
6.	Co-operation. (CO3-PO4)	<input type="checkbox"/> Very proactive in giving co-operation	<input type="checkbox"/> Always give full co-operation when required	<input type="checkbox"/> Always give satisfied co-operation	<input type="checkbox"/> Give less co-operation	<input type="checkbox"/> Fail to show any cooperation at all
7.	Frequency of discussion with supervisor/co-workers. (CO4-PO2)	<input type="checkbox"/> At least 8 times	<input type="checkbox"/> At least 6 times	<input type="checkbox"/> At least 4 times	<input type="checkbox"/> At least twice	<input type="checkbox"/> Never have any discussion
8.	Communication Ability. (CO4-PO2)	<input type="checkbox"/> Able to communicate effectively with co-workers	<input type="checkbox"/> Able to communicate with co-workers	<input type="checkbox"/> Able to communicate satisfactorily with co-workers	<input type="checkbox"/> Poor communication with co-workers	<input type="checkbox"/> Unable to communicate with co-workers



No.	Criteria	5 (Excellent)	4 (Good)	3 (Satisfactory)	2 (Average)	1 (Weak)
9.	Oral and written presentation skills. (CO3 – PO4)	<input type="checkbox"/> Able to express and present very fluently and very convincing.	<input type="checkbox"/> Able to express and present fluently and convincing.	<input type="checkbox"/> Able to express and present quite fluently and quite convincing.	<input type="checkbox"/> Able to express and present clearly but with minimum fluently.	<input type="checkbox"/> Unable to express and present clearly and lack of fluency.
10.	Organization skills in individual and group effectiveness and its activity. (CO4-PO2)	<input type="checkbox"/> Well-explained on background and workplace activity	<input type="checkbox"/> Substantial explanation on background and workplace activity	<input type="checkbox"/> Acceptable explanation on background and workplace activity	<input type="checkbox"/> Able to explain background and workplace activity with minimal clarity	<input type="checkbox"/> Unable to explain background and workplace activity
11.	Ability to explain scope of work and relate to theoretical knowledge. (CO1-PO5)	<input type="checkbox"/> Well-explained the scope of work and able to relate to theoretical knowledge	<input type="checkbox"/> Substantial explanation on the scope of work and able to relate to theoretical knowledge	<input type="checkbox"/> Acceptable explanation on the scope of work with minimal relationship to theoretical knowledge	<input type="checkbox"/> Minimal explanation on the scope of work with minimal relationship to theoretical knowledge	<input type="checkbox"/> Unable to explain the scope of work and fail to relate to theoretical knowledge
12.	Safety. (CO1-PO5)	<input type="checkbox"/> Always adhere to safety requirements	<input type="checkbox"/> Adhere to safety requirements most of the time	<input type="checkbox"/> Adhere to safety requirements satisfactorily	<input type="checkbox"/> Minimal adherence to safety requirements	<input type="checkbox"/> Unable to adhere To safety requirements

*Please tick (✓) at appropriate scale

Percentage from Progress Report = Total Marks Earned From Progress Report X 50%

60

= %

PROGRESS REPORT FOR INDUSTRIAL TRAINING
 (Faculty Supervisors Evaluation Form)

A) Student Information

Name : _____ UITM No. : _____
 Programme : _____ ID No. : _____
 Session : _____ Semester : _____
 Date of Commencement : _____ Date of Completion : _____

B) Organization Information

Organization : _____
 Name of Supervisor : _____
 Designation : _____

C) Faculty Supervisor Information


Name : _____

D) Marks

No.	Criteria	CO1-PO5	CO2-PO8	CO3-PO4	CO4-PO2	TOTAL MARKS
1.	Attendance verification	/5				
2.	Punctuality and Attitude	/5				
3.	Quality of work	/5				
4.	Learning capability		/5			
5.	Application of knowledge		/5			
6.	Co-operation			/5		
7.	Discussion with supervisor/co-workers				/5	
8.	Communication Ability				/5	
9.	Oral and written presentation skills			/5		
10.	Organization skills				/5	
11.	Scope of work and relate to theoretical knowledge	/5				
12.	Safety	/5				
CO-PO MARKS		/25	/10	/10	/15	/60

Signature & Official Stamp
 (Faculty Supervisors)

Date



Faculty Supervisors Evaluation Form



No.	Criteria	5 (Excellent)	4 (Good)	3 (Satisfactory)	2 (Average)	1 (Weak)
1.	Attendance verification (CO1 - PO5)	<input type="checkbox"/> Constantly verified by supervisor.	<input type="checkbox"/> Satisfactory verified by supervisor.	<input type="checkbox"/> Moderately verified by supervisor.	<input type="checkbox"/> Fairly verified by supervisor.	<input type="checkbox"/> No verification by supervisor.
2.	Punctuality and Attitude. (CO1-PO5)	<input type="checkbox"/> Punctual with outstanding adherence to rules and regulations	<input type="checkbox"/> Punctual with good adherence to rules and regulations	<input type="checkbox"/> Punctual with satisfactory adherence to rules and regulations	<input type="checkbox"/> Moderate punctuality with minimal adherence to rules and regulations	<input type="checkbox"/> Poor punctuality and unable to adhere to rules and regulations
3.	Quality of work (task assigned). (CO1-PO5)	<input type="checkbox"/> Accomplish the tasks before the deadline with no correction	<input type="checkbox"/> Accomplish the tasks on time with no correction	<input type="checkbox"/> Accomplish the task on time with minimum correction	<input type="checkbox"/> Able to accomplish part of the tasks with delay	<input type="checkbox"/> Fail to accomplish tasks assigned
4.	Learning capability. (CO2-PO8)	<input type="checkbox"/> Demonstrate outstanding measures and proactive learning capability	<input type="checkbox"/> Able to act and learn with minimum supervisions	<input type="checkbox"/> Able to learn with supervisions	<input type="checkbox"/> Able to learn with substantial supervision	<input type="checkbox"/> Unable to learn despite with supervision
5.	Application of knowledge. (CO2-PO8)	<input type="checkbox"/> Excellent demonstration of theoretical knowledge application at work place	<input type="checkbox"/> Able to apply substantial amount of theoretical knowledge at work place	<input type="checkbox"/> Able to apply acceptable amount of theoretical knowledge at work place	<input type="checkbox"/> Able to apply minimal theoretical knowledge at work place	<input type="checkbox"/> Unable to apply theoretical knowledge at work place
6.	Co-operation. (CO3-PO4)	<input type="checkbox"/> Very proactive in giving co-operation	<input type="checkbox"/> Always give full co-operation when required	<input type="checkbox"/> Always give satisfied co-operation	<input type="checkbox"/> Give less co-operation	<input type="checkbox"/> Fail to show any cooperation at all
7.	Frequency of discussion with supervisor/co-workers. (CO4-PO2)	<input type="checkbox"/> At least 8 times	<input type="checkbox"/> At least 6 times	<input type="checkbox"/> At least 4 times	<input type="checkbox"/> At least twice	<input type="checkbox"/> Never have any discussion
8.	Communication Ability. (CO4-PO2)	<input type="checkbox"/> Able to communicate effectively with co-workers	<input type="checkbox"/> Able to communicate with co-workers	<input type="checkbox"/> Able to communicate satisfactorily with co-workers	<input type="checkbox"/> Poor communication with co-workers	<input type="checkbox"/> Unable to communicate with co-workers



No.	Criteria	5 (Excellent)	4 (Good)	3 (Satisfactory)	2 (Average)	1 (Weak)
9.	Oral and written presentation skills. (CO3 – PO4)	<input type="checkbox"/> Able to express and present very fluently and very convincing.	<input type="checkbox"/> Able to express and present fluently and convincing.	<input type="checkbox"/> Able to express and present quite fluently and quite convincing.	<input type="checkbox"/> Able to express and present clearly but with minimum fluently.	<input type="checkbox"/> Unable to express and present clearly and lack of fluency.
10.	Organization skills in individual and group effectiveness and its activity. (CO4-PO2)	<input type="checkbox"/> Well-explained on background and workplace activity	<input type="checkbox"/> Substantial explanation on background and workplace activity	<input type="checkbox"/> Acceptable explanation on background and workplace activity	<input type="checkbox"/> Able to explain background and workplace activity with minimal clarity	<input type="checkbox"/> Unable to explain background and workplace activity
11.	Ability to explain scope of work and relate to theoretical knowledge. (CO1-PO5)	<input type="checkbox"/> Well-explained the scope of work and able to relate to theoretical knowledge	<input type="checkbox"/> Substantial explanation on the scope of work and able to relate to theoretical knowledge	<input type="checkbox"/> Acceptable explanation on the scope of work with minimal relationship to theoretical knowledge	<input type="checkbox"/> Minimal explanation on the scope of work with minimal relationship to theoretical knowledge	<input type="checkbox"/> Unable to explain the scope of work and fail to relate to theoretical knowledge
12.	Safety. (CO1-PO5)	<input type="checkbox"/> Always adhere to safety requirements	<input type="checkbox"/> Adhere to safety requirements most of the time	<input type="checkbox"/> Adhere to safety requirements satisfactorily	<input type="checkbox"/> Minimal adherence to safety requirements	<input type="checkbox"/> Unable to adhere To safety requirements

*Please tick (✓) at appropriate scale

Percentage from Progress Report = Total Marks Earned From Progress Report X 20%

= %

60

COURSE OUTCOMES – PROGRAMME OUTCOMES MATRIX

COURSE CODE	COURSE NAME	COURSE CREDIT HOURS	ECM376	CENTRE OF STUDY		CEPM							
			INDUSTRIAL TRAINING	PREPARED BY	HAMIDAH								
			4.0	DATE	MAR-13								
COURSE OUTCOMES (use verbs according to taxonomy)	TAXONOMY LEVELS			PROGRAM OUTCOMES						ASSESSMENT			
	COGNITIVE	PSYCHOMOTOR	AFFECTIVE	PO1	PO2	PO3	PO4	PO5	PO6		PO7	PO8	PO9
1. Practice good working ethics and quality delivery of project undertaken.			I				√						Academic Advisor (Placement Report and Logbook Evaluation Form) Industrial and Faculty Supervisors. (Industrial and Faculty Supervisors Evaluation Forms)
2. Exhibit pleasant interpersonal skills as an individual in working independently, collaborative and in multi-disciplinary team.			III								√		Industrial and Faculty Supervisors. (Industrial and Faculty Supervisors Evaluation Forms)
3. Practice good organizational skills in enhancing individual and group effectiveness and productivity.			IV				√						Industrial and Faculty Supervisors. (Industrial and Faculty Supervisors Evaluation Forms)
4. Exhibit good communication with fellow workers and supervisors in issues related to projects undertaken.			II	√									Industrial and Faculty Supervisors. (Industrial and Faculty Supervisors Evaluation Forms)

Program outcome for EC110

- PO2 – Ability to communicate effectively, not only with engineers but also with the public (A)
- PO4 – Ability to act effectively as an individual and as group with leadership capabilities (A)
- PO5 – Understanding of the social, cultural, global, environmental responsibilities, ethics and the needs for sustainable development (A)
- PO8 – Ability to function in multidisciplinary teams (A)

CADANGAN MENGGANTIKAN JAMBATAN KONKRIT SEDIADA KEPADA JAMBATAN KONKRIT BARU MERENTANGI SUNGAI KELANG,
DI JALAN JELATEK, KUALA LUMPUR

No.	DRAWING DESCRIPTION	REF.NO	CONSTRUCTION DRAWING						
			REV / DATE RECEIVED						
			0	1	2	3	4	5	
1	LIST OF DRAWINGS	RB 6305/BR3/LOD/01	31/5/2018						
2	LOCATION PLAN	RB 831/BR3/LOC/01	31/5/2018						
3	ROAD LAYOUT PLAN	RB 831/BR3/RD/01	31/5/2018						
4	DRAINAGE LAYOUT PLAN	RB 831/BR3/RD/02	31/5/2018		29/5/2019				
5	ROAD FURNITURE LAYOUT PLAN	RB 831/BR3/RD/03	31/5/2018						
6	PROFILE CH. 940M TO CH. 1220M	RB 831/BR3/RD/04	31/5/2018						
7	TYPICAL DETAIL OF WASH TROUGH	RB 831/BR3/RD/05	31/5/2018						
8	ELEMENTS OF CURVES	RB 831/BR3/RD/06	31/5/2018						
9	CROSS SECTION AND PAVEMENT DETAIL	RB 831/BR3/RD/07	31/5/2018						
10	REGULATION AND TREATMENT OF EXISTING PAVEMENT	RB 831/BR3/RD/08	31/5/2018						
11	TYPICAL DETAILS OF HRGW DRAINS AND SUMP	RB 831/BR3/RD/09	31/5/2018		29/5/2019				
12	DETAIL OF SUMP NO.101	RB 6305/BR3/RD/09B	16/3/2019						
13	DETAILS OF CONCRETE KERB AND WALKWAY	RB 831/BR3/RD/10	31/5/2018						
14	PIPE CULVERT HEADWALL	RB 831/BR3/RD/11	31/5/2018						
15	REGULATORY AND WARNING SIGNS	RB 831/BR3/RD/12	31/5/2018						
16	STANDARD ROAD MARKING	RB 831/BR3/RD/13	31/5/2018						
17	STANDARD NORMAL LETTERING AND NUMERALS	RB 831/BR3/RD/14	31/5/2018						
18	DETAILS OF SIGNAGES	RB 831/BR3/RD/15	31/5/2018						
19	TYPICAL GENERAL ARRANGEMENT OF TRAFFIC SIGNS	RB 831/BR3/RD/16	31/5/2018						
20	TYPICAL SIGN STRUCTURAL DETAILS	RB 831/BR3/RD/17	31/5/2018						
21	TYPICAL STRUCTURAL DETAILS FOR GUIDE SIGNS	RB 831/BR3/RD/18	31/5/2018						
22	TYPICAL FOOTING DETAILS FOR GUIDE SIGNS	RB 831/BR3/RD/19	31/5/2018						
23	GENERAL NOTES	RB 831/BR3/ST/01	31/5/2018						
24	GENERAL LAYOUT PLAN, ELEVATION AND SECTIONS	RB 831/BR3/ST/02	31/5/2018						
25	PILING LAYOUT PLAN	RB 831/BR3/ST/03	31/5/2018	16/3/2019					
26	PILE SCHEDULE FOR NEW BRIDGE (ABUTMENT B)	RB 6305/BR3/ST/03B	16/3/2019						
27	DETAILS OF ABUTMENT - CONCRETE	RB 831/BR3/ST/04	31/5/2018						
28	DETAILS OF ABUTMENT - REINFORCEMENT OF PILE CAP	RB 831/BR3/ST/05	31/5/2018						
29	DETAILS OF ABUTMENT - REINFORCEMENT OF ELEVATION & SECTION	RB 831/BR3/ST/06	31/5/2018						

CADANGAN MENGGANTIKAN JAMBATAN KONKRIT SEDIADA KEPADA JAMBATAN KONKRIT BARU MERENTANGI SUNGAI KELANG,
DI JALAN JELATEK, KUALA LUMPUR

No.	DRAWING DESCRIPTION	REF.NO	CONSTRUCTION DRAWING						
			REV / DATE RECEIVED						
			0	1	2	3	4	5	
28	DETAILS OF ABUTMENT - REINFORCEMENT OF WINGWALL & APPROCH SLAB	RB 831/BR3/ST/07	31/5/2018						
29	DIAPHRAGM BEAM & BEARING PAD DETAILS	RB 831/BR3/ST/08	31/5/2018						
30	PRECAST GIRDER ARRANGEMENT LAYOUT & GIRDER SEATING DETAILS	RB 831/BR3/ST/09	31/5/2018						
31	R.C DECK SLAB REINFORCEMENT & PARAPET WALL DETAILS	RB 831/BR3/ST/10	31/5/2018						
32	SEQUENCE OF CONSTRUCTION (1 OF 2)	RB 831/BR3/ST/11	31/5/2018						
33	SEQUENCE OF CONSTRUCTION (2 OF 2)	RB 831/BR3/ST/12	31/5/2018						
34	NEW JERSEY PARAPET DETAILS	RB 831/BR3/ST/13	31/5/2018						
35	HANDRAIL AND WALKWAY SHELTER DETAILS	RB 831/BR3/ST/14	31/5/2018						
36	600mm. DIA. BORED PILE DETAILS	RB 831/BR3/ST/15	16/3/2019						
37	STEEL TRUSSS - GENERAL LAYOUT PLAN & ELEVATION	RB 831/BR3/ST/16	31/5/2018		27/12/2018	20/4/2019			
38	STEEL TRUSS - SECTION	RB 831/BR3/ST/17	31/5/2018		3/11/2018	5/12/2018	16/3/2019		
39	STEEL TRUSS - PILING LAYOUT PLAN	RB 831/BR3/ST/18	31/5/2018		27/12/2018	16/3/2019			
40	STEEL TRUSS - DIMENSION & REINFORCEMENT DETAIL (PIER 1 & 3)	RB 831/BR3/ST/19	31/5/2018						
	STEEL TRUSS - DIMENSION & REINFORCEMENT DETAIL (PIER 3)	RB 6305/BR3/ST/19A	31/5/2018		31/1/2018	27/12/2018			
41	STEEL TRUSS - DIMENSION & REINFORCEMENT DETAIL (PIER 2)	RB 831/BR3/ST/20	31/5/2018						
42	STEEL TRUSS - DIMENSION & REINFORCEMENT DETAIL (PIER 4 & 5)	RB 831/BR3/ST/21	31/5/2018		5/12/2018	16/3/2019			
43	STEEL TRUSS ELEVATION 12.45m - (NO.1)	RB 831/BR3/ST/22	31/5/2018		27/12/2018				
	STEEL TRUSS ELEVATION 26.80m - (NO.3)	RB 6305/BR3/ST/22A			19/10/2018	20/4/2019			
44	STEEL TRUSS ELEVATION 50m - (NO.2)	RB 831/BR3/ST/23	31/5/2018						
45	STEEL TRUSS ELEVATION 50m - (NO.3)	RB 831/BR3/ST/24	31/5/2018		19/10/2018				
46	STEEL TRUSS ELEVATION 50m - (NO.4)	RB 831/BR3/ST/25	31/5/2018						
47	STEEL TRUSS ELEVATION 46m - (NO.5)	RB 831/BR3/ST/26	31/5/2018		19/10/2018				
48	STEEL TRUSS DETAILS 50m - SHEET 1 OF 3	RB 831/BR3/ST/27	31/5/2018						
49	STEEL TRUSS DETAILS 50m - SHEET 2 OF 3	RB 831/BR3/ST/28	31/5/2018						
50	STEEL TRUSS DETAILS 50m - SHEET 3 OF 3	RB 831/BR3/ST/29	31/5/2018						
51	STEEL TRUS DETAILS 12.45m - SHEET 1 OF 2	RB 831/BR3/ST/30	31/5/2018						
52	STEEL TRUS DETAILS 12.45m - SHEET 2 OF 2	RB 831/BR3/ST/31	31/5/2018						
53	250mm DIA. MICROPILE DETAILS	RB 831/BR3/ST/32	31/5/2018						



JABATAN KEJURUTERAAN AWAM & PENGANGKUTAN BANDAR
DEWAN BANDARAYA KUALA LUMPUR

CADANGAN MENGGANTIKAN JAMBATAN KONKRIT
SEDIADA KEPADA JAMBATAN KONKRIT BARU
MERENTANGI SUNGAI KELANG, DI JALAN JELATEK,
KUALA LUMPUR

CONSTRUCTION DRAWINGS

MAY 2018

MASTER COPY

CONTROLLED COPY

13 MAY 2018

PEGAWAI PENGUASA

PENGARAH
JABATAN KEJURUTERAAN AWAM & PENGANGKUTAN BANDAR
DEWAN BANDARAYA KUALA LUMPUR
TINGKAT 11-13, BANGUNAN DEWAN BANDARAYA
JALAN RAJA LAUT
50350 KUALA LUMPUR


JURUTERA PERUNDING:

renhill consulting sdn. bhd. (394809-A)

SUITE 2302, LEVEL 23 PLAZA PERMATA,
NO. 6 JALAN KAMPAR
OFF JALAN TUN RAZAK
50400 KUALA LUMPUR.
TEL. 03-27168888 FAX. 03-27168889



Renhill



13 1 MAY 2010

SCALE REFERRED TO PG 00P



MASTER COPY

CONTROLLED COPY

CONSTRUCTION DRAWING

SEKUTUPAN: 1. RAKAM PERANCANGAN
 2. RAKAM PERANCANGAN
 3. RAKAM PERANCANGAN
 4. RAKAM PERANCANGAN
 5. RAKAM PERANCANGAN
 6. RAKAM PERANCANGAN
 7. RAKAM PERANCANGAN
 8. RAKAM PERANCANGAN
 9. RAKAM PERANCANGAN
 10. RAKAM PERANCANGAN


<p>DEWAN BANDARAYA KUALA LUMPUR</p> <p>DAFTAR PERANCANGAN JALAN JALAN AMPANG HILIR DI DAIRAH BANDARAYA KUALA LUMPUR</p> <p>TAJUK: LUKUS BRIDGE OVER SG. KELANG LOCATION PLAN</p> <p>NO. RAKAM: RB 6305/BR3/LOC/01</p>	
<p>IR. SABIH BINTI ALI JALAN KUALA LUMPUR NO. 1234 KUALA LUMPUR</p>	<p>IR. AZLI SHAH BIN ALI BASHIR JALAN KUALA LUMPUR NO. 1234 KUALA LUMPUR</p>
<p>CHE MAT NAWA BIN MAT DAUD JALAN KUALA LUMPUR NO. 1234 KUALA LUMPUR</p>	<p>TUAN HASSAN HANIFF BIN SURIP JALAN KUALA LUMPUR NO. 1234 KUALA LUMPUR</p>
<p>ranhill consulting sdn. bhd. (199809-A)</p> <p>NO. 1234 JALAN KUALA LUMPUR NO. 1234 KUALA LUMPUR</p>	<p>NO. 1234 JALAN KUALA LUMPUR NO. 1234 KUALA LUMPUR</p>
<p>SKALA: 1:2000</p>	<p>NO. 1234 JALAN KUALA LUMPUR NO. 1234 KUALA LUMPUR</p>

**BANDAR HULU KELANG
NEGERI SELANGOR**

**Kg. Penden
Cheras
Jalan Ampang
Pusat Bandaraya**

LE12 Jalan Tun Razak

**SEK. 88
BANDAR KUALA LUMPUR
WILAYAH PERSEKUTUAN**



**Setiawangsa
Wangsa Maju**

**Kg. Dato Keramat
Keramat Jaya**

**Setiawangsa
Wangsa Maju**

**Kg. Dato Keramat
Keramat Jaya**

NOTE :
ALL EXISTING TRAFFIC SIGNALS TO BE MAINTAINED.

13 MAY 2010

SPACE RESERVED FOR P.C. DRAW




MASTER COPY

CONTROLLED COPY

CONSTRUCTION DRAWING

<p>DEWAN BANDARAYA KUALA LUMPUR</p> <p>UNIT TEK: CAJANGAN MENGANTIKAN JAMBATAN KONKRIT SEGARA KEPADA BUKIT BUKIT TANGSI SONG KLANG, DI JALAN BAYAN, KUALA LUMPUR</p> <p>JAK LUMPUR</p> <p>BRIDGE OVER S.S. KELANG</p> <p>ROAD FUTURE LAYOUT PLAN</p> <p>NO. RUMAH: RB 6305/BR3/RD/03</p> <p>NO. TEL: 03-2071-1000</p>	<p>IR. SULEIN BIN ALLEN</p> <p>IR. AFI SHAH BIN ALI BASHAH</p> <p>CHE MAT HAN BIN MAT DAUD</p>	<p>1 : 400</p>	<p>REVISION:</p> <table border="1"> <tr> <th>NO.</th> <th>DESCRIPTION</th> <th>DATE</th> </tr> <tr> <td>1</td> <td>ISSUED FOR PERMIT</td> <td>13/05/2010</td> </tr> <tr> <td>2</td> <td>ISSUED FOR CONSTRUCTION</td> <td>13/05/2010</td> </tr> </table>	NO.	DESCRIPTION	DATE	1	ISSUED FOR PERMIT	13/05/2010	2	ISSUED FOR CONSTRUCTION	13/05/2010
NO.	DESCRIPTION	DATE										
1	ISSUED FOR PERMIT	13/05/2010										
2	ISSUED FOR CONSTRUCTION	13/05/2010										



CH.940m TO CH.1260m

13 MAY 2018

MASTER COPY

CONTROLLED COPY

CONSTRUCTION DRAWING


NOTE:
RICE BURNERS ARE TO BE KEPT IN COLLISION WITH THE ROAD LAYOUT PLAN AND SIGNALISE PLAN.

THIS DRAWING IS FOR INFORMATION ONLY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL DATA AND CONDITIONS ON THE SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE RELEVANT AUTHORITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES AND STRUCTURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING PLANTS AND TREES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING ROADS AND PATHS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING SERVICES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES AND STRUCTURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING PLANTS AND TREES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING ROADS AND PATHS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING SERVICES.




<p>ronhill consulting Sdn. Bhd. (130689-A)</p> <p>100, Jalan Sultan Ismail, 50000 Kuala Lumpur, Malaysia</p> <p>Tel: +603-2078-8888</p>		<p>IR. SAUJAN B. SALEH Jabatan Kejuruteraan Awam dan Industri</p> <p>IR. AZI SAHRI BIN HUSSEIN Jabatan Kejuruteraan Awam dan Industri</p> <p>CHE MAT JANI BIN MAT DAUD Jabatan Kejuruteraan Awam dan Industri</p>	<p>DEWAN BANDARAYA KUALA LUMPUR</p> <p>JABATAN KONSULTAN JERAMBAAN KONSIST SEDANDA KEPADA JABATAN KONSULTAN JERAMBAAN KONSIST HANGI SURONG KELING, DI JALAN SEATEK, KUALA LUMPUR.</p> <p>PROJEK: JERAMBAAN KONSIST SEDANDA KEPADA JABATAN KONSULTAN JERAMBAAN KONSIST HANGI SURONG KELING, DI JALAN SEATEK, KUALA LUMPUR.</p> <p>NO. PROJEK: RB 6305/BR3/RD/04</p>
<p>TITIK: _____</p> <p>RUJUKAN: _____</p> <p>SKALA: _____</p>	<p>HORIZ 1:500 VERT 1:50</p>	<p>REFAK: E TRANSPORTASI/01-ROSTER/1018-031 - 031A/01/02/2017/04-0031-031-03-01-04</p>	

SKREW Ø	f	e
0"	30"	30"
10"	20"	30"
20"	15"	30"
30"	10"	40"




END ELEVATION
SCALE 1:25

PLAN OF CULVERT HEADWALL
SCALE 1:25



SECTION 2 - 2
SCALE 1:25



SECTION 1 - 1
SCALE 1:25

- NOTES:
1. DIMENSIONS ARE FOR ONE END OF PIPE ONLY.
 2. LAPS IN STRUCTURAL GRADE BARS AND MESH SHALL BE 25 x DIAMETER PLUS 150mm MINIMUM.
 3. MESH SHALL BE AT LEAST TWO HORIZONTAL BARS WHETHER WESH OR B.L.S. OVER THE PIPE IN THE END WALL, AND ALONG SLOPING TOP OF HEADWALL UNLESS OTHERWISE STATED.
 4. CLEAR CONCRETE TO ALL REINFORCEMENT SHALL BE 40mm UNLESS OTHERWISE STATED.
 5. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED.
 6. CONCRETE GRADE SHALL BE 75/20.
 7. THE EXACT LOCATION, SKEW, INVERT LEVELS, LENGTH, AND SLOPE OF CULVERT SHALL BE CONFIRMED BY THE ENGINEER.

NOMINAL PIPE DIA.	SKEW	DIMENSIONS													REINFORCEMENT					
		A	B	C	D	E	F	G	H/A	I	J	K	L	M	N	O	P	Q	R	
600	0	1200	1240	1240	1280	1300	300	300	1050/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
900	0	1500	1570	1570	1600	1600	400	400	1350/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1200	0	1800	1900	1900	1900	3000	600	600	1650/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1500	0	2100	2425	2425	2100	4100	1050	1050	1950/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1650	0	2280	2600	2600	2280	4100	1125	1125	2100/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1800	0	2400	2770	2770	2400	4100	1200	1200	2250/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
2100	0	2700	2980	2980	2700	5100	1200	1200	2550/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
2400	0	3000	3310	3310	3000	5000	1400	1400	2850/175	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125
2700	0	3300	3641	3641	3300	6300	1540	1540	3150/200	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100
3000	0	3600	3972	3972	3600	6800	1680	1680	3450/250	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100
600	10	1220	1240	1135	1130	1410	505	105	1050/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
900	10	1525	1555	1415	1385	1740	705	210	1350/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1200	10	1830	1960	1700	1670	3650	905	315	1650/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1500	10	2140	2425	2245	2100	3710	1050	720	1950/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1650	10	2480	2770	2555	2400	4100	1125	770	2100/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1800	10	2740	2980	2830	2700	4800	1260	860	2350/175	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125
2100	10	3046	3310	3168	3000	5188	1400	1020	2850/175	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125
2400	10	3350	3641	3511	3300	6090	1540	1260	3150/200	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100
2700	10	3655	3972	3827	3600	6635	1680	1300	3450/250	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100
600	20	1280	1240	1025	1025	1920	685	-55	1050/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
900	20	1585	1555	1255	1255	2565	935	25	1350/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1200	20	1815	1900	1480	1480	3195	1100	100	1650/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1500	20	2245	2425	2175	2100	3940	1050	545	1950/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1650	20	2425	2600	2330	2250	4130	1125	580	2100/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1800	20	2605	2770	2485	2400	4125	1200	620	2300/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
2100	20	2975	3118	2795	2700	5158	1580	723	2550/175	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125	Ø12-125
2400	20	3192	3461	3105	3000	5727	1732	803	2850/175	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100
2700	20	3511	3810	3416	3300	6300	1905	884	3150/200	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100
3000	20	3831	4156	3726	3600	6872	2078	964	3450/250	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100	Ø12-100
600	30	1385	1240	905	899	2180	860	-165	1050/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
900	30	1720	1555	1080	1075	2770	1140	-100	1350/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1200	30	2080	1900	1280	1280	3465	1420	-35	1650/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1500	30	2425	2330	1445	1445	4110	1700	35	1950/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
600	40	1570	1240	760	750	2355	1005	-220	1050/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
900	40	1980	1570	870	860	3195	1310	-135	1350/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1200	40	2350	1900	995	995	3920	1620	-50	1650/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1500	40	2745	2330	1130	1130	4795	1925	35	1950/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
600	50	1970	1240	675	675	2815	1115	-180	1050/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
900	50	2335	1500	620	620	3735	1440	-100	1350/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1200	50	2890	1900	705	705	4670	1765	-105	1650/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150
1500	50	3270	2330	815	775	5670	2095	245	1950/150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150	Ø12-150

DETAILS OF CULVERT HEADWALL FOR SINGLE PIPE AT ANGLE OF SKEW

CONTROLLED COPY

CONSTRUCTION DRAWING

ronhill consulting
sdn. bhd. (INCORPORATED)

DESIGNER: [Signature]
CHECKED BY: [Signature]
DATE: [Date]

SCALE: 1:15

REVISIONS

DATE: [Date]

BY: [Signature]

FOR: [Project Name]

PROJECT NO: [Project Number]

DATE: [Date]

DEWAN BANDARAYA KUALA LUMPUR

IBRA KEMAS
CAJANGAN MERTAGANTIKAN AMBILAN KOSONG BERSEKUTUAN KEKADA KEPADA
Dewan Bandaraya Kuala Lumpur
Jalan Sultan Abdul Aziz
50000 Kuala Lumpur

APRIL 2018

REVISIONS

NO. 1

APRIL 2018

REVISIONS


NO. 1

APRIL 2018


REVISIONS

NO. 1


APR



PEDESTRIAN CROSSING (ZEBRA)
NOT TO SCALE



GIVE WAY LINE
NOT TO SCALE



CENTRE LINE / LANE LINE (URBAN AREA)
NOT TO SCALE




STOP LINE
NOT TO SCALE



DOUBLE LINE
NOT TO SCALE




TURN LINE
NOT TO SCALE



YELLOW BOX MARKING
NOT TO SCALE

URBAN ROAD	W	D	S
1	3000	300	1000
2	1975	300	1000
3	1125	300	1000
4	950	300	1000
5	875	300	1000
6	750	300	1000
7	600	300	1000
8	637.5	300	1000
9	450	300	1000
10	975	300	1000
11	1500	300	1000



CHEVRON HATCHING FOR MERGING TRAFFIC
1 : 200

CHEVRON HATCHING FOR DIVERGING TRAFFIC
1 : 200

CHEVRON HATCHING FOR TRAFFIC ISLANDS
1 : 200

- NOTES:
- 1) CONTINUITY LINE :
 - a) - (S=1000 C=1000 W=100) AT INTERSECTION.
 - b) - (S=1000 C=1000 W=200) AT RAMP EXITS AND ENTRANCES.
 - 2) GIVE-WAY LINE : (S=300 C=300 W=500) AT THE MOUTH OF AN INTERSECTION.
 - 3) CENTRE LINE / LANE LINE : S=1000 C=1700 W=100 IN URBAN AREA
 - 4) EDGE LINE / CHANNELLING LINE :
 - a) - ON SHORT RADIUS CURVES IN RURAL AREA
 - b) - AT TRAFFIC ISLAND OR AT ADJACENT EDGE FOR PROHIBITION OF PARKING.
 - c) - CHANNELLING LINE - (CONTINUOUS 150mm WIDTH) AT THE JUNCTION OR CROSS - ISLAND.
 - d) - CHANNELLING LINE - (CONTINUOUS 100mm WIDTH) AT THE JUNCTION OR CROSS - ISLAND.
 - 5) STOP LINE : (CONTINUOUS 300mm WIDTH)
 - 6) PEDESTRIAN CROSSING (ZEBRA) : - ON STRAIGHT ROAD.
 - 7) DOUBLE LINE : (W=1000) NO PASSING ZONES OR CENTRE LINE OF MULTILANE ROAD IN URBAN AREA
 - 8) BUS STOP / BUS LAY-BY LINE : (S=500 W=100) TO BE FOLLOWED BY TURNING VEHICLES
 - 9) TURN LINE : (S=500 C=600 W=100) TO BE FOLLOWED BY TURNING VEHICLES
 - 10) YELLOW BOX LINE : PAINTED AT INTERSECTION FOR PROHIBITION OF PARKING OR WAITING
- ALL DIMENSIONS ARE IN METERS, UNLESS OTHERWISE STATED.
APPLICATION PRINCIPLES OF ROAD MARKINGS ARE DEFINED IN JKR, ABJAHAN TEKNIK (JALAN) 20/81.

CONTROLLED COPY

MASTER COPY

13 MAY 2018

SPACE RESERVED FOR I.C. COPY.



CONSTRUCTION DRAWING

PAVEMENT DIRECTION ARROWS
1 : 50

renhill consulting
ren. bnd. (PROSAS)

AS SHOWN

DESK
SCALE

DESK
SCALE

DESK
SCALE


DEWAN BANDARAYA KUALA LUMPUR
KADANGAN NEGANTIKAN JAMBATAN KONTRAK BERADA KEPADA
DI JALAN MELAYU, TUNJANG SINGA RELANG, KEPADA
BANK URBAN
BRIDGE OVER SG. SELANG
STANDARD ROAD MARKING

APRIL 2018
ET. USMAN
RB 6305/BR3/RD/13


DEWAN BANDARAYA KUALA LUMPUR
KADANGAN NEGANTIKAN JAMBATAN KONTRAK BERADA KEPADA
DI JALAN MELAYU, TUNJANG SINGA RELANG, KEPADA
BANK URBAN
BRIDGE OVER SG. SELANG
STANDARD ROAD MARKING

APRIL 2018
ET. USMAN
RB 6305/BR3/RD/13

NORMAL ALPHABET (UPPER CASE)



NORMAL ALPHABET (LOWER CASE)




ALPHABET	k1	k2	w	w	w	w	w
A	0.018	0.018	0.821	1.018	0.673	0.794	
B	0.164	0.097	0.782	1.042	0.685	0.860	
C	0.091	0.073	0.909	1.073	0.655	0.720	
D	0.164	0.079	0.824	1.097	0.648	0.855	0.055
E	0.164	0.115	0.931	1.070	0.681	0.895	0.090
F	0.170	0.036	0.655	0.881	0.608	0.655	0.050
G	0.085	0.133	0.885	1.003	0.646	0.830	
H	0.164	0.164	0.800	1.127	0.682	0.848	
I	0.050	0.152	0.515	0.673	0.630	0.700	0.388
J	0.164	0.018	0.615	0.865	0.681	0.803	
K	0.164	0.018	0.615	0.865	0.681	0.803	
L	0.170	0.030	0.648	0.848	0.687	0.808	
M	0.164	0.164	1.008	1.253	0.678	0.838	0.455
N	0.164	0.164	0.879	1.208	0.681	0.831	0.442
O	0.091	0.091	0.838	1.121	0.646	0.779	0.491
P	0.164	0.061	0.733	0.858	0.697	0.773	0.481
Q	0.091	0.091	0.964	1.145	0.655	0.715	0.479
R	0.168	0.097	0.788	1.042	0.681	0.818	0.485
S	0.073	0.115	0.855	1.042	0.638	0.687	0.418
T	0.027	0.027	0.782	0.936	0.655	0.665	0.477
U	0.139	0.139	0.824	1.103	0.681	0.721	0.468
V	0.058	0.058	0.838	0.952	0.655	0.685	0.478
W	0.079	0.079	1.238	1.384	0.655	0.655	1.030
X	0.030	0.030	0.681	0.921	0.638	0.638	0.709
Y	0.027	0.027	0.848	0.993	0.630	0.630	0.667
Z	0.061	0.079	0.709	0.848	0.655	0.661	0.552

UNIT NUMERAL WIDTH / LETTER WIDTH, SPACING CONSTANTS, MOSAIC WIDTH (NORMAL LETTERS)

NUMBER	k1	k2	w	w	w	w
1	0.091	0.150	0.384	0.582		
2	0.036	0.091	0.721	0.848		
3	0.081	0.121	0.752	0.933		
4	0.012	0.085	0.861	0.958		
5	0.103	0.073	0.733	0.808		
6	0.073	0.073	0.739	0.885		
7	0.012	0.036	0.861	0.739		
8	0.169	0.109	0.739	0.936		
9	0.073	0.085	0.752	0.909		
0	0.095	0.085	0.824	0.894		
()	0.103	0.206	0.479	0.788		
()	0.208	0.103	0.479	0.788		
()	0.048	0.012	0.218	0.279		
(-)	0.061	0.109	0.315	0.485		
.	0.036	0.133	0.218	0.386		
.	0.073	0.121	0.182	0.375		

DESIGN EXAMPLE




LETTER TYPE - NORMAL

Height of upper case letter: - H = 330 mm
 to calculate width of 'Ampang' :-
 From formula :-
 $(k1 + k2) \times H$
 Where k1 = WA + Wm + ... + Wn
 k2 = Constant for first letter 'A'

To calculate height of mosaic (Hm) :-
 $(0.018 + 1.230 + 0.061 + 0.794 + 0.844 + 0.830) \times (0.048 + 0.115) \times 330$
 $= (5.275 - 0.163) \times 330$
 $= (5.412) \times 330$
 $= 1785.966 \text{ mm say } 1786 \text{ mm}$
 To calculate height of mosaic (Hm) :-
 $Hm = 0.085 H$
 $Hm = 0.384 H$
 $Hm = Hm + h + Hb$
 $= 0.095 (330) + 330 + 0.384 (330)$
 $= 478.17 \text{ mm say } 478 \text{ mm}$

DESIGN EXAMPLE




NUMBER TYPE - NORMAL

Height of upper case letter: - H = 330 mm
 to calculate width of '32' :-
 From formula :-
 $(k1 + k2) \times H$
 Where k1 = W3 + W2
 k2 = Constant for first number '3'

To calculate height of mosaic (Hm) :-
 $(0.033 + 0.848) \times (0.061 + 0.091) \times 330$
 $= (1.781 - 0.152) \times 330$
 $= (1.629) \times 330$
 $= 537.57 \text{ mm say } 538 \text{ mm}$
 To calculate height of mosaic (Hm) :-
 $Hm = 0.085 H$
 $Hm = 0.384 H$
 $Hm = Hm + h + Hb$
 $= 0.095 (330) + 330 + 0.384 (330)$
 $= 478.17 \text{ mm say } 478 \text{ mm}$

TYPICAL GENERAL LAYOUT DESIGN OF SIGNBOARD



CONSTRUCTION DRAWING

IR. SABUDIN BIN MOHAJIR
 JAWAHIR ENGINEERING CONSULTANTS (MALAYSIA) SDN BHD
 IR. AZLI SHAH BIN ALI BASHARI
 JAWAHIR ENGINEERING CONSULTANTS (MALAYSIA) SDN BHD
 CHE HAT HAN BIN HAT DAUD
 JAWAHIR ENGINEERING CONSULTANTS (MALAYSIA) SDN BHD


DEWAN BANDARAYA KUALA LUMPUR
 CADANGAN MENGGANTIKAN JAMBATAN KONKRET SEDIAWA KEPADA
 JAMBATAN BERTANGKAPAN DI JALAN MELAYU, KUALA LUMPUR
 BRIDGE OVER SB. BELANG
 STANDARD NORMAL LETTERING AND NUMERALS
 FIKSAS
 PERIOD: APRIL 2010
 NO. LAKSAL: RD 6305/BR3/RD/14

CONTROLLED COPY

MASTER COPY

18 MAY 2010

SPACE RESERVED FOR FC COPY



GENERAL

- 1 ALL DIMENSIONS ARE GIVEN IN MILLIMETRES UNLESS OTHERWISE STATED.
- 2 THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS BEFORE WORK STARTS.
- 3 THE BRIDGE IS DESIGNED TO CARRY THE FOLLOWING LIVE LOAD :-
(i) TYPE HA LOADING OR TYPE HA IN COMBINATION WITH 30 UNITS TYPE HB LOADING IN ACCORDANCE WITH BD 37/01 ISSUED BY DEPARTMENT OF TRANSPORT, U.K. AND CHECKED FOR SERVICEABILITY LIMIT STATE.
(ii) TYPE HA LOADING OR TYPE HA IN COMBINATION WITH 45 UNITS TYPE HB LOADING AND CHECKED FOR ULTIMATE LIMIT STATE.
- 4 THE NOTES IN THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT DRAWINGS FOR A PARTICULAR BRIDGE OR BOX CULVERT.

CONCRETE

- 1 CONCRETE GRADES SHALL BE AS FOLLOW :-
(i) PRESTRESSED PRECAST BEAMS CONCRETE REFER TO RELEVANT DRAWINGS.
(ii) DECK SLAB : 50/20.
(iii) R.C DAMPHRAM, PARAPET WALLS, PILECAP, MEDIAN, INSITU KERBS : 40/20.
(iv) ABUTMENT, R.C RETAINING WALLS, R.C WINGWALLS, APPROACH SLABS : 40/20.
(v) PILECAPS : 40/20.
(vi) CONCRETE INFILL TO BRIDGE WALKWAYS : 20/20.
(vii) LEAN CONCRETE : 15/20.

- 2 THE CONCRETE GRADE OF SPACER BLOCK SHALL BE SIMILAR TO THE STRUCTURAL GRADES.
- 3 THE POSITION AND TYPE OF EACH CONSTRUCTION JOINT ARE TO BE SUBMITTED TO THE APPROVAL OF THE ENGINEER (SEE SPECIFICATION).
- 4 CONCRETE PROPERTIES USED IN DESIGN ASSUMPTIONS : -
(i) MODULUS OF ELASTICITY OF CONCRETE = 5000 KN/mm² FOR GRADE 150 CONCRETE (UHPC)
(ii) CREEP STRAIN IN CONCRETE = 36 x 10⁻⁶ PER 1/mm² OF CONCRETE STRESS (POST-TENSIONING).
(iii) SHRINKAGE STRAIN = 200 x 10⁻⁶ (POST-TENSIONING).

SURFACE FINISH

- 1 UNLESS OTHERWISE SHOWN ON DRAWINGS, SURFACE FINISH TO BE 'AS CAST' THAT IS (i) AGAINST CLASS F3 FORMWORK FOR PERMANENTLY VISIBLE SURFACES (EXPOSED).
(ii) AGAINST CLASS F1 FORMWORK FOR PERMANENTLY CONCEALED SURFACES (BURIED).
- 2 ALL UNFORMED SURFACES WHICH ARE NOT EXPOSED TO VIEW SHALL HAVE A CLASS U2 SURFACE FINISH IN ACCORDANCE WITH THE SPECIFICATION.
- 3 ALL UNFORMED EXPOSED SURFACES SHALL HAVE A CLASS U3 SURFACE FINISH IN ACCORDANCE WITH THE SPECIFICATION.
- 4 ALL RIBBED FINISH SHALL BE BUSH HAMMER FINISH IN ACCORDANCE WITH THE SPECIFICATION.

REINFORCEMENT

- 1 UNLESS OTHERWISE SHOWN ON DRAWINGS, ALL REINFORCING BARS SHALL COMPLY WITH BS 4449.
- 2 BENDING OF REINFORCEMENT TO BE IN ACCORDANCE WITH BS 4466.
- 3 SPLICES, OTHER THAN THOSE SHOWN ON THE DRAWING, MAY BE MADE ONLY WITH THE APPROVAL OF THE ENGINEER.
- 4 UNLESS OTHERWISE SHOWN ON DRAWING, SPLICES IN ADJACENT BARS TO BE STAGGERED.
- 5 SPACER BARS, NOT LESS THAN SIZE 25mm DIAMETER TO BE PROVIDED BETWEEN ADJACENT LAYERS OF PARALLEL REINFORCEMENT AND SPACED AT NOT MORE THAN 60 X DIAMETER OF SMALLER BAR.
- 6 UNLESS OTHERWISE SHOWN ON DRAWING, COVER TO REINFORCEMENT SHALL BE : -
(i) PRESTRESSED PRECAST BEAMS : 30mm
(ii) DAMPHRAMS : 30mm
(iii) R.C DECK SLAB, PARAPET WALLS, FASCIA, MEDIANS AND INSITU KERBS : 30mm
(iv) ABUTMENTS, RETAINING WALLS, WINGWALLS, APPROACH SLABS : 50mm
(v) PIERS, PILE CAPS, COLUMN, CROSS-BEAMS : 50mm
(vi) UNDERSIDES OF PILE CAPS : 75mm
(vii) BOX CULVERTS AND WINGWALLS : 50mm

PRESTRESSED SYSTEMS

- 1 ANY ALTERNATIVE PRESTRESSED SYSTEM SUBMITTED BY THE TENDERER SHOULD BE ACCOMPANIED BY SUPPORTING CALCULATION AND DETAIL DRAWINGS.
- 2 THE PRESTRESSING TENDONS USED FOR POST-TENSIONED BEAMS ARE TO BE 7-WIRE 15.2mm STRAND TO ASTM A416-80 FOR LOW RELAXATION GRADE 270 STEEL OR BS 5896:1980 SUPER-STRAND-1860-129-RELAX CLASS 2 HAVING THE FOLLOWING PROPERTIES : -
(i) NOMINAL SIZE = 15.20mm DIAMETER
(ii) NOMINAL CROSS SECTION AREA = 140mm²
(iii) SPECIFIED CHARACTERISTIC STRENGTH = 260.70 KN
(iv) MODULUS OF ELASTICITY = 195.00 KN/mm²
3 ESTIMATED LOSSES OF PRESTRESSING INCLUDES : -
(i) RELAXATION OF TENDONS = 2.5%
(ii) ELASTIC DEFORMATION OF CONCRETE AND SUBSEQUENT SHRINKAGE AND CREEP OF THE CONCRETE
(iii) FRICTION LOSSES
4 INITIAL JACKING FORCE = 75% OF SPECIFIED CHARACTERISTIC STRENGTH
5 COEFFICIENT FOR FRICTION LOSSES IN THE DUCTS ARE AS FOLLOWS : -
U = 0.2
K = 0.001

TENSIONING PARTICULARS FOR POST-TENSIONING GIRDERS

- 1 CABLES IN THE GIRDER ARE TO BE TENSIONED FROM ONE END ONLY EXCEPT OTHERWISE INDICATED.
- 2 ALL STRANDS IN A CABLE SHALL BE PULLED SIMULTANEOUSLY AND ANCHORED IN A COMPACT AND EFFICIENT ANCHORAGE.
- 3 STRONG RIGID SHEATHS OR DUCT FORMERS SHALL BE USED AND CLOSELY SUPPORTED SO THAT THEY ARE NOT DISPLACED DURING THE CONCRETING OPERATION.
- 4 ANCHORAGE PULL-IN WARES WITH THE PRESTRESSING SYSTEM USED AND SHOULD BE PROVIDED FOR THE TENDONS. THE TENDONS SHALL BE TENSIONED IN THE PRESTRESSED OPERATION. ANCHORAGE DETAILS SHALL BE IN ACCORDANCE WITH THE SYSTEM ADOPTED.
- 5 LOSSES IN THE JACKING SYSTEM HAVE BEEN IGNORED.

KEY PLAN FOR ALTERNATELY PLACING REINFORCEMENT

11 LAP AND ANCHORAGE LENGTH FOR BAR (CONCRETE GRADE 40 N/mm² AND ABOVE) SHALL COMPLY WITH BS 5400 PART 4.

REBAR	LAP LENGTH (mm)	1.4 x LAP LENGTH (mm)
T10	400	560
T12	450	630
T16	550	770
T20	650	910
T25	775	1085
T32	950	1330


* INCREASE IN LENGTH BY 1.4 WHERE THE CLEAR DISTANCE BETWEEN THE LAPPED BARS IS LESS THAN 150mm.

ABBREVIATION

R.L.	REDUCED LEVEL
R.C.	REINFORCED CONCRETE
CH.	CHANNEL
S.E.	SUPER-ELEVATION
B.P.	BEARING PAD
T	TOP
B	BOTTOM
B.F.	BOTH FACES
N.F.	NEAR FACE
F.F.	FAR FACE
E.G.L.	EXISTING GROUND LEVEL
AZL	AZIMUTH
VL	VARIABLE LENGTH
L.S.D	LAND SURVEY DATUM
E.J	EXPANSION JOINT
AS	ALTERNATELY STAGGERED

- 7 FULL COVER SHALL BE MAINTAINED AT GROOVES AND OTHER ARCHITECTURAL FINISHES TO THE CONCRETE SURFACE.
- 8 TYPE OF REINFORCEMENT IS DENOTED BY THE FOLLOWING SYMBOLS IN THE DRAWINGS : -
(i) R - PLAIN ROUND STEEL BAR.
(ii) T - DEFORMED HIGH YIELD STEEL BAR.
- 9 UNLESS OTHERWISE SHOWN ON DRAWINGS, THE SYSTEM OF BAR MARKING IS AS BELOW : -

— MILD STEEL	— HIGH TENSILE BAR
2 R16 - 101 - 150	2 T16 - 101 - 150



31 MAY 2018



SPACE RESERVED FOR RE CORP

MASTER COPY

CONTROLLED COPY

CONSTRUCTION DRAWING

R. SARUDIN bin Hujud, SLLM JABATAN REJENTERSEKUTU NO. 10, JALAN BUKIT MELAKA, 75000 MELAKA, NEGERI SEMBILAN.	R. OZUL SHAH BIN ALI BASHOH JABATAN REJENTERSEKUTU NO. 10, JALAN BUKIT MELAKA, 75000 MELAKA, NEGERI SEMBILAN.	CHE MAT HANI BIN MAT DAUD JABATAN REJENTERSEKUTU NO. 10, JALAN BUKIT MELAKA, 75000 MELAKA, NEGERI SEMBILAN.	TUAN HANI MOHAMMAD BIN SUPIP JABATAN REJENTERSEKUTU NO. 10, JALAN BUKIT MELAKA, 75000 MELAKA, NEGERI SEMBILAN.	DEWAN BANDARAYA KUALA LUMPUR CADANGAN REJENTERSEKUTU ANEKASAH KONGSER BERKUALITI KEPADA JABATAN REJENTERSEKUTU BARU MELAKA (SUNGAI SELANG, KEPAKA DI JALAN MELAKA, BUKIT MELAKA, NEGERI SEMBILAN). BERSEKUTU NO. 10, JALAN BUKIT MELAKA, 75000 MELAKA, NEGERI SEMBILAN.	04 APRIL 2018 No. Lisis. RB 6305/BR3/ST/01

- NOTES:**
1. ALL DIMENSIONS ARE IN MILLIMETRE UNLESS OTHERWISE STATED.
 2. ALL CHANGES, LEVELS AND BEAM LENGTH ARE IN METRE.
 3. FOR ESTIMATED PILE LENGTH REFER TO PILE SCHEDULE.
 4. ALL LEVELS AND POSITIONS FOR PILES AND GRIDS TO BE JOINTLY VERIFIED AT SITE.
 5. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS.
 6. PILE TEST :-
 - i) PRELIMINARY PILE TO BE TESTED TO 2.5 TIMES OF THE WORKING LOAD AS FOLLOWS :
 - 1 NO. UTILIZING MAINTAINED LOAD TEST.
 - ii) WORKING PILE TO BE TESTED TO 2 TIMES OF THE WORKING LOAD AS FOLLOWS :
 - 1 NO. UTILIZING MAINTAINED LOAD TEST.
 - 12 NOS. UTILIZING PAN WITH CAPING.
 7. PILE ALLOWABLE BEARING CAPACITY IS TO BE REASSESSED AFTER CONSTRUCTION OF PILES. DATA ARE TO BE SUBMITTED TO ENGINEER FOR FURTHER ACTION.
 8. FINAL PILE LENGTH IS TO BE RECOMMENDED BASED ON THE TEST RESULTS ASSESSMENT AND SPT 'N' VALUE ENCOUNTERED AT EACH PILE LOCATION.
 9. AS BUILT PILE POSITIONS BY LICENSED SURVEYOR TO BE SUBMITTED BEFORE COMMENCING PILE CAP WORKS.
 10. AS-BUILT PILE POSITIONS BY LICENSED SURVEYOR SHALL BE SUBMITTED BEFORE COMMENCING THE PILE CAP CONSTRUCTION.
 11. IF ROCKS ENCOUNTERED AT SHALLOW DEPTH DURING CONSTRUCTION, THE CONTRACTOR NEED TO INFORMED THE S.O REPRESENTATIVE AT SITE TO CONFIRM THE ROCK SOCKETING LENGTH BASED ON ROCK QUALITY AND ROCK TEST RESULT.
 12. IF LIMESTONE ROCK ENCOUNTERED PROBING OF MIN. 6m SHALL BE CARRIED OUT FROM THE INTERGED TOE LEVEL OF PILE.
 13. PRE-BORING CAVITY TREATMENT TE BE CARRIED OUT AT LIMESTONE ROCK.
 14. 12 NOS. PROFILING WITH STANDARD PENETRATION TEST (SPT) 'N' VALUE RECORDED AT EVERY 1.5m TO THE DEPTH 2 TIMES THE PILE DIAMETER FROM THE TOE OF THE PILE SHALL BE CARRIED PRIOR TO CONSTRUCTING OF BORED PILE.
 15. CORING INTO INCLINED ROCK SURFACE, LIMESTONE CRACKS, CAVITIES, SOIL BELOW BOLLDER FLASHER AND ROCK THAT NOT SATISFYING THE ROCK SOCKETING CRITERIA MENTIONED IN NOTES FOR ROCK SOCKETING SHALL BE CONSIDERED AS BARRID IN SOIL.

- NOTES FOR ROCK SOCKETING:-**
1. DETERMINATION OF ROCK CORING SHALL FULLFILL ALL THREE (3) CRITERIA BELOW :
 - CHANGE OF TOLLS TO ROCK CORING TOOLS AND CUT OFF POINT LOAD TEST
 - AT LEAST THREE (3) ROCK SAMPLES TO ACHIEVE MINIMUM INDEX STRNGTH OF 2.0 MPa SUBJECT TO SITE CONFORMATION OF TYPICAL ROCK LUMP SIZES BASE ON THE SIZE CORRECTION FACTOR.
 - RECORDED ROCK MATERIAL (RMR) OF MORE THAN 70% SUBJECT TO SITE CALIBRATION UPON START WORK UNLESS OTHERWISE AGREED BY THE ENGINEER.
 2. ANY OTHER MATERIAL THAT DO NOT FULLFILL THE CRITERIA OF THE ROCK CORING METHOD ABOVE SHALL BE CONSIDERED BORING IN SOIL.
 3. CORING INTO INCLINED ROCK SURFACE, LIMESTONE PINNACLES, CAVITIES AND SOIL BELOW BOLLDER/FLOASER SHALL BE CONSIDERED AS BORING IN SOIL.
 4. ROCK CORING LENGTH SHALL BE MEASURED FROM THE FLATTENED HORIZONTAL KELLY BAR OR STEEL BAR AT MINIMUM OF FIVE POSITION OVER THE BOREHOLE TO CONFIRM ROCK CORING DEFINITION.

- LEGEND**
- ⊕ - DENOTES 250mm DIA. MICROPIE.
- DRAWING REFERENCE**
1. RB6305/BR3/ST/32.
 2. RB6305/BR3/ST/00A AND RB6305/BR3/ST/00B
 3. PILE SCHEDULE FOR BRIDGE.

RECEIVED


15 MAR 2019

DEWAN BANDARAYA KUALA LUMPUR

CAJANGAN MENDAPATKAN JAWABAN KONKRIT SEDAJAD, KEPADA
 DR. HENY WENYEN, KURATOR, BUREAU PERENCANAAN SUNGAI RELANG,
 BERSEKUTUANG S.S. SELANG
 PLANG LAYOUT PLAN

ML. LUSONG RB 6305/BR3/ST/03

NOV. 01



<p>renhill consulting sdn. bhd. (Private)</p> <p>EN. S. VEYAPALAN EN. CHE MAT NAWI BIN MAT DAUD EN. S. VEYAPALAN EN. CHE MAT NAWI BIN MAT DAUD</p>	<p>IR. SABRUDIN BIN MORD, SALLEH EN. S. VEYAPALAN EN. CHE MAT NAWI BIN MAT DAUD</p>	<p>DEWAN BANDARAYA KUALA LUMPUR</p> <p>CAJANGAN MENDAPATKAN JAWABAN KONKRIT SEDAJAD, KEPADA DR. HENY WENYEN, KURATOR, BUREAU PERENCANAAN SUNGAI RELANG, BERSEKUTUANG S.S. SELANG PLANG LAYOUT PLAN</p>
<p>15/03/2019</p>	<p>01</p>	<p>15 MAR 2019</p>

CONTROLLED COPY

MASTER COPY

DRAWING REFERENCE

1. RB 6305/BR3/ST/03.
- PILING LAYOUT PLAN.
2. RB6305/BR3/ST/15.
- 250mm DIA. MICROPILES DETAILS.

PILE SCHEDULE FOR NEW BRIDGE

PILE ID.	PILE DIA.	PILE TYPE	WORKING LOAD ON SINGLE PILE	ESTIMATED PILE LENGTH BELOW CUT-OFF WITH ROCK SOCKET (m)	ROCK SOCKET LENGTH (m)
P1	250 mm	MICROPILE	900 kN	49.5	3.0
P2	250 mm	MICROPILE	900 kN	49.5	3.0
P3	250 mm	MICROPILE	900 kN	49.5	3.0
P4	250 mm	MICROPILE	900 kN	49.5	3.0
P5	250 mm	MICROPILE	900 kN	49.5	3.0
P6	250 mm	MICROPILE	900 kN	49.5	3.0
P7	250 mm	MICROPILE	900 kN	49.5	3.0
P8	250 mm	MICROPILE	900 kN	49.5	3.0
P9	250 mm	MICROPILE	900 kN	49.5	3.0
P10	250 mm	MICROPILE	900 kN	49.5	3.0
P11	250 mm	MICROPILE	900 kN	49.5	3.0
P12	250 mm	MICROPILE	900 kN	49.5	3.0
P13	250 mm	MICROPILE	900 kN	49.5	3.0
P13a	250 mm	MICROPILE	900 kN	49.5	3.0
P14	250 mm	MICROPILE	900 kN	49.5	3.0
P15	250 mm	MICROPILE	900 kN	49.5	3.0
P16	250 mm	MICROPILE	900 kN	49.5	3.0
P17	250 mm	MICROPILE	900 kN	49.5	3.0
P18	250 mm	MICROPILE	900 kN	49.5	3.0
P20	250 mm	MICROPILE	900 kN	49.5	3.0
P21	250 mm	MICROPILE	900 kN	49.5	3.0
P22	250 mm	MICROPILE	900 kN	49.5	3.0
P23	250 mm	MICROPILE	900 kN	49.5	3.0
P24	250 mm	MICROPILE	900 kN	49.5	3.0
P25	250 mm	MICROPILE	900 kN	49.5	3.0
P27	250 mm	MICROPILE	900 kN	49.5	3.0
P28	250 mm	MICROPILE	900 kN	49.5	3.0
P29	250 mm	MICROPILE	900 kN	49.5	3.0
P30	250 mm	MICROPILE	900 kN	49.5	3.0
P31	250 mm	MICROPILE	900 kN	49.5	3.0
P32	250 mm	MICROPILE	900 kN	49.5	3.0
P33	250 mm	MICROPILE	900 kN	49.5	3.0
P34	250 mm	MICROPILE	900 kN	49.5	3.0
P35	250 mm	MICROPILE	900 kN	49.5	3.0
P38	250 mm	MICROPILE	900 kN	49.5	3.0
P37	250 mm	MICROPILE	900 kN	49.5	3.0
P38	250 mm	MICROPILE	900 kN	49.5	3.0
P40	250 mm	MICROPILE	900 kN	49.5	3.0
P41	250 mm	MICROPILE	900 kN	49.5	3.0
P42	250 mm	MICROPILE	900 kN	49.5	3.0

PILE SCHEDULE FOR NEW BRIDGE

PILE ID.	PILE DIA.	PILE TYPE	WORKING LOAD ON SINGLE PILE	ESTIMATED PILE LENGTH BELOW CUT-OFF WITH ROCK SOCKET (m)	ROCK SOCKET LENGTH (m)
P43	250 mm	MICROPILE	900 kN	48.5	3.0
P44	250 mm	MICROPILE	900 kN	48.5	3.0
P45	250 mm	MICROPILE	900 kN	48.5	3.0
P46	250 mm	MICROPILE	900 kN	48.5	3.0
P47	250 mm	MICROPILE	900 kN	48.5	3.0
P48	250 mm	MICROPILE	900 kN	48.5	3.0
P49	250 mm	MICROPILE	900 kN	48.5	3.0
P50	250 mm	MICROPILE	900 kN	48.5	3.0
P51	250 mm	MICROPILE	900 kN	48.5	3.0
P52	250 mm	MICROPILE	900 kN	48.5	3.0
P53	250 mm	MICROPILE	900 kN	48.5	3.0
P54	250 mm	MICROPILE	900 kN	48.5	3.0
P55	250 mm	MICROPILE	900 kN	38.5	9.5
P56	250 mm	MICROPILE	900 kN	38.5	9.5
P57	250 mm	MICROPILE	900 kN	38.5	9.5
P58	250 mm	MICROPILE	900 kN	38.5	9.5
P59	250 mm	MICROPILE	900 kN	38.5	9.5
P60	250 mm	MICROPILE	900 kN	38.5	9.5
P61	250 mm	MICROPILE	900 kN	38.5	9.5
P62	250 mm	MICROPILE	900 kN	38.5	9.5
P63	250 mm	MICROPILE	900 kN	38.5	9.5
P64	250 mm	MICROPILE	900 kN	38.5	9.5
P65	250 mm	MICROPILE	900 kN	38.5	9.5
P66	250 mm	MICROPILE	900 kN	38.5	9.5
P67	250 mm	MICROPILE	900 kN	33.0	6.0
P68	250 mm	MICROPILE	900 kN	33.0	6.0
P70	250 mm	MICROPILE	900 kN	33.0	6.0
P71	250 mm	MICROPILE	900 kN	33.0	6.0
P72	250 mm	MICROPILE	900 kN	30.5	8.0
P73	250 mm	MICROPILE	900 kN	30.5	8.0
P74	250 mm	MICROPILE	900 kN	30.5	8.0
P75	250 mm	MICROPILE	900 kN	30.5	8.0
P76	250 mm	MICROPILE	900 kN	30.5	8.0
P77	250 mm	MICROPILE	900 kN	28.0	8.0
P78	250 mm	MICROPILE	900 kN	28.0	8.0
P79	250 mm	MICROPILE	900 kN	28.0	8.0
P80	250 mm	MICROPILE	900 kN	28.0	8.0
P81	250 mm	MICROPILE	900 kN	28.0	8.0
P82	250 mm	MICROPILE	900 kN	26.0	7.5
P83	250 mm	MICROPILE	900 kN	26.0	7.5
P84	250 mm	MICROPILE	900 kN	26.0	7.5

15 MAR 2019

CONSTRUCTION DRAWING

SKALA: 1:1000
 TITIK: 1000
 15 MAR 2019

ranhill consulting
 sdn. bhd. (130889-A)
 100, JALAN SRI PERAK, 47100 PANGKALAN, SELATAN KEPULAUAN MELAYU, NEGARA MALAYSIA

IR. SARIENI BIN MOHD. RAJAH
 JAWATAN: ENJINER UTAMA
 EN. S. JEFERAN
 JAWATAN: ENJINER UTAMA
 EN. CHE MAT NAWI BIN MAT DAUD
 JAWATAN: ENJINER UTAMA

DESKRIpsi: 1. BANGUNAN
 2. BANGUNAN
 3. BANGUNAN

NO. SKALA: 1:1000
 NO. TITIK: 1000

NO. RUMAH: 1000
 NO. RUMAH: 1000

NO. RUMAH: 1000
 NO. RUMAH: 1000

DEWAN BANDARAYA KUALA LUMPUR
 JAWATAN: ENJINER UTAMA
 EN. S. JEFERAN
 JAWATAN: ENJINER UTAMA
 EN. CHE MAT NAWI BIN MAT DAUD
 JAWATAN: ENJINER UTAMA

DEWAN BANDARAYA KUALA LUMPUR
 JAWATAN: ENJINER UTAMA
 EN. S. JEFERAN
 JAWATAN: ENJINER UTAMA
 EN. CHE MAT NAWI BIN MAT DAUD
 JAWATAN: ENJINER UTAMA

DEWAN BANDARAYA KUALA LUMPUR
 JAWATAN: ENJINER UTAMA
 EN. S. JEFERAN
 JAWATAN: ENJINER UTAMA
 EN. CHE MAT NAWI BIN MAT DAUD
 JAWATAN: ENJINER UTAMA

DEWAN BANDARAYA KUALA LUMPUR
 JAWATAN: ENJINER UTAMA
 EN. S. JEFERAN
 JAWATAN: ENJINER UTAMA
 EN. CHE MAT NAWI BIN MAT DAUD
 JAWATAN: ENJINER UTAMA

DEWAN BANDARAYA KUALA LUMPUR
 JAWATAN: ENJINER UTAMA
 EN. S. JEFERAN
 JAWATAN: ENJINER UTAMA
 EN. CHE MAT NAWI BIN MAT DAUD
 JAWATAN: ENJINER UTAMA


DEWAN BANDARAYA KUALA LUMPUR
 JAWATAN: ENJINER UTAMA
 EN. S. JEFERAN
 JAWATAN: ENJINER UTAMA
 EN. CHE MAT NAWI BIN MAT DAUD
 JAWATAN: ENJINER UTAMA

DEWAN BANDARAYA KUALA LUMPUR
 JAWATAN: ENJINER UTAMA
 EN. S. JEFERAN
 JAWATAN: ENJINER UTAMA
 EN. CHE MAT NAWI BIN MAT DAUD
 JAWATAN: ENJINER UTAMA

DEWAN BANDARAYA KUALA LUMPUR
 JAWATAN: ENJINER UTAMA
 EN. S. JEFERAN
 JAWATAN: ENJINER UTAMA
 EN. CHE MAT NAWI BIN MAT DAUD
 JAWATAN: ENJINER UTAMA







DEWAN BANDARAYA KUALA LUMPUR
 JAWATAN: ENJINER UTAMA
 EN. S. JEFERAN
 JAWATAN: ENJINER UTAMA
 EN. CHE MAT NAWI BIN MAT DAUD
 JAWATAN: ENJINER UTAMA







ADDITIONAL REINFORCEMENT AT DETAILS OF STREET LIGHTING POST SUPPORT
SCALE 1:10

NOTES:
1) UPVC CABLE DUCT FOR BRIDGE PARAPET SHALL BE CONFORMED ACCORDING TO THE RELEVANT BRIDGE SECTIONS DETAIL.







BASE PLATE FOR HANDRAIL
SCALE 1 : 5




BASE PLATE FOR SHELTER WALKWAY
SCALE 1 : 5




HANDRAIL POST
SCALE 1 : 10



ELEVATION OF HANDRAIL
SCALE 1 : 15



DETAIL OF SHELTER FOR WALKWAY
SCALE 1 : 25



TYPICAL CHANNEL PROTECTION
SCALE 1 : 50

31 MAY 2018

SPACE RESERVED FOR P.C. MARK



MASTER COPY

CONTROLLED COPY

CONSTRUCTION DRAWING

rahil consulting
SHEK BUNYI
SHEK BUNYI
SHEK BUNYI
SHEK BUNYI
ANN

DR. SAIBUN BIN MOHD. SALLEH
MR. AZLI SHAH BIN ALI BASHAH
CHE. MAT HARI BIN MAT DAUD
ANN

WAN HAJI AH HANID BIN SIRIP
ANN

DEWAN BANDARAYA KUALA LUMPUR
JALAN SRI MURNI
KUALA LUMPUR

REVISION TABLE

NO.	DATE	DESCRIPTION
1	APRIL 2018	ISSUE FOR PERMIT TO CONSTRUCT
2	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
3	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
4	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
5	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
6	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
7	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
8	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
9	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
10	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
11	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
12	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
13	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
14	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
15	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
16	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
17	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
18	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
19	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
20	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
21	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
22	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
23	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
24	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
25	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
26	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
27	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
28	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
29	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
30	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
31	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
32	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
33	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
34	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
35	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
36	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
37	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
38	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
39	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
40	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
41	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
42	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
43	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
44	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
45	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
46	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
47	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
48	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
49	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
50	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
51	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
52	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
53	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
54	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
55	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
56	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
57	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
58	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
59	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
60	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
61	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
62	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
63	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
64	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
65	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
66	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
67	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
68	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
69	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
70	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
71	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
72	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
73	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
74	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
75	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
76	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
77	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
78	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
79	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
80	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
81	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
82	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
83	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
84	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
85	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
86	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
87	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
88	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
89	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
90	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
91	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
92	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
93	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
94	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
95	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
96	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
97	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
98	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
99	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT
100	MAY 2018	ISSUE FOR PERMIT TO CONSTRUCT

RECEIVED
 CONTROLLED COPY
 MASTER COPY





- GENERAL NOTES:**
- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS. DISCREPANCIES IF ANY SHALL BE RESOLVED PRIOR TO THEIR EXECUTION.
 - ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE STATED.
 - ALL LEVELS AND ELEVATIONS SHALL BE JOINTLY CONFIRMED AT SITE PRIOR TO COMMENCEMENT OF THE WORKS.
 - CONSTRUCTION SHALL COMPLY FOLLOWING CODES OF PRACTICE :
 - FOUNDATION - BS 8004
 - STRUCTURAL - BS 5400
 - REINFORCEMENT - BS 4449
 - IN THE EVENT OF A DISCREPANCY BETWEEN THE NOTES OF THIS DRAWING AND NOTES IN OTHER RELEVANT DRAWINGS, THE CONTRACTOR SHALL VERIFY AND CONFIRM WITH THE S.O SUCH DISCREPANCY.
 - ALL LEVEL TO BE JOINTLY CONFIRMED AT SITE BEFORE COMMENCEMENT OF WORK.

NOTES FOR MICROPILES:

- API STEEL PIPE SHALL BE 177.8mm O.D. t = 9.19mm
 $\rho = 592 \text{ N/mm}^2$ (441 N60)
 $\rho_{\text{allow}} = 30 \text{ N/mm}^2$ (28 DAYS)
- IN CASE OF DIFFICULTY IN OBTAINING API PIPE ABOVE CONTRACTOR MAY SUBMIT ALTERNATIVE PROPOSAL FOR ENGINEER'S REVIEW.
- BEFORE COMMENCEMENT OF WORK CONTRACTOR SHALL SUBMIT COMPLETE METHOD STATEMENT FOR ENGINEER APPROVAL.
- TEMPORARY CASING SHALL BE USED TO MAINTAIN STABILITY OF BORERHOLE IF NECESSARY.
- WHERE PERMANENT CASING ARE REQUIRED, THE CONTRACTOR NEED TO INFORM THE S.O REPRESENTATIVE AT SITE FOR APPROVAL.
- PILE CUT-OFF LEVEL SHALL BE DECIDED ON SITE.
- VERTICAL TOLERANCE OF THE PILE SHALL BE 1 : 75 WHILE POSITIONAL TOLERANCE ON PLAN SHALL BE 75mm.

DRAWING REFERENCE


- RB 6302/RB3/ST/03.
 - PILING LAYOUT PLAN.
- RB 6303/RB3/ST/03A.
 - PILE SCHEDULE FOR NEW BRIDGE (ABUTMENT A)
- RB 6305/RB3/ST/03B.
 - PILE SCHEDULE FOR NEW BRIDGE (ABUTMENT B)



15 MAR 2019

CONSTRUCTION DRAWING

TARIKH 15/03/2019	BUKALAH 01	RUMAH 01	RUMAH 01	RUMAH 01
REVISI REVISI AS PER CLOUDED	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01	RUMAH 01
RUMAH 01	RUMAH 01			



PILE SCHEDULE FOR RC WALL FOUNDATION

INDEX	PILE DIA.	PILE TYPE	WORKING LOAD ON SINGLE PILE	PILE NOS.	ESTIMATED PILE LENGTH BELOW CUT-OFF WITH ROCK SOCKET (m)	ROCK SOCKET LENGTH (m)
P1	250 mm	MICRO PILE	400 kN	10	18.0	-
P2	250 mm	MICRO PILE	400 kN	14	16.0	-
P3	250 mm	MICRO PILE	400 kN	8	34.5	1.5
P4	250 mm	MICRO PILE	400 kN	4	22.0	-
P2	250 mm	MICRO PILE	400 kN	4	34.5	1.5
ADDITIONAL PILE (X)	250 mm	MICRO PILE	400 kN	4	45.0	-

PILE SCHEDULE FOR STEEL TRUSS FOUNDATION

INDEX	PILE DIA.	PILE TYPE	WORKING LOAD ON SINGLE PILE	PILE NOS.	ESTIMATED PILE LENGTH BELOW CUT-OFF WITH ROCK SOCKET (m)	ROCK SOCKET LENGTH (m)
P1	250 mm	MICRO PILE	400 kN	10	18.0	-
P2	250 mm	MICRO PILE	400 kN	14	16.0	-
P3	250 mm	MICRO PILE	400 kN	8	34.5	1.5
P4	250 mm	MICRO PILE	400 kN	4	22.0	-
P2	250 mm	MICRO PILE	400 kN	4	34.5	1.5
ADDITIONAL PILE (X)	250 mm	MICRO PILE	400 kN	4	45.0	-

- NOTES:**
- ALL DIMENSIONS ARE IN MILLIMETRE UNLESS OTHERWISE STATED.
 - ALL CHANGES, LEVELS AND BEAM LENGTH ARE IN METRE.
 - FOR ESTIMATED PILE LENGTH REFER TO PILE SCHEDULE.
 - ALL LEVELS AND POSITIONS FOR PILES AND ORDERS TO BE JOINTLY VERIFIED AT SITE.
 - THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS.
 - PILE TEST :-
 (1) WORKING PILE TO BE TESTED TO 2 TIMES OF THE WORKING LOAD AS FOLLOWS :
 - 2 NOS. UTILIZING STATWANG LOAD TEST FOR STEEL TRUSS PILE
 - 4 NOS. UTILIZING PDA TEST WITH CAPWAP FOR STEEL TRUSS PILE
 - 1 NOS. UTILIZING PDA TEST WITH CAPWAP FOR RC WALL PILE
 - PILE ALLOWABLE BEARING CAPACITY IS TO BE REASSESSED AFTER THE RESULTS OF THE TESTS ARE OBTAINED AND ARE TO BE SUBMITTED TO ENGINEER FOR FURTHER ACTION.
 - FINAL PILE LENGTH IS TO BE DETERMINED BASED ON THE TEST PILE RESULTS ASSESSMENT AND SPT 'N' VALUE ENCOUNTERED AT EACH PILE LOCATION.
 - AS BUILT PILE POSITIONS BY LICENSED SURVEYOR TO BE SUBMITTED BEFORE COMMENCING PILE CAP WORKS.
 - NOTES FOR ROCK SOCKETINGS:
 a. DEFINITION OF ROCK CORING SHALL FULFILL ALL THREE (3) CRITERIA BELOW :
 - CHANGE OF TOOLS TO ROCK CORING TOOLS AND
 - THE AT LEAST THREE (3) TOOLS SHALL BE SUBMITTED BY CHANGING OUT POINT LOAD TEST TOOLS TO THE ENGINEER FOR VERIFICATION OF THE CORING TOOLS.
 b. CORING SHALL BE SUBJECT TO SITE CONSERVATION OF TYPICAL ROCK LUMP SIZES BASED ON THE SIZE CORRECTION FACTOR, $F = (0.6/50)$ AND WHERE OF IS 50% OF THE CORING TOOLS.
 c. RECOVERED ROCK MATERIAL OF MORE THAN 20% SUBJECT TO ITS CALIBRATION UPON START WORK UNLESS OTHERWISE AGREED BY THE ENGINEER.
 d. ANY OTHER MATERIAL THAT DO NOT FULFILL THE DEFINITION OF THE ROCK CORING SHALL BE CONSIDERED BORING IN SOIL.
 e. CORING LOGS SHALL BE SUBMITTED TO THE ENGINEER FOR VERIFICATION OF THE CORING LOGS.
 f. ROCK CORING LENGTH SHALL BE MEASURED FROM THE FLATTENED HORIZONTAL BENCH MARK SURFACE. THIS PLAN HORIZONTAL SURFACE SHALL BE PROVIDED USING TO CONFIRM ROCK CORING DEFINITION.

⊕ -- DENOTES 250mm DIA. MICROPILE.

CONSTRUCTION DRAWING

15 MAR 2019

RECEIVED






DIA. ZUBAIR BIN ABDULLAH BIN MOHD. SALLEH
 EN. SURETAPALAN
 EN. CHE MAT MAWI BIN MAT DAUD

DEWAN BANDARAYA KUALA LUMPUR
 CADANGAN MENGGANTIKAN JAMBATAN KONKRIT SEDIAADA KEPADA
 JAMBATAN BERTINGKAT SEMENTIANG SUNGAI KELANG,
 DI JALAN KELANG, KUALA LUMPUR
 TRAK LUBANG
 STEEL TRUSS - PILING LAYOUT PLAN
 TAHUN: APRIL 2018
 NO. LUKAS: RB 6305/BR3/ST/18
 RY. 03

ronhill consulting
 EN. SURETAPALAN
 EN. CHE MAT MAWI BIN MAT DAUD

TARIKH	REVISI	REVISI AS SHOWN
24-08-18	01	REVISI AS SHOWN
26-12-18	02	REVISI AS SHOWN
15-03-19	03	REVISI AS SHOWN

DESKRIPSI: RUMAH
 NO. LUKAS: RB 6305/BR3/ST/18
 RY. 03



RECEIVED
CONTROLLED COPY
MASTER COPY

SPACE RESERVED FOR PE CHECK

27 DEC 2018



CONSTRUCTION DRAWING

DEWAN BANDARAYA KUALA LUMPUR
CAANGAN MENSANTAN JAMBATAN KONKRIT SEDAJA KEPADA
DI JALAN NEJATEK KUALA LUMPUR
TRAKS LUBAN
BRIDGE OVER S6 JELANG
STEEL TRUSS - DIMENSION & REINFORCEMENT DETAIL (PIER 3)

TAMBAH	REVISI	REVISI	REVISI	NO. RUMAH	SKALA	REVISION	REVISION	REVISION
24-09-18	REVISED AS SHOWN			01				
01-11-18	REVISED AS SHOWN			02				
28-12-18	REVISED AS SHOWN			03				

IR. SABUDIN BIN MOHD. SALLEH JAMBATAN KERTASABANG KUALA LUMPUR	EN. SUEYAPALAN TUMBUK PERUMAH ATAM JAMBATAN KERTASABANG KUALA LUMPUR	EN. CHE MAT HAWI BIN MAT DAUD JAMBATAN KERTASABANG KUALA LUMPUR	EN. HAZWAN MOHAMMAD JAMBATAN KERTASABANG KUALA LUMPUR
TUAN HAJI ABD. HANID BIN SURIP PERUMAH PERUMAHAN PERUMAHAN BANGAR JAMBATAN KERTASABANG KUALA LUMPUR			

2018	2018	2018	2018
2018	2018	2018	2018
2018	2018	2018	2018
2018	2018	2018	2018



RECEIVED

CONTROLLED COPY

TRUSS SIZE (mm)	SPAN (m)	UTILITIES	HEIGHT (m)
2000	20 AND 50	TIE, DRG AND FIBERGLASS	5

SHAKE ASSUMED FOR FE CHOP




6. WELDING ELECTRODES E7018 (LOW HYDROGEN TYPE) MUST BE USED.
7. SURFACE PREPARATION OF ALL STRUCTURAL STEEL MEMBERS SHALL BE BY BLAST-CLEANING BEFORE APPLICATION OF PAINT. BLAST-CLEANING PROCESSES SHALL MEET SURFACE CLEANLINESS OF GRADE Sa 2.5 OF ISO 8501-1:1989.
8. THE PAINTING SHALL CONFORM TO THE FOLLOWING SCHEDULE:
 - 1.4. COAT - ZINC RICH EPoxy PRIMER (NOT LESS THAN 50 MICRONS DFT)
 - 1.5. COAT - POLYURETHANE FINISH
 - 1.6. COAT - POLYURETHANE FINISH
 - 1.7. COAT - POLYURETHANE FINISH
9. CONTRACTOR TO CONFIRM AND SUBMIT TO ENGINEER AS BUILT DIMENSION OF FILE CAP PRIOR TO FABRICATION OF TRUSSES.
10. APPLY PREZAMBER OF 30mm AT JOINTS.

DEWAN BANDARAYA KUALA LUMPUR
KORRET SEMADAM NEPAD
KUALA LUMPUR

CONSTRUCTION DRAWING

DATE: APRIL 2019
BY: LWIN RB 6305/BRC/ST/22A

REVISION AS SHOWN



- NOTES**
1. FABRICATION & SECTION OF STRUCTURAL STEEL SHALL CONFORM WITH THE PROVISIONS OF BRSSMA. CONTRACTOR SHALL SUBMIT TO ENGINEER FOR APPROVAL A DETAILED METHOD STATEMENT OF ERECTION OF THIS STRUCTURE TOGETHER WITH ALL NECESSARY SAFETY MEASURES TO BE ENFORCED BY A REGISTERED PROFESSIONAL ENGINEER BEFORE PROCEEDING WITH ACTUAL ERECTION WORK.
 2. THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH OTHER RELEVANT ARCHITECTURAL, STRUCTURAL AND MECHANICAL DRAWINGS AND SPECIFICATIONS.
 3. ALL THE STRUCTURAL STEEL (ROLLED SECTIONS, PLATES, ANGLES) SHALL BE OF GRADE A36.
 4. FOR BOLTS USE B.S. GRADE 4.6 UNLESS OTHERWISE STATED (DIAMETER OF HOLES TO BE BOLTS DIAMETER +2mm).
 5. ONE SET OF APPROPRIATE HUT & WASHER SHALL BE USED WITH EVERY BOLT.

- LEGEND:**
- 1. H.S.F.C. - DENOTES HIGH STRENGTH FRICTION CHIP BOLT
 - 2. H.S. - DENOTES HIGH STRENGTH BOLT (GRADE 8.8)
 - 3. FC - DENOTES FIXED CONNECTION
 - 4. SC - DENOTES SLIDING CONNECTION

SECTION MARK	SECTION SIZE IN mm
A	152 x 152 x 30 kg/m UC
B	120 x 120 x 12 THK. ANGLE
C	152 x 89 x 16 kg/m UB
D	100 x 100 x 10 THK. ANGLE
E	203 x 203 x 66 kg/m UC
F	203 x 203 x 53 kg/m UC

REVISION NO.	REVISION	DATE
01		
02		

NO.	REVISION	DATE
15-0-18		
18-04-19		

NO.	REVISION	DATE
15-0-18		
18-04-19		