



اُنِيُوْرَسِيْتِي تِي كُونُوْلُو كِي مَارَا  
UNIVERSITI  
TEKNOLOGI  
MARA

**DEPARTMENT OF BUILDING**

**FACULTY OF ARCHITECTURE, PLANNING AND SURVEYING**

**UNIVERSITI TEKNOLOGI MARA**

**(PERAK)**

**OCTOBER 2012**

It is recommended that this practical report which is prepared

**By**

**Ahmad Shahreezdakuan bin Said**

**2010856772**

**entitled**

**Construction of Retaining Rubble Wall**

Is accepted to fulfill part of the stipulation for achieving Diploma in Building.

Report supervisor

Dr. Siti Akhtar binti Mahayuddin.

Prac. Training Coordinator

En. Noor Azam bin Yahaya.

En. Zulkifli bin Abdul Halim.

Head of Programme

Dr. Hayroman bin Ahmad.

## **ABSTRACT**

Generally, this practical training report clarify information about all of the works, processes and methods to construct a retaining rubble wall. This practical training report is prepared based on the study, observation and experience gained throughout 5 months of practical training on site project construction. This report contains of several parts which explain different types of information or details. This practical training report is started with explanation and clarification of company background and background of project. The construction of retaining rubble wall is not an easy or simple type of construction. This is because of, based on the observation made, the construction of retaining rubble wall involving a heavy and sticky type of construction method and also involving many parties. Besides that, the quantity and quality of the general workers and the machineries would also affect the fluency level of the construction. Also explained in this practical training report, the characteristics and advantages or the specialties of the retaining rubble wall compared to other type of retaining walls. Next, this report also explained about the materials used for the retaining rubble wall construction and the equipment used by the general workers. Moreover, the safety features of the construction site and suitable type of personel protective equipment should be worn by the general worker when constructing the retaining rubble wall which are prepared by the contractor. The method statement of retaining rubble wall construction with the problem and solution are also explained in this report. As the conclusion, this practical training report can explain in details about the construction of retaining rubble wall practically to all of the readers.

## ACKNOWLEDGEMENT

Alhamdulillah, a full gratitude to Allah S.W.T. whom with His permission and bless, I have been given the opportunities and occasion to complete the Practical Training Report perfectly right on the time. First and foremost, I would like to dedicate my millions of thanks for those who had sacrifice and spending much time to advice, guiding, cooperation and reprimand me in finishing this practical training report especially to Mr. Wong Siew Yu as the Project Manager of Mainstay Development Sendirian Berhad and Encik Abdul Rahim bin Ismail as the Project Coordinator of Mainstay Development Sendirian Berhad. Special thanks to Puan Siti Khadijah binti Abdul Khadir as the clerk of work from Senie Associates Sendirian Berhad and officers from Pembinaan Tetap Teguh Sendirian Berhad as the contractor company for the guidance and help. Thousands of thanks also dedicated to Dr. Siti Akhtar binti Mahayuddin as my supervising lecturer, Encik Noor Azam bin Yahaya and Encik Zulkifli bin Abdul Halim as the practical training coordinator and Dr. Hayroman bin Ahmad as the program coordinator. Not to forget, thank you to all of the lecturers of Building Department, my parents and supportive family for their non-stoppable support on financial, suggestion and encouragement in preparing this practical training report. May Allah bless their help, contribution and sacrifice.

Thank you.

<b>CONTENT</b>			<b>PAGE</b>
ACKNOWLEDGEMENT			i
ASBTRACT			ii
TABLE OF CONTENT			iii
LIST OF TABLES			v
LIST OF FIGURES			vi
LIST OF PHOTOS			vii
LIST OF ABBREVIATIONS			xi
CHAPTER	1.0	INTRODUCTION	1
	1.1	INTRODUCTION	1
	1.2	THE STUDY BACKGROUND	3
	1.3	OBJECTIVES OF STUDY	4
	1.4	SCOPE OF STUDY	5
	1.5	METHOD OF STUDY	6
CHAPTER	2.0	COMPANY BACKGROUND	8
	2.1	INTRODUCTION	8
	2.2	COMPANY PROFILE	10
	2.3	OBJECTIVES OF COMPANY	12
	2.4	ORGANIZATION CHART	14
	2.5	LIST OF PROJECTS	15
	2.5.1	PREVIOUS PROJECT	15
	2.5.2	CURRENT PROJECT	16
	2.5.3	UPCOMING PROJECT	17
CHAPTER	3.0	CASE STUDY: CONSTRUCTION OF RETAINING RUBBLE WALL AT ‘MSTAY SR HILL VILLA’, DENGKIL, SEPANG, SELANGOR.	18
	3.1	INTRODUCTION	18
	3.2	FEATURES OF RETAINING RUBBLE WALL	21
	3.3	DESIGN OF RETAINING RUBBLE WALL	24



# CHAPTER 1

## INTRODUCTION

### 1.1 INTRODUCTION

The construction project of 20 unit house or in other word, residential centre which include 19 unit double storey bungalows type A and a single unit of double storey bungalow type B is a construction project which developed by the developer company, Mainstay Development Sendirian Berhad (private limited). This construction project is the second project that developed and conducted by Mainstay Development Sendirian Berhad after the completion of its first project, a shopping complex or business centre of Space U8 Eco-Mall which situated at Bukit Jelutong, Seksyen U8, Shah Alam, Selangor Darul Ehsan on year 2011. 'Mstay SR Hill Villa', name given to the project for the reasons of the name of developer company (Mainstay Development Sendirian Berhad) and the owner of the project (SEKATA Rakyat Berhad @ Koperasi Kakitangan Bank Kerjasama Rakyat). And the coordination or the location of the project is situated on hilly area with magnificent view.

The construction project cost about RM12,236,616.24 contains 20 units of bungalow house with 2 different design. Located at Mukim Dengkil, Daerah Sepang which strategically located because the location of the project is nearby to several main cities such as Nilai, Federal Territory of Putrajaya, Bandar Baru Salak Tinggi and also nearby to many of point of interest such as Sepang International Circuit (SIC) and Kuala Lumpur International Airport (KLIA). Therefore, the development of Mukim Dengkil must be collateral with the development and advancement of those nearby main cities and able to accommodate rising capacity of population rate by year to year. With this Mstay SR Hill Villa construction project could fulfill the