



**DEPARTMENT OF BUILDING
UNIVERSITI TEKNOLOGI MARA
(PERAK)**

**INSTALLATION OF FLOOR AND WALL FINISHES FOR
BATHROOM AT APPLE 99 HOTEL**

**Prepared by:
SITI NOOR AIDA BINTI SAMSURI
2016458618**

ACKNOWLEDGEMENT

Bismillahirrahmannirrahim.

Alhamdulillah, praise to Allah, the Most Merciful, the Most Graceful.

I would like to extend my heartfelt gratitude for the guidance, advice and help rendered throughout the period of training by the following group of amazing individuals. First and foremost, I would like to thank Mr. Kenny Low and Mr. Lim Cher Seong as a site manager from Kerjaya Prospek (M) Sdn.Bhd for the opportunity given, to conduct my training in his esteem company. His team of professionals comprising of Miss Mardiana, Miss Nurul Faeda, Pn Murni Azmera and En Muhammad Hafiz as a site engineers, have enabled me to learn and develop my understanding, knowledge and feel of real time projects, and the theory involved in analysis of structures, building and civil works. Besides, I would like to thank En. Muhammad Izzuddin as a site supervisor, because spending his time to guide and share the knowledge about construction field along the days of practical training.

I would also like to thank all the UiTM lecturers that have taught and nurtured me in becoming a better student and person. I would also like to extend my deepest appreciation to the lecturers who are directly involved during my training stint. To Miss Nor Azizah Binti Talkis, Supervising Lecturer, En Muhammad Naim Bin Mahyuddin, Practical Training Coordinator and Dr. Dzulkarnaen Bin Ismail, Programme Coordinator, I value the time, effort, encouragement and ideas that they have contributed towards the successful completion of my training, this report and the valuable knowledge that have been shared over the last few semesters.

Last but not least, my special thanks to my beloved parents for their sacrifices over the years to complete this practical training report. Thank you for being a part of my spirit booster. I would have never been as positive to finish this report if it were not from their advices and guidance.

Thank you so much.

ABSTRACT

Floor and wall finishes in construction is one of the important thing to elaborate. Therefore, this report will discuss about the requirement that client wants in wall and floor finishes for bathroom at hotel Apple 99, Melaka. The example of finishing materials in modern construction are marble, ceramic or porcelain. The objective of this project is to demonstrate the installation of floor and wall finishes that using one of the finishing material which is ceramic or porcelain. Porcelain tiles are in vogue especially in modern houses and available in various colors and combinations. Furthermore, this report also will describe the method of inspection that contractor do after the installation and identify the problem and the solution of the installation. Observing the installation process of tiles are very helpful because the problem can detect and also can monitor the requirement that client wants directly. As a conclusion, finishes used to improve and decorative qualities of building and structures, as well as to protect structural members from external factors.

CONTENTS	PAGE NO.
Acknowledgements	i
Abstract	ii
Contents	iii-iv
List of Tables	v-vi
List of Figures	vii-viii
CHAPTER 1.0 INTRODUCTION	1-6
1.1 Background and Scope of Study	1-2
1.2 Aim	3
1.3 Objectives	3
1.4 Methods of Study	3-6
CHAPTER 2.0 COMPANY BACKGROUND	7-14
2.1 Introduction of Company	7
2.2 Company Profile	8-10
2.2.1 Company Vision	10
2.2.2 Company Mission	10
2.3 Organization Chart	11
2.4 List of Project	12-14
2.4.1 Completed Projects	12-13
2.4.2 Project in Progress	14

CHAPTER 3.0 CASE STUDY (BASED ON TOPIC OF THE REPORT)	15-46
3.1 Introduction to Case Study	15-19
3.2 Method Statement Installation of Floor Finishes for Bathroom Hotel Apple 99, Melaka	20
3.2.1 Explanation of Floor Finishes Installation	21-25
3.2.2 Explanation of Wall Finishes Installation	26-28
3.3 Method Statement Form for Installation of Floor Finishes Bathroom Hotel Apple 99, Melaka	29-34
3.4 Method Statement Form for Installation of Wall Finishes Bathroom Hotel Apple 99, Melaka	35-38
3.5 The Problem and The Solution of the Installation Floor and Wall Tile at Bathroom Hotel Apple 99, Melaka	39-43
3.6 Method of Inspection After the Installation of Floor and Wall Tiles	44-46
3.6.1 Water Flow Inspection Before Start The Installation of Wall Tiles	44
3.6.2 Inspection with Client Representative	45-46
 CHAPTER 4.0 CONCLUSION	 47
4.1 Conclusion	47
 REFERENCES	 48-49
 APPENDIX	 50